

P.O. Box 21017 1601 Lewis Avenue Building Billings, Montana 59104 (406) 259-7860



SEP 1 7 1992

DIVISION OF OIL GAS & MINING

September 16, 1992

-- VIA FEDERAL EXPRESS --

State of Utah Division of Oil, Gas & Mining 355 West North Temple Salt Lake City, UT 84180

Gentlemen:

RE: Applications for Permit to Drill

Enclosed are copies of the Federal Applications for Permit to Drill the seven wells on the attached list. Also attached is a copy of the water permit and one copy of the Archeology Survey which are referenced in the APDs.

Every effort to comply with statewide spacing was made when staking these seven wells. However, in many instances both topographical reasons and requests by the Bureau of Land Management necessitated moving some of the sites from the location which was originally intended. If there is anything else we need to do in order to ensure that these locations are acceptable according to State regulations, please let me know.

Approximate starting dates have been put on the APDs. However, the order of drilling may change depending on when the permits are approved.

As operator we hereby request that the information on these wells be held tight for the maximum period allowed by State regulations.

If you have any questions or need further information, please let me know.

Sincerely,

Bobbie Schuman

Coordinator of Operations,

Environmental and Regulatory Affairs

/rs
Enclosures/Attachments

Form 3160-3 ~(November 1983)

Drilling Program/Casing Diagram

Evidence of Bond Coverage

"D"

"E"

SUBMIT IN TRIPLICATE. HIMITED CTATES reverse side)

Form approved. Budget Bureau No. 1004-0136 Expires August 31

(Other instructions on

(formerly 9-331C)		LD SIAILS		•		01, 1900
,	DEPARTMENT	1	5. LEASE DESIGNATION	AND SERIAL NO.		
	BUREAU OF		U-096550			
A DDL ICATIO	N FOR PERMIT T	O DRILL DEF	PEN, OR PLUG E	RACK	6. IF INDIAN, ALLOTTEE	OR TRIBE NAME
	IN TOR PERIORIT I	,, (CI	n/a			
1a. TYPE OF WORK	ILL 🖾	DEEPEN	PLUG BA	CK 🗆	7. UNIT AGREEMENT N.	AMB
b. TYPE OF WELL					n/a	
OIL X	AS OTHER		SINGLE MULTIP	'LE 🗌	8. FARM OR LEASE NAM	
2. NAME OF OPERATOR			החתכותבת	ותודר	Balcron Monum	ent Federal
EOUITABLE RES	SOURCES ENERGY C	IIIIL	9. WELL NO.			
3. ADDRESS OF OPERATOR	300.1000 1111110		#23-11	•		
P.O. Box 2101	17; Billings, MT Report location clearly and	59104			10. FIELD AND POOL, O	R WILDCAT
4. LOCATION OF WELL (B	leport location clearly and	in accordance with an	y State requirements.*)		Monument Butte	e/Green Rive
At surface 1787' FSL,	2147' FWL NE	SW			11. SEC., T., R., M., OR E AND SURVEY OR AR	LK.
At proposed prod. zo					·	
					NE SW Sec. 11	•
	AND DIRECTION FROM NEAR				12. COUNTY OR PARISH	l .
Approximate	ly 16 miles from	n Myton, UT.	See EXHIBIT "B"		Duchesne	UTAH
15. DISTANCE FROM PROP LOCATION TO NEARES		16.	NO. OF ACRES IN LEASE		OF ACRES ASSIGNED HIS WELL	
PROPERTY OR LEASE (Also to nearest dr)	LINE, FT.		40 acres		40	
18. DISTANCE FROM PRO	POSED LOCATION®	19.	PROPOSED DEPTH	20. ROTA	RY OR CABLE TOOLS	
OR APPLIED FOR, ON TH	DRILLING, COMPLETED, HIS LEASE, FT.		5,750'	R	Rotary	
21. ELEVATIONS (Show wh	ether DF, RT, GR, etc.)		,		22. APPROX. DATE WO	
GI 5,622'			:		November 15,	1992
23.		PROPOSED CASING A	ND CEMENTING PROGR	AM		
SIZE OF HOLE	BIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH		QUANTITY OF CEMEN	T
12-1/4"	8-5/8"	24# 260' 2		250 s	SX G. W.38-QaOTAV/ICTA	
See attached	Drilling Progra	n for product	production casing.		THEODILL	
					1.3	
EXHIBITS		l	I	1	SEP 171	992
	d Drilling Progr	am "(G" Rig Layout		921 17	·
	d Surface Use Pr	ogram "l	U" DODE Schomati	C	DUNOMAL	∩ E
	c Prognosis		I" Location Site	and E	levati DIV SION	UF NING
		- • •		1 /07	OULCAC AAA	Mana n \

Drillsite Layout/Cut and Fill Diagrams "F" Archeology Report In accordance with request by the Vernal BLM representative, only one copy of EXHIBIT "F" Archeology Report is included with this permit.

"J"

Existing Roads/Planned Auc CAS (MANINIA) B)

Existing Wells (Map C)

SELF CERTIFICATION: I hereby certify that I am authorized, by proper lease interest owner, to conduct these operations associated with the application. Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Equitable Resources Energy Company as principal and Safeco Insurance Company of America as surety under BLM Bond No. MT 0576 (Nationwide Oil & Gas Bond #5547188) who will be responsible for compliance with all of the terms and conditions of that portion of the lease associated with this application.

IN ABOVE SPACE DESCRIBE PROFOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout

Coordinator of Environmental TITLE and Regulatory Affairs DATE 9-15-92
APPROVED BY THE STATE APPROVAL DATE OF LITAH DIVISION OF
OIL, GAS, AND MINING
BY: SPACING: 649-3-Z

T9S, R16E, S.L.B. & M. S 89°56' W (GLO) 0°01' W (GLO) 0,01, BALCRON MONUMENT FED #23-11 ELEV UNGRADED GROUND 5622.01 2147.13 BEARING 1787.60 ᆼ BASIS

S 89°59' W (GLO)

X = SECTION CORNERS LOCATED

BASIS OF BEARINGS; G.L.O. PLAT 1911

BASIS OF ELEV; U.S.C.S. 7-1/2 min QUAD (MYTON SOUTHEAST)

EQUITABLE RESOURCES ENERGY CO.

WELL LOCATION, BALCRON MONUMENT FED #23-11, LOCATED AS SHOWN IN THE NE 1/4 SW 1/4 OF SECTION 11, T9S, R16E, S.L.B. & M, DUCHESNE COUNTY UTAH.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTEGOTION TUAL SURVEYS MADE BY ME OR UNDER SUAMOSTAL, AND THAT THE SAME ARE TRUE OF CORRECT TO THE BEST OF MY KNOWLEDGE AND STAFF.

REGISTREM AND SURVEYOR REGISTRATION No. 3154

TRI STATE LAND SURVEYING & CONSULTING 38 EAST 100 NORTH, VERNAL, UTAH 84078 (801) 781-2501

SCALE:	1" = 1000'	SURVEYED BY: SS KH
DATE:	7/28/92	WEATHER: CLEAR & HOT
NOTES:		FILE # #M-23-11

EXHIBIT "A"
Proposed Drilling Program
Page 1

EQUITABLE RESOURCES ENERGY COMPANY
Balcron Oil Division
Balcron Monument Federal #23-11
NW SW Section 11-T9S-R16E
Duchesne County, Utah

In accordance with requirements outlined in 43 CFR 3162-3.1 (d):

1. ESTIMATED IMPORTANT GEOLOGICAL MARKERS:

See Geologic Prognosis (EXHIBIT "C")

2. ESTIMATED DEPTHS OF ANTICIPATED OIL, GAS OR WATER:

See Geologic Prognosis (EXHIBIT "C)

- 3. OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:
 - a. EXHIBIT "H" is a schematic of the BOP equipment and choke manifold. A 2M system will be used. The BOPE will be installed after setting 8-5/8" casing at 260'. The blind rams and pipe rams will be tested to 1500 psi. Pipe rams will be operationally checked each 24-hour period and blind rams each time pipe is pulled out of the hole.
 - b. The BOPE will be tested to 1500 psi when initially installed, whenever any seal subject to test pressure is broken, and following related repairs. The pipe and blind rams will be activated at least weekly and on every trip the pipe and blind rams will be activated.
 - c. An accumulator of sufficient capacity to open the hydraulically-controlled choke valve lines (if so equipped), close all rams, and retain a minimum of 200 psi above precharge on the closing manifold without the use of the closing unit pumps will be installed during the drilling of this well.
 - d. An upper kelly cock will be used during the drilling of this well.
 - e. Visual mud monitoring equipment will be used to detect volume changes indicating loss or gain in circulating fluid volume.
 - f. Sufficient quantities of mud materials will be maintained or readily accessible for the purpose of assuring well control.

EXHIBIT "A"
Proposed Drilling Program
Page 2

4. PROPOSED CASING AND CEMENTING PROGRAM:

- a. Surface casing will be set in the Duchesne River formation to approximately 260' and cemented to surface.
- b. All potentially productive hydrocarbon zones will be isolated.
- c. Casing designs are based on factors of burst: 1.25, collapse: 1.125, and joint strength: 1.8.
- d. All casing strings will be pressure tested to 0.22 psi/ft. of casing string length or 1500 psi whichever is greater (not to exceed 70% of yield).
- E. For details of casing, cement program, drilling fluid program, and proposed mud program, see the following two attachments:

Drilling Program/Casing Design (EXHIBIT "D")
Geologic Prognosis (EXHIBIT "C")

5. HAZARDOUS PRESSURES, TEMPERATURES, FLUIDS/GASSES EXPECTED:

- a. Expected bottom hole temperature is 125 degrees F. Expected bottom hole pressure is 1500 psi.
- b. No abnormal pressures or temperatures have been noted or reported in wells drilled to the Green River formation in this area.
- c. No dangerous levels of hydrogen sulfide, hazardous fluids, or gasses have been found, reported, or known to exist at the depth to be drilled in this well, in this area.

6. ANTICIPATED STARTING DATE AND DURATION OF OPERATIONS:

- a. The drilling operations for this well will begin as soon as the BLM approves this APD.
- b. These drilling operations should be completed within 12 days after spudding the well depending on weather and hole conditions.
- c. If the well is productive, a sundry notice and plat showing exact installed facilities will be submitted.
- d. If this well is non-productive, a sundry notice will be filed with the BLM District Office within 30 days following completion of the well for abandonment.

Multi-Point Surface Use and Operations Plan

EQUITABLE RESOURCES ENERGY COMPANY
BALCRON OIL DIVISION
BALCRON MONUMENT FEDERAL #23-11
NE SW Section 11, T9S, R16E
DUCHESNE COUNTY, UTAH

1. Existing Roads: Refer to Maps "A" & "B" (shown in RED)

- A. The proposed well site is staked and four reference stakes are present. 200'& 250' NE and 175' & 225' NW
- B. The Monument Federal #23-11 is located approximately 16.6 miles Southwesterly of Myton Utah, in the NE1/4 SW1/4 Section 11, T9S, R16E, SLB&M, Duchesne County, Utah. To reach the 23-11, proceed West from Myton, Utah along U.S. Highway 40 for 1.6 miles to the junction of this highway and Sand Wash road; Proceed South along the Sand Wash road approximately 9.3 miles to an intersection with Monument Butte Gas Plant road Proceed West along said Gas Plant road 3.0 miles to road intersection, turn left and continue 1.9 miles, turn left and proceed 0.6 miles to Balcron well #23-11 access road. Follow flags 150' to location.
- C. Access roads refer to Maps "A" and "B".
- D. Access roads within a one-mile radius refer to map "B".
- E. The existing roads will be maintained in the same or better condition as existed prior to the commencement of operations and said maintenance will continue until final abandonment and reclamation of the well location.

2. Planned Access Roads: Refer to Map "B" (shown in GREEN)

Approximately 150 feet of new road construction will be required for access to the proposed well location. A BLM right-of-way is hereby applied for a portion of the access.

A. Width - maximum 30-foot overall right-of-way with an 18foot road running surface, crowned & ditched and/or sloped and dipped. B. Construction standard - the access road will be constructed so as to conform to the standards outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development. (1989)

The road will be constructed to meet the standards of the anticipated traffic flow and all-weather requirements. Construction will include ditching, draining, crowning, and capping or sloping and dipping the roadbed as necessary to provide a well constructed and safe road. Prior to construction/upgrading, the roadway shall be cleared of any snow cover and allowed to dry completely. Traveling off of the thirty (30) foot right-of-way will not be allowed.

Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossing shall be designed so they will not cause siltation or the accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts.

Upgrading shall not be allowed during muddy conditions.

Should mud holes develop, they shall be filled in and detours around them avoided.

- C. Maximum grade 4%
- D. Turnouts no turnouts will be required on this access road.
- E. Drainage design None required.
- F. Culverts, cuts and fills no culverts will be required.
 There are no major cuts and/or fills on/along the proposed access road route.
- G. Surface materials any construction materials which may be required for surfacing of the access road will be purchased from a local contractor having a permitted source of materials in the area, if required by the Authorized Officer, Bureau of Land Management. None anticipated at this time.
- H. Gates, cattleguards or fence cuts none required.
- I. Road maintenance during both the drilling and production phase of operations, the road surface and

shoulders will be kept in a safe and useable condition and will be maintained in accordance with the original construction standards. All drainage ditches and culverts will be kept clear and free-flowing, and will also be maintained in accordance with the original construction standards. The access road right-of-way will be kept free of trash during operations.

- J. The proposed access road has been centerline flagged.
- 3. Location of Existing Wells Within a One-Mile Radius:

Please Refer to Map "C"

- A. Water wells none known.
- B. Abandoned wells see Map "C"
- C. Temporarily abandoned wells none known.
- D. Disposal wells none known.
- E. Drilling wells none known.
- F. Producing wells see Map "C".
- G. Shut-in wells none known.
- H. Injection wells none known.
- I. Monitoring wells none known.
- 4. Location of Existing and/or Proposed Facilities Owned by Equitable Resources Energy Company Within a One-Mile Radius:
 - A. Existing
 - 1. Tank batteries see Map #B.
 - 2. Production facilities see Map #B.
 - 3. Oil gathering lines none.
 - 4. Gas gathering lines see Map #B.
 - B. New Facilities Contemplated
 - 1. All production facilities will be located on the disturbed portion of the well pad and at a minimum of twenty-five (25) feet from the toe of the backslope or toe of the fill slope.
 - 2. The production facilities will consist primarily of a pumping unit, Two tanks and an emergency pit. A diagram showing the proposed production facility layout will be submitted to the Authorized Officer via "Sundry Notice" (Form 3160-5) for approval of subsequent installation operations.
 - 3. Production facilities will be accommodated on the existing well pad. Construction materials required for installation of the production facilities will be

obtained from the site; any additional materials required will be purchased from a local supplier having a permitted (private) source of materials within the area.

A dike will be constructed completely around those production facilities which contain fluids (i.e. production tanks, produced water tanks and/or heater treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

- 4. All permanent (onsite for six months or longer) above the ground structures constructed or installed including pumping units) will be painted Desert Brown. All production facilities will be painted within six (6) months of installation. Facilities required to comply with Occupational Health and Safety Act Rules and Regulations will be excluded from this painting requirement.
- C. The production (emergency) pit will be 12'x12' and will be fenced. Said fence will be maintained in good condition.
- D. During drilling and subsequent operations, all equipment and vehicles will be confined to the access road right-of-way and any additional areas as specified in the approved Application for Permit to Drill.
- E. Reclamation of disturbed areas no longer needed for operation will accomplished by grading, leveling and seeding as recommended by the Bureau of Land Management.

For Pipeline:

- F. Any proposed pipelines will be submitted to the authorized officer Via Sundry Notice for approval of subsequent operations.
- G. Equitable Resources Energy Company shall be responsible for road maintenance from the beginning to completion of operations.

5. Location and Type of Water Supply

A. Water to be used for the drilling of these wells will be hauled by truck over the roads described in item #1 and item #2, from a well owned by Owen Dale Anderson of Vernal

Utah.

B. No water well will be drilled on this location.

6. Source of Construction Materials

- A. No construction materials are needed for drilling operations. In the event of production, the small amount of gravel needed for facilities will be hauled in by truck from a local gravel pit over existing access roads to the area. No special access other than for drilling operations and pipeline construction is needed.
- B. All access roads crossing Federal land are described under item #2, and shown on Map #A.

All construction material for these location sites and access roads shall be borrowed material accumulated during the construction of the location sites and access roads. No additional construction material from other sources is anticipated at this time, if in the future it is required the appropriate actions will be taken to acquire it from private sources.

- C. All surface disturbance area is on B.L.M. lands.
- D. There are no trees on this location.

7. Methods of Handling Waste Materials:

- A. Cuttings the cuttings will be deposited in the reserve pit.
- B. Drilling fluids including salts and chemicals will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within ninety (90) days after termination of drilling and completion activities.

In the event adverse weather conditions prevent removal of the fluids from the reserve pit within this time period, an extension may be granted by the Authorized Officer upon receipt of a written request from Equitable Resources Energy Company.

The reserve pit will be constructed so as not to leak, break, or allow discharge. If at the time of construction it is determined to be necessary, the reserve pit will be lined with a plastic nylon reinforced liner.

C. Produced fluids - liquid hydrocarbons produced during completion operations will be placed in test tanks on the location. Produced waste water will be confined to a lined pit (reserve pit) or storage tank for a period not to exceed ninety (90) days after initial production. During the ninety (90) day period, in accordance with NTL-2B, an application for approval of a permanent disposal method and location, along with the required water analysis, shall be submitted for the Authorized Officer's approval. Failure to file an application within the time frame allowed will be considered an incidence of noncompliance.

Any spills of oil, gas, salt water or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

- D. Sewage self-contained, chemical toilets will be provided for human waste disposal. Upon completion of operations, or as needed, the toilet holding tanks will be pumped and the contents thereof disposed of in the nearest, approved, sewage disposal facility.
- E. Garbage and other waste material garbage, trash and other waste materials will be collected in a portable, self-contained and fully-enclosed trash cage during drilling and completion operations. Upon completion of operations (or as needed) the accumulated trash will be disposed of at an authorized sanitary landfill. No trash will be burned on location or placed in the reserve pit.
- F. Immediately after removal of the drilling rig, all debris and other waste materials not contained in the trash cage will be cleaned up and removed from the well location. No adverse materials will be left on the location. Any open pits will be fenced during the drilling operation and the fencing will be maintained until such time as the pits are backfilled.
- G. The reserve and/or production pit will be constructed on the existing location and will not be located in natural drainages where a flood hazard exists or surface runoff will destroy or damage the pit walls. All pits will be constructed so as not to leak, break, or allow the discharge of liquids therefrom.

8. Ancillary Facilities:

None anticipated.

9. Wellsite Layout:

- A. Plat #1 shows the drill site layout as staked. Cross sections have been drafted to visualize the planned cuts and fills across the location. An average minimum of six (6) inches of topsoil will be stripped from the location (including areas of cut, fill, and/or subsoil storage) and stockpiled for future reclamation of the well site. Refer to Figure #1 for the location of the topsoil and subsoil stockpiles. The reserve pit will be located on the Southeast side, and the flare pit will be downwind of the prevailing wind direction on the Northwest. Access to the well pad will be from the West near corner #7.
- B. Plat #2 is a diagram showing the rig layout. No permanent living facilities are planned. There will be three (3) trailers on location during drilling operation.
- C. A diagram showing the proposed production facility layout will be submitted to the Authorized Officer via Sundry Notice (Form 3160-5) for approval of subsequent operations.
- D. The reserve pit will be constructed so as to be capable of holding 12,000 bbls. of fluid. The flare pit will be located downwind of the prevailing wind on the East side of location between corner #5 and corner #6, at least 100' from the wellhead and at least 30' from the reserve pit. This pit might be used for testing, but only after the drilling is completed and the drilling equipment and personnel are off the well site location.

The reserve pit will not be lined unless requested by the B.L.M. or unless it is deemed necessary by Equitable. Resources. If a plastic-nylon reinforced liner is used, it will be torn and perforated after the pit dries and before backfilling of the reserve pit.

- E. Prior to the commencement of drilling operations, the reserve pit will be fenced on three (3) sides using 39-inch net wire with one strand of barbed wire on top of the net wire. The net wire will be no more than two inches above the ground. the barbed wire will be three inches above the net wire. total height of the fence will be at least 42-inches.
 - Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
 - 2. Standard steel, wood, or pipe posts shall be used between the corner braces. The maximum distance between any two (2) posts shall be no greater than

sixteen (16) feet.

3. All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The fourth side of the reserve pit will be fenced immediately upon removal of the drilling rig and the fencing will be maintained until the pit is backfilled.

F. Any hydrocarbons on the pit will be removed from the it as soon as possible after drilling operations are completed.

10. Plans for Reclamation of the Surface:

The B.L.M. will be contacted prior to commencement of any reclamation operations.

A. Production

- Immediately upon well completion, the well location and surrounding area(s) will be cleared of all debris, materials, trash and junk not required for production.
- 2. Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with 43 CFR 3162.7-1.
- 3. If a plastic or nylon reinforced pit liner is used, it shall be torn and perforated before backfilling of the reserve pit.
- 4. Before any dirt work to restore the location takes place, the reserve pit will be completely dry and all cans, barrels, pipe, etc. will be removed.

Other waste and spoil materials will be disposed of immediately upon completion of drilling and workover activities.

- 5. The reserve pit and that portion of the location and access road not needed for production facilities/operations will be reclaimed within one hundred twenty (120) days from the date of well completion, weather permitting.
- 6. If the well is a producer, Equitable Resources Energy Company will upgrade and maintain access roads as necessary to prevent soil erosion, and accommodate year round traffic. Reshape areas unnecessary to operations, distribute topsoil, disk and seed all

disturbed areas outside the work area according to the recommended seed mixture. Perennial vegetation must be established. Additional work shall be required in case of seeding failures, etc.

If the well is abandoned/dry hole, Equitable Resources Energy Company will, restore the access road and location to approximately the original contours. During reclamation of the site, push the fill material into cuts and up over the backslope. Leave no depressions that will trap water or form ponds. Distribute topsoil evenly over the location, and seed according to the above seed mixture. The access road and location shall be ripped or dished prior to seeding. Perennial vegetation must be established. Additional work shall be required in case of seeding failures, etc.

Seeded will be prepared by dishing, then roller packing following the natural contours. Seed will be drilled on contours at a depth no greater than one-half inch (1/2"). In areas that cannot be drilled, seed will be broadcast at double the seeding rate and harrowed into soil. Certified seed will be used whenever available.

Fall seeding will be completed after September 1 and prior to prolonged ground frost. Spring seeding, to be effective, will be completed after the frost has left the ground and prior to May 15th.

7. Upon completion of backfilling, leveling and recontouring, the stockpiled topsoil will be evenly spread over the reclaimed area(s). Prior to reseeding, all disturbed surfaces will be scarified and left with a rough surface. No depressions will be left that would trap water and form ponds. All disturbed surfaces will be reseeded with the following seed mixture:

Pure Live Seed	(PLS)	
lbs./acre	` '	Seed Mix
1		Forage Kochia (Kochia prostrata)
5		Ephriam Crested Wheatgrass
•		(Agropyron cristatum Ephriam)
4	3.	Russian Wildrye (Elymus junceus)
2 .		Fourwing Saltbush
	i.	(Atriplex canescens)

Seed will be drilled on the contour to a approximate depth of one-half (1/2) inch. All seeding will be conducted after September 1 and prior to ground frost.

Spring seeding will be done after the frost leaves the ground and no later than May 15. If the seeding is unsuccessful, Equitable Resources may be required to make subsequent seedings.

B. Dry Hole/Abandoned Location

- 1. On lands administered by the Bureau of Land Management, abandoned well sites, roads, or other disturbed areas will be restored to near their original condition. This procedure will include:
 - (a) re-establishing irrigation systems where applicable,
 - (b) re-establishing soil conditions in irrigated fields in such a way as to ensure cultivation and harvesting of crops and,
 - (c) ensuring revegetation of the disturbed areas to the specifications of the Bureau of Land Management at the time of abandonment.
- 2. All disturbed surfaces will be recontoured to the approximate natural contours and reseeded according to BLM specifications. Reclamation of the well pad and access road will be performed as soon as practical after final abandonment and reseeding operations will be performed in the fall or spring following completion of reclamation operations.
 - (a) A silt catchment basin of approximately 1/2 acre foot capacity will be constructed according to BLM specifications approximately 300' West of corner #1, where flagged.

11. Surface Ownership:

The well site and proposed access road are situated on surface lands administered by

Bureau of Land Management Vernal District Office Vernal, Utah

12. Other Information:

A. Topographic and geologic features of the area (reference Topographic Map #A) are:

The proposed drill site is located in the Monument Butte

oil field, which lies in a large basin formed by the Uinta Mountains to the North and the Bookcliff Mountains to the South. The site is located approximately 15 miles Northwest of the Green River, which is the major drainage for this area, and approximately 11 miles South of Myton Utah.

This basin floor is interlaced with numerous canyons and ridges formed by the non-perennial streams of the area. The sides of these canyons are steep and ledges formed in sandstone, conglomerate deposits and shale are common in this area.

The geologic structures that are visible in the area are of the Uinta formation (Eocene Epoch) tertiary period and the cobblestone and younger alluvial deposits from the Quaternary period.

The soils in the semi-arid area of the Williams Fork Formation (Upper Cretaceous) and Wasatch Formation (Eocene) consist of light brownish gray clay (OL) to sand soil (SM-ML) type with poorly graded gravels.

Outcrops of sandstone ledges, conglomerate deposits and shale are common in this area.

The topsoils in the area range from a sandy clay (SM-ML) type soil to a clayey (OL) soil.

The majority of the numerous washes and draws in the area are of a non-perennial nature flowing during the early spring run-off and heavy rain storms of long duration which are rare as the normal annual rainfall in the area is only 8".

The flora of the area includes sagebrush, mountain mahogany, serviceberry, rabbit brush, greasewood, fourwing saltbush, Gambel scrub oak, willow, tamarack, shadscale, Spanish bayonet, indian rice grass, cheatgrass, wheatgrass, curly grass, crested wheatgrass, sweet clover, gum weed, foxtail, mustard, Canadian thistle, Russian thistle, Kochia, sunflowers and cacti.

The fauna of the area includes cattle, horses, elk, deer, coyotes, rabbits, rodents, lizards, bull snakes, rattle snakes, water snakes and horned toads. Birds of the area are ground sparrows, bluejays, bluebirds, magpies, ravens, rapters, morning doves, swallows, nighthawks, hummingbirds, and chukar.

B. The surface ownership is Federal. The surface use is

grazing and petroleum production.

- C. 1. The closest live water is the Green River which is approximately 15 miles Southwest of the proposed site.
 - 2. There are no occupied dwellings in the immediate area
 - 3. An archaeological report will be forwarded upon completion.
 - 4. There are no reported restrictions or reservations noted on the oil and gas lease.

13. Lessee's or Operator's Representative:

Balcron Oil
a division of Equitable Resources Energy Company
1601 Lewis Avenue
P.O. Box 21017
Billings, Montana 59104
(8:00 a.m. to 5:00 p.m.)
(406)259-7860
FAX: (406)245-1361

Dave McCoskery, Drilling Engineer Home (406)248-3864 Mike Perius, Operations Supervisor Home (406)656-9719

14. certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which presently exist; that any statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Balcron Oil, a division of Equitable Resources Energy Company, and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

September 15, 1992

Date

Bobbie Schuman
Coordinator of Enviromental
and Regulatory Affairs
BALCRON OIL division of
Equitable Resources Energy
Company

Bobbie Schuman

. EXPLORATORY_

BALCRON OIL COMPANY

				-	-			DEVEL	ראשווים	X
WELL MAME:_	Balcron Monum	<u>ent Feder</u>	al_#23-	1.1	PROSPECT/F	IELD:	Monumen	t_Butte	20000	
LOCATION:	1787 FSL, 214 Duchesne	Z_FWL			SECTION		_100008814	95	DECT	LOE_
יאטטט: -	Duchesne	STATE:	<u>n</u> I	er (nuð)	: <u>5044</u>	F21 VR	: _ 2630	ińi¥r	DELIM	2/20
FORM. TOPS:	•	•					•			*
	Prognosis Depth Datum	Sumple	Top.	Criti WI	•	61.0	gnosis	elque3.	Top	Cnli
Formalion	Depth Datum	Depth.	Datum	Daium	Formation	Depth	Datum	Depth	Datum	Dat
K8 -									:	
ichesne	Surf. 1491 1479 h 2212 3418									
reen River	1491 '-14/9			-4139						
orseshoe Benc ouglas Creek	n 2212 3418			<u>3444</u> _						
ouglas Creek	4680 950 4692 938			962						
2V 2	4870760			784					~~~~.	
av 3	5162 468			492	~~~~~~					
satch_Tongue	554585			NDE_						
D	:_5.750									
		W								
CONTROL MEL	L: Goa <u>tes_Fed.</u>		alr/ali	·NW/SW	_Section	- <u>1</u> 1	_Township	_95	Range	16E
							-			
SVHEFES:					LDGS:					
SÁHPLÉS:	· samples.		· lo		Logs: DIL-SFL		_ from S	urface	la	TD
,	samples, samples, samples, samples,		' lo		_LDI=CNL		_ (rom S	surtace	' lo	ĪŪ
'	samples,		1 6				_		10	
	สวพปากส '		' to				", lion		1 10	
	anwiler'		' lo				- lion		' lo 'lo:	
Cond Samula	a To:						-		, (o	
Utah Geologi	cal Survey Samp	le Librar	y				_ from		, 10	
						•				
០ ព្រះ៥៩ ៖	•				DRILL STEH	TESTS				
	3 of may not been one and may been been been been been				none					
									4,	
									•	
						·				
										•
•		,						_		
HUG LOGGER/		Yes		-	WELLSITE G		ST:	•		
Required:	(Yes/No) 2 man unit				Name:			 Tala II:	, ,	
Type: _					Address:			1416, 11.	`	
COMMENTS:				•	,					
Control of										
						~~~~~			, 	
					~~~~~~~					
m 4.14 11 3 5.14 11		anDald-de-				•		010 00		
_ - ๒แต่มพบติด ถ,		anDelinde:					DATE:	<u>8-10-92</u>		

BALCRON OIL DRILLING PROGRAM

WELL NAME: Balcron Monument

PROSPECT/FIELD: Monument Butte

Federal # 23-11

LOCATION: NE SW Sec 11 Twn 9S Rge 16E

COUNTY: Duchesne

STATE: Utah

TOTAL DEPTH: 5750'

HOLE SIZE

INTERVAL

12 1/4" Surf to 260' 7 7/8" 260' to 5750'

CASING	INTERVAL	CASING

STRING TYPE	FROM	то	SIZE	WEIGHT	GRADE
Surface	0′	260 ′	8 5/8"	24 #/FT	J-55
Production	0′	5750 ′	5 1/2"	15.50#/Ft	J-55
	All ca	sing wil	l be ST&C,	8RD, New	

CEMENT PROGRAM

Surface 250 sacks class "G" with 3% CaCl.

(Note: Volumes are 100% excess.)

Production

250 sacks Haliburton Hifill with 10 #/SK Gilsonite tailed with 180 sacks 50/50 Poz with 0.3% CFR-3, 1/4 #/Sk Flocele, 0.5% Halad-24, and 10% salt.

(Note: Actual volumes will be calculated from

caliper log.)

PRELIMINARY DRILLING FLUID PROGRAM

TYPE	FROM	TO	WEIGHT	PLAS. VIS	YIELD POINT	
Fresh Gel/Native Mud Water/Fresh Gel		260 5750 ′	8.5 8.7-8.9	NA 10-12	NA 12-14	_

COMMENTS

1.) No cores or DSTs are planned .

DMM

9-9-92

BALCRON OIL CO.

Operator: BALCRON OIL	·	Well Name: MONUMENT BUTTE AREA
Project ID:	1	Location: Monument Butte, Utah

Design Parameters:	Design Factors:	
Mud weight (9.63 ppg) : 0.500 psi/ft	Collapse : 1.125	
Shut in surface pressure : 2280 psi	Burst : 1.00	
Internal gradient (burst) : 0.100 psi/ft	8 Round : 1.80 (J)	
Annular gradient (burst) : 0.000 psi/ft	Buttress : 1.60 (J)	
Tensile load is determined using air weight	Body Yield : 1.50 (B)	
Service rating is "Sweet"	Overpuli : O lbs.	•

	Length (feet)	Size (in.)	Weight (lb/ft)	Grade	Join		epth feet)	Drift (in.)	Cost
1	SFC ŢO TD	5-1/2"	15.50	J-55	ST&C		APD SHEET	4.825	
	Load (psi)	Collapse Strgth (psi)	S.F.	Burst Load (psi)	Min Int Strgth (psi)	Yield S.F.	Load (kips)	Tension Strgth (kips)	S.F.
1	2850	4040	1.418	2850	4810	1.69	88.35	5 202	2.29 J

Prepared by :

McCoskery, Billings, MT

Date

11-30-1992 (Revised 8/30/93)

Remarks

The mud gradient and bottom hole pressures (for burst) are 0.500 psi/ft and 2,850 psi, respectively.

The design factors used in this casing string design are as shown above. As a general guide-NOTE: line, Lone Star Steel recommends using minimum design factors of 1.125 - Collapse (with evacuated casing), 1.0 - Burst, 1.8 - 8 Round Tension, 1.6 - Buttress Tension, and 1.5 - Body Yield. Collapse strength under axial tension was calculated based on the Westcott, Dunlop and Kemler curve. Engineering responsibility for use of this design will be that of the purchaser. Costs for this design are based on a 1990 pricing model. (Version 1.0G)

BALCRON OIL CO.

Operator: BALCRON OIL	Well Name: Monument Fed. 23-11
Project ID: 1	Location: Utah

Design Parameters:	Design Factors:	
Mud weight (8.80 ppg) : 0.457 psi/ft	Collapse : 1.125	
Shut in surface pressure : 2054 psi	Burst : 1.00	
Internal gradient (burst) : 0.100 psi/ft	8 Round : 1.80	(1)
Annular gradient (burst) : 0.000 psi/ft	Buttress : 1.60	(1)
Tensile load is determined using air weight	Body Yield : 1.50	(B)
Service rating is "Sweet"	Overpull : 0	ibs.

	Length (feet)	Size (in.)	Weight (lb/ft)	Grade	e Join		Depth (feet)	Drift (in.)	Cost
1	5,750	5-1/2"	15.50	J-55	5 ST&C		5,750	4.825	
	Load (psi)	Collapse Strgth (psi)	s.F.	Burst Load (psi)	Min Int Strgth (psi)	Yield S.F.	Load	Tension Strgth (kips)	S.F.
1	2629	4040	1.537	2629	4810	1.83	89.13	202	2.27 J

Prepared by : McCoskery, Billings, MT

Date : 09-15-1992

Remarks


Minimum segment length for the 5,750 foot well is 1,500 feet.

The mud gradient and bottom hole pressures (for burst) are 0.457 psi/ft and 2,629 psi, respectively.

NOTE: The design factors used in this casing string design are as shown above. As a general guideline, Lone Star Steel recommends using minimum design factors of 1.125 - Collapse (with evacuated casing), 1.0 - Burst, 1.8 - 8 Round Tension, 1.6 - Buttress Tension, and 1.5 - Body Yield. Collapse strength under axial tension was calculated based on the Westcott, Dunlop and Kemler curve. Engineering responsibility for use of this design will be that of the purchaser. Costs for this design are based on a 1990 pricing model. (Version 1.0G)



United States Department of the Interior



BUREAU OF LAND MANAGEMENT MONTANA STATE OFFICE 222 NORTH 32ND STREET P.O. BOX 36800 BILLINGS, MONTANA 59107-6800

IN REPLY TO:

MTM 12619-A et al BLM BOND NO. MT0576 (922.31)

April 25, 1989

NOTICE

Equitable Resources Energy Company P. O. Box 21017

OIL AND GAS

Billings, Montana 59104

CORPORATE MERGER RECOGNIZED RIDER TO NATIONWIDE BOND ACCEPTED

Acceptable evidence has been filed in this office concerning the merger of Balcron Oil Company into Equitable Resources Energy Company, the surviving corporation. Information provided shows that Balcron Oil Company merged into Equitable Resources Energy Company, changing the former entity's name to Balcron Oil, a Division of Equitable Resources Energy Company. Please note that Divisions cannot hold leases, therefore, after consultation with Balcron Oil, this office is recognizing only the merger action.

A rider was filed on April 20, 1989, to be made a part of \$150,000 Nationwide Oil and Gas Bond No. 5547188 (BLM Bond No. MT0576) with Balcron Oil Company as principal and Safeco Insurance Company of America as surety. By means of this rider, the surety consents to changing the name on the bond from Balcron Oil Company to Equitable Resources Energy Company. The rider is accepted effective April 20, 1989.

For our purposes, the merger is recognized effective April 20, 1989.

The oil and gas lease files and communitization agreement files identified on the enclosed Exhibit A have been noted as to the merger. Other lease interests will be transferred by assignments from Ballard & Cronoble to Equitable Resources Energy Company.

Cynthia L. Embretson, Chief Fluids Adjudication Section

1 Enclosure 1-Exhibit Λ

cc: (w/encl.)

AFS, Denver (1)

All DMs (1 ea.)

RMO Section (1)

Regional Forester, Lakewood (2)

Regional Forester, Missoula (2)

Bureau of Reclamation (1)

Form 3104-8 (July 1984)

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

STATE, NATIONWIDE, OR NATIONAL PETROLEUM RESERVE IN ALASKA OIL AND GAS BOND

Act of February 25, 1920 (30 U.S.C. Sec. 181)
Act of August 7, 1947 (30 U.S.C. Sec. 351)

Department of the Interior Appropriations Act, Fiscal Year 1981 (P.L. 96-514)

Other Oil and Gas Leasing Authorities as Applicable

(M. laka mana)

Knor	WALL MEN BY THESE PRESENTS, That we BALCRON OIL COMPANY	•
of	1601 Lewis Avenue, Billings, MT 59104	
as proof	incipal, and SAFECO INSURANCE COMPANY OF AMERICA 111 Presidential Blvd., Suite 231, Bala Cynwyd, PA 19004	:_
of the ustatu statu lesse same	THOUSAND AND 00/100	nd, for has and any any and any
	The coverage of this bond shall extend to all of the principal's holdings of federal oil and gas leases in the United Sincluding Alaska, issued or acquired under the Acts cited in Schedule A.	tates
	The coverage of this bond extends only to the principal's holdings of federal oil and gas leases issued or acquired the Acts cited and in the States named in Schedule A and to any other State or States that may be named in a rider at hereto by the lessor with the consent of the surety.	
	The coverage of this bond extends only to the principal's holdings of federal oil and gas leases within the National leum Reserve in Alaska.	Petro

NAMES OF STATES

Mineral Leasing Act of February 25, 1920 (30 U.S.C. Sec. 181), Acquired Lands Leasing Act of August 7, 1947 (30 U.S.C. Sec. 351), and

ALL STATES

The conditions of the foregoing obligations are such that, whereas the said principal has an interest in oil and gas leases issued under the Acts cited in this bond: (1) as lessee; (2) as the approved holder of operating rights in all or part of the lands covered by such leases under operating agreements with the lessees; or (3) as designated operator or agent under such leases pending approval of an assignment or operating agreement; and

other oil and gas leasing authorities as applicable.

WHEREAS the principal is authorized to drill for, mine, ex-

tract, remove, and dispose of oil and gas deposits in or under the lands covered by the leases, operating agreements or designations and is obligated to comply with certain covenants and agreements set forth in such instruments; and

WHEREAS the principal and surety agree that without notice to the surety the coverage of this bond, in addition to the present holdings of the principal, shall extend to and include:

8.443 B12 10/88

SURETY RIDER

raye o UI 4

SAFECO INSURANCE COMPANY OF AMERICA GENERAL INSURANCE COMPANY OF AMERICA FIRST NATIONAL INSURANCE COMPANY OF AMERICA HOME OFFICE: SAFECO PLAZA SEATTLE, WASHINGTON 98185

To be attached to and i	
Type of Bond: .	Nationwide Oil and Gas Lease Bond
Bond No.	5547188 (BLM Bond No. MT0576)
dated effective	9/8/88
executed by .	(MONTH, DAY, YEAR) BALCRON OIL COMPANY, as Principa
and by .	(PRINCIPAL) SAFECO INSURANCE COMPANY OF AMERICA , as Surety
in favor of .	(SURETY) UNITED STATES DEPARTMENT OF THE INTERIOR, BUREAU OF LAND (OBLIGEE) MANAGEMENT
In consideration of the	mutual agreements herein contained the Principal and the Surety hereby consent to changing
. From: .	The name of the Principal BALCRON OIL COMPANY
	EQUITABLE RESOURCES ENERGY COMPANY
Nothing herein contain	ned shall vary, alter or extend any provision or condition of this bond except as herein expressly stated.
·This rider is effective	1/1/89 (MONTH, DAY, YEAR)
Signed and Sealed	4/10/89 (MONTH, DAY, YEAR) EQUITABLE RESOURCES ENERGY COMPANY
Ву:	TITLE
ву:`	SAFEO INSURANCE COMPANY OF AMERICA SURETY R. Coorge Voinghet Attorney-in-Fact






SAFECO INSURANCE COMPANY OF AMERICA GENERAL INSURANCE COMPANY OF AMERICA HOME OFFICE: SAFECO PLAZA SEATTLE, WASHINGTON 98185

EXHIBIT "E" 3798 Page 4 of 4

No
(NOW ALL BY THESE PRESENTS:
That SAFECO INSURANCE COMPANY OF AMERICA and GENERAL INSURANCE COMPANY OF AMERICA, each Washington corporation, does each hereby appoint
THOMAS L. VEHAR; R. GEORGE VOINCHET, Pittsburgh, Pennsylvania
ts true and lawful attorney(s)-in-fact, with full authority to execute on its behalf fidelity and surety bonds or undertakings and other documents of a similar character issued in the course of its business, and to bind the respective company thereby.
IN WITNESS WHEREOF, SAFECO INSURANCE COMPANY OF AMERICA and GENERAL INSURANCE COMPANY OF AMERICA have each executed and attested these presents
this 4th day of September , 19 87.
CERTIFICATE
- · · · · · · · · · · · · · · · · · · ·
Extract from the By-Laws of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA:
"Article V, Section 13. — FIDELITY AND SURETY BONDS the President, any Vice President, the Secretary, and any Assistant Vice President appointed for that purpose by the officer in charge of surety operations, shall each have authority to appoint individuals as attorneys-in-fact or under other appropriate titles with authority to execute on behalf of the company fidelity and surety bonds and other documents of similar character issued by the company in the course of its business On any instrument making or evidencing such appointment, the signatures may be affixed by facsimile. On any instrument conferring such authority or on any bond or undertaking of the company, the seal, or a facsimile thereof, may be impressed or affixed or in any other manner reproduced; provided, however, that the seal shall not be necessary to the validity of any such instrument or undertaking."
Extract from a Resolution of the Board of Directors of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA adopted July 28, 1970.
"On any certificate executed by the Secretary or an assistant secretary of the Company setting out, (i) The provisions of Article V, Section 13 of the By-Laws, and (ii) A copy of the power-of-attorney appointment, executed pursuant thereto, and (iii) Certifying that said power-of-attorney appointment is in full force and effect, the signature of the certifying officer may be by facsimile, and the seal of the Company may be a facsimile thereof."
I, Boh A. Dickey, Secretary of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA, do hereby certify that the foregoing extracts of the By-Laws and of a Resolution of the Board of Directors of these corporations, and of a Power of Attorney issued pursuant thereto, are true and correct, and that both the By-Laws, the Resolution and the Power of Attorney are still in full force and effect.
IN WITNESS WHEREOF, I have hereunto set my hand and affixed the facsimile seal of said corporation
this <u>l0th</u> day of <u>April</u> , 19 89.

EQUITABLE RESOURCES ENERGY CO.

WELLSITE LAYOUT



TRI-STATE
LAND SURVEYING. INC.
38 WEST 100 NORTH, VERNAL, UTAH 84078
801-781-2501








EXHIBIT "G"
Rig Layout





#3000 STACK__











SEP 1 7 1992

DIVISION OF OIL GAS & MINING

14 pages

CULTURAL RESOURCE EVALUATION OF SEVEN PROPOSED WELL LOCATIONS IN THE CASTLE PEAK DRAW LOCALITY OF DUCHESNE COUNTY, UTAH

Report Prepared for BALCRON OIL COMPANY

Dept. of Interior Permit No.: UT-92-54937 AERC Project 1348 (BLCR-92-5)

Utah State Project No.: UT-92-AF-498b

Principal Investigator & Author of Report F. Richard Hauck, Ph.D.



ARCHEOLOGICAL-ENVIRONMENTAL RESEARCH CORPORATION (AERC)

181 North 200 West, Suite 5 P.O. Box 853 Bountiful, Utah 84011-0853

September 8, 1992

ABSTRACT

Intensive cultural resource evaluations have been conducted for Balcron Oil Company of seven proposed well locations on federal lands in the Castle Peak Draw locality of Duchesne County, Utah. These seven locations involved a total of 66 acres of which 6 acres (.5 mile) includes two access routes associated with Units 24-5 and 23-15. The remaining 60 acres involves ten acre parcels at six of the proposed Units (24-5, 14-11, 23-11, 23-15, 32-15, and 41-15). Unit 13-5 was not examined since it had been previously evaluated by AERC (Hauck 1981). These evaluations were conducted by F. Richard Hauck on September 3, 1992.

No previously recorded significant or National Register eligible cultural resources will be adversely affected by the proposed developments.

No diagnostic isolated artifacts were observed during the evaluations.

One newly identified cultural resource activity locus was identified, evaluated, and recorded during the examinations. This site (42DC 761) consists of a non-significant lithic scatter associated with the access route into Unit 23-15.

AERC recommends project clearance based on adherence to the stipulations noted in the final section of this report.

TABLE OF CONTENTS

•								page
Abstract	•	•	•	•, ,			•	ii
Table of Contents	•	•	•		. i.	•	•	iii
List of Maps of the Project A	rea	•	•		•	•	•	iv
General Information .	•	•		•	•	•		1
Project Location	•	•	•	:	•		•	1
Environmental Descri	ption	•	•	. 1		•	•	4
Previous Research in the Loc	ality	•	• .	•	•	•		4
File Search	•	•	•	•	•		•	4
Prehistory and History	y of th	e Proje	ct Area		•	•	•	4
Site Potential in the P	roject	Develo	pment	Zone		•	•	5
Field Evaluations .	•		•	•	•	•	•	5
Methodology .	•	•	•	•	•	•	, ;	5
Site Significance Crite	eria	•	٠.	•.	•	•	•	6
Results of Inventory		•	•	•	•	•	•	6
Conclusion and Recommenda	ations		•	•	• .	•	٠	7
Deferences								8

LIST OF MAPS OF THE PROJECT AREA

						page
MAP 1: Cultural Resource Survey of Proposed Well Units in the Castle Peak Draw Locality, Duchesne County		,	•			2
reak Diaw Excainty, Ducheshe County	•	•		•	•	. —
		1.4				
MAP 2: Cultural Resource Survey of Proposed Well Units in the Castle			٠			
Peak Draw Locality, Duchesne County	•	•	•	•	•	3

GENERAL INFORMATION

On September 3, 1992, AERC archaeologist F.R. Hauck conducted intensive cultural resource evaluations for Balcron Oil Company of Billings, Montana. These examinations involved six separate well locations (24-5, 14-11, 23-11, 23-15, 32-15, and 41-15) and two linear access route evaluations totalling .5 mile associated with Units 24-5 and 23-15. Unit 13-5 was not included in the evaluations since it was previously examined for cultural loci and materials in 1981 (Hauck 1981). This project area is situated in the Castle Peak Draw locality of Duchesne County, Utah.

This project is situated on federal lands administered by the Diamond Mountain Resource Area of the Vernal District of the Bureau of Land Management.

The purpose of the field study and this report is to identify and document cultural site presence and assess National Register potential significance relative to established criteria (cf., Title 36 CFR 60.6). The proposed development of these well locations requires an archaeological evaluation in compliance with the Antiquities Act of 1906, the Reservoir Salvage Act of 1960-as amended by P.L. 93-291, Section 106 of the National Historic Preservation Act of 1966-as amended, the National Environmental Policy Act of 1969, the Federal Land Policy and Management Act of 1979, the Archaeological Resources Protection Act of 1979, the Native American Religious Freedom Act of 1978, the Historic Preservation Act of 1980, and Executive Order 11593.


In addition to documenting cultural identity and significance, mitigation recommendations relative to the preservation of cultural data and materials can be directed to the Vernal District Office of the Bureau of Land Management relative to the locations on public lands, and to the Antiquities Section of the Utah State Division of History. This work was done under U.S. Department of Interior Permit for Utah UT-92-54937 which expires on January 31, 1993.

The six evaluated well locations involved 10 acre parcel evaluations for a total of 60 acres evaluated. Two 15 to 20 meter-wide survey transects were walked within the 100 foot-wide corridors covering a total distance of .5 mile or some 6 acres.

Project Location

The project location is in the Vernal District of the Bureau of Land Management. It is situated on the Myton SE, 7.5 minute topographic quad as shown on the attached maps.

Units 13-5 and 24-5 are situated in the SW and SE quarters of Section 5, Township 9 South, Range 17 East. Units 14-11 and 23-11 are in the SW quarter of Section 11, Township 9 South, Range 16 East. The last three units (23-15, 32-15, and 41-15) are respectively situated in the SW and NE quarters of Section 15, Township 9 South, Range 16 East.



9 South 17 East

Meridian: SL

Quad: Myton SE, Utah

MAP 1

Cultural Resource Survey of Proposed Well Units in the Castle Peak Draw Locality, Duchesne County

Legend:

Ten Acre Survey Area

Access Route


Scale: 1:24000

BLCR-92-5 Series: Uinta Basin

Date:

9-8-92

AKK



T. 9 SouthR. 16 EastMeridion: SLQuad: MytonSE, Utah

MAP 2
Cultural Resource Survey
of Proposed Well Units in
the Castle Peak Draw
Locality, Duchesne County

Ten Acre
Survey
Area

Access
Route
Cultural
Site

Project: Scale: 1:24000
BLCR-92-5

Series: Uinta Basin

Date: 9-8-92 3

A short access route to Unit 24-5 extends from the SE quarter of Section 5 to the west into the SW quarter of that same section (see Map 1). The second access route links Unit 23-15 to an existing well in the SE quarter of Section 15 (see Map 2).

Environmental Description:

The project areas range within the 5200 to 5900 foot elevation zone above sea level. Open rangeland terrain surfaces are associated with all locations.

The vegetation in the project area includes Chrysothamnus spp., Sarcobatus vermiculatus, Ephedra viridis, Artemesia tridentata, Atriplex canescens, and Bromus tectorum.

The geological associations within the project area consist of fluvial and lake deposits which correlate with the Uinta Formation which is of Tertiary age.

PREVIOUS RESEARCH IN THE LOCALITY

File Search

Records searches of the site files and maps at the Antiquities Section of the State Historic Preservation Office in Salt Lake City were conducted on September 8, 1992. A similar search was conducted in the Vernal District Office of the BLM on September 3, 1992. The National Register of Historic Places has been consulted and no registered historic or prehistoric properties will be affected by the proposed developments.

A variety of known cultural sites are situated in the Castle Peak Draw locality. Most of these prehistoric resources, including 42DC 349, 350. 351, 352, 353, and 732 have been identified and recorded by AERC during previous evaluations (Hauck 1981, 1992a).

Prehistory and History of the Cultural Region

Currently available information indicates that the Northern Colorado Plateau Cultural Region has been occupied by a variety of cultures beginning perhaps as early as 10,000 B.C. These cultures, as identified by their material remains, demonstrate a cultural developmental process that begins with the earliest identified Paleoindian peoples (10,000 -- 7,000 B.C.) and extends through the Archaic (ca. 7,000 B.C. -- A.D. 300), and Formative (ca. A.D. 400 -- 1100) Stages, and the Late Prehistoric-Protohistoric periods (ca. A.D. 1200 -- 1850) to conclude in the Historic-Modern period which was initiated with the incursion of the Euro-American

trappers, explorers, and settlers. Basically, each cultural stage — with the exception of the Late Prehistoric hunting and gathering Shoshonean bands — features a more complex life-way and social order than occurred during the earlier stage of development (Hauck 1991:53). For a more comprehensive treatment of the prehistory and history of this region see <u>Archaeological Evaluations in the Northern Colorado Plateau Cultural Area</u> (Hauck 1991).

Site Potential in the Project Development Zone

Previous archaeological evaluations in the region have resulted in the identification and recording of a variety of cultural resource sites having eligibility for potential nomination to the National Register of Historic Places (NRHP). The majority of these sites are lithic scatters containing cobble reduction materials. Open occupations are also frequently being identified in this locality. Sites associated with the open rangeland generally appear to have been occupied during the Middle Archaic Stage with occasional indications of Paleoindian activity based on the recovery of isolated Plano style projectile points. The north-south drainage canyons appear to contain the majority of Late Prehistoric (Numa) sites probably because those canyon floors were transportation corridors and convenient pastures for the Ute horse herds. Evidence of Formative Stage occupation, i.e., the Fremont Culture, is rarely observed in the rangeland environment but is common within the Green River and White River canyons.

The majority of known sites in this project area are lithic scatters (42DC 349, 350, and 353). Open occupations such as 42DC 352 are also present. Site 42DC 351 is a rock shelter. Based on the recovery of a Folsom point and a Desert Side-notch arrow point, a possible Paleoindian component and a more recent Numic component exist on Site 42DC 353. Sites in the project locality generally appear to have been occupied during the Archaic Stage and the Late Prehistoric Period.

Site density in Castle Peak Draw appears to range from six to over ten sites per section in the project locality. This moderate to high density decreases substantially on the benches.

FIELD EVALUATIONS

<u>Methodology</u>

Intensive evaluations consisted of the archaeologist walking 10 to 20 meter wide transects within each ten acre parcel associated with a well location. In addition, double 15 to 20 meterwide transects were walked flanking the flagged centerline. Thus, ca. .5 mile or 6 acres of public lands associated with the two access routes and another 60 acres associated with six of the seven well locations were examined by F.R. Hauck. Unit 13-5 was not examined since it had already been evaluated by AERC in the past (Hauck 1981).

Observation of cultural materials results in intensive examinations to determine the nature of the resource (isolate or activity locus). The analysis of each specific cultural site results in its subsequently being sketched, photographed, and appropriately recorded on standard IMACS forms. Cultural sites are then evaluated for significance utilizing the standards described below and mitigation recommendations are considered as a means of preserving significant resources which may be situated within the development zone.

Site Significance Criteria

Prehistoric and historic cultural sites which can be considered as eligible for nomination to the National Register of Historic Places have been outlined as follows in the National Register's Criteria for Evaluation as established in Title 36 CFR 60.6:

The quality of significance in American ... archaeology ... and culture is present in ... sites ... that possess integrity of location, design, setting, materials, workmanship, feeling, and association and:

a. That are associated with events that have made a significant contribution to the broad patterns of our history; or

b. that are associated with the lives of persons significant in our past; or

c. that embody the distinctive characteristics of a type, period, or method of construction ...; or

d. that have yielded, or may be likely to yield, information important in prehistory or history.

In addition to satisfying one or more of these general conditions, a significant cultural resource site in Utah will generally be considered as being eligible for inclusion in the National Register if it should advance our current state of knowledge relating to chronology, cultural relationships, origins, and cultural life ways of prehistoric or historic groups in the area.

In a final review of any site's cultural significance, the site must possess integrity and at least one of the above criteria to be considered eligible for nomination to the National Record of Historic Places.

Results of the Inventory:

A single non-significant prehistoric cultural resource activity locus was observed, evaluated and recorded during the archaeological evaluations. This site has been subsequently listed in the State and BLM files as 42DC 761.

Site 42DC 761 consists of a small, bare rockshelter that opens to the east. The slope below the shelter contains four fragments of detritus. The shelter has no depth potential based on a trowel test in its entrance and one just outside the

entrance. The sparsity of material remains and lack of depth suggest the site was occupied possibly during a single episode related to core reduction.

No previously recorded cultural sites will be adversely affected by the proposed pipeline developments. Site 42DC 353 is situated in the vicinity of the present development program but will not be affected by the proposed development.

No isolated diagnostic artifacts were observed or collected during the survey on BLM administrated lands.

CONCLUSION AND RECOMMENDATIONS

AERC recommends that a cultural resource clearance be granted to Balcron Oil Company relative to the development of the seven well locations noted above based upon adherence to the following stipulations:

- 1. All vehicular traffic, personnel movement, construction and restoration operations should be confined to the flagged areas and corridors examined as referenced in this report, and to the existing roadways and/or evaluated access routes.
- 2. All personnel should refrain from collecting artifacts and from disturbing any significant cultural resources in the area.
- 3. The authorized official should be consulted should cultural remains from subsurface deposits be exposed during construction work or if the need arises to relocate or otherwise alter the location of the exploration area.

F. Richard Hauck, Ph.D.

President and Principal

Investigator

REFERENCES

Hauck, F. Richard

- Cultural Resource Inventory of Nine Proposed Well Locations and Access Roads in the Coyote Basin Locality of Uintah County, Utah, and in the Castle Peak Draw Locality of Duchesne County, Utah: Report prepared for Diamond Shamrock, DS-81-2, Archeological-Environmental Research Corporation (AERC), Bountiful.
- 1991 Archaeological Evaluations on the Northern Colorado Plateau Cultural Area, AERC Paper No. 45, Archeological-Environmental Research Corporation, Bountiful.
- 1992a Cultural Resource Evaluations of Four Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-2, Archeological-Environmental Research Corporation (AERC), Bountiful.
- 1992b Addendum to Cultural Resource Evaluations of Four Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-4, Archeological-Environmental Research Corporation (AERC), Bountiful.

Bureau of Land Manyement Utah State Of Lee (AERC FORMAT) Summary Report of Inspection for Cultural Resources	Report Acceptable Yes No Mitigation Acceptable Yes No Comments:
1. Report Title	UNITS 13-5, 24-5, 14-11, 23-11, 23-15, and 41-15
9 8 1 9 9 2 3. Report Date	UT-92-54937 4. Antiquities Permit No.
A E R C <u>5. Responsible Institution</u>	B L C R - 9 2 - 5 Duchesne County
6. Fieldwork	7 Section
intensively examined the 10 acre 1 14-11, 23-11, 23-15, 32-15, and 42-1 the attached maps) by walking a se- flanking the flagged centerline and	ocations for six of these Wells (24-5, 5) and new access corridors (as shown on eries of 10 to 20 meter-wide transects within the flagged Well pad. Unit 13-5
9. Linear Miles Surveyed and/or Definable Acres Surveyed and/or Legally Undefinable 66 Acres Surveyed	I 10. Inventory Type R = Reconnaissance I = Intensive S = Statistical Sample
during the survey. This lithic so was observed in association with t	Report of Mitigation Acceptable Yes No Comments:
The National Register of Historic I	Places (NRHP) has been consulted and no
15. Literature Search, Location/ Date:	Utah SHPO 9-8-92 Vernal District Office Records 9-3-92

Authorization No .U.9.2.A.F.4.9.8.5.

Department of the Interior

16. Conclusion/ Recommendations:

AERC recommends that a cultural resource clearance be granted to Balcron Oil Company for these proposed developments based on the following stipulations:

- 1. All vehicular traffic, personnel movement, construction and restoration operations should be confined to the corridor examined as referenced in this report, and to the existing roadways and/or evaluated access routes.
- 2. All personnel should refrain from collecting artifacts and from disturbing any significant cultural resources in the area.
- 3. The authorized official should be consulted should cultural remains from subsurface deposits be exposed during construction work or if the need arises to relocate or otherwise alter the location of the exploration area.

17. Signature of Administrator & Field Supervisor

UT 8100-3 (2/85)

Administrator

Field Supervisor Balcron Monument Federal #13-5 NW SW Section 5, T9S, R17E Duchesne County, Utah 1980' FSL, 660' FWL FLS #U-020252 PTD 5,620' GL 5,224'

Balcron Monument Federal #24-5 SE SW Section 5, T9S, R17E Duchesne County, Utah 765' FSL, 2243' FWL FLS #U-020252 PTD 5,600' GL 5,223'

Balcron Monument Federal #23-11
NE SW Section 11, T9S, R16E
Duchesne County, Utah
1787 FSL, 2147' FWL
FLS #U-096550
PTD 5,750'
GL 5,622'

Balcron Monument Federal #14-11
SW SW Section 11, T9S, R16E
Duchesne County, Utah
1048' FSL, 446' FWL
FLS #U-096547
PTD 5,720'
GL 5,661'

Balcron Monument Federal #41-15
NE NE Section 15, T9S, R16E
Duchesne County, Utah
460' FNL, 500' FEL
FLS #U-017985
PTD 5,700'
GL 5,714'

Balcron Monument Federal #32-15 SW NE Section 15, T9S, R16E Duchesne County, Utah 1868' FNL, 1993' FEL FLS #U-017985 PTD 5,610' GL 5,681'

Balcron Monument Federal #23-15
NE SW Section 15, T9S, R16E
Duchesne County, Utah
1724' FSL, 2078' FWL
FLS #U-017985
PTD 5,700'
GL 5,828'

8-92 WED 10:51 OR PERMANENT CHANGE OF WATER RECEIVED ROC. by DIL STATE OF UTAH APR 17 1987 WATER AIGHT SPECIAL # 20 DIVISION OF OIL GAS & MINING For the purpose of obtaining permission to make a permanent change of water in the State of Utah, application is hereby made to the State Engineer, based upon the following showing of facts, submitted in accordance with the requirements of the Laws of Utah. *WATER USER CLAIM NO. 43 - 9974 *APPLICATION NO. 8-14389 Changes are proposed in (check those applicable) ____point of return. __point of diversion. _____ nature of use. place of use. OWNER INFORMATION Dale Anderson Name: Owen PO BOX 1168 Address: 2. *PRIORITY OF CHANGE: _____ *FILING DATE: ____ *Is this change amendatory? (Yes/No): ___ 3. RIGHT EVIDENCED BY: 43 -Prior Approved Change Applications for this right: 83-43-21 84-43-73 E 14099 ___cis and/or _____ ac-it. SOURCE: U.G.W (well) POINT(S) OF DIVERSION: South 1167 ft East 340 ft from Ny4 Corner Section 27 TIS, RZW, USR+M Description of Diverting Works: The water will be rediverted from ______at a point: _____ 8. POINT(S) OF REDIVERSION Description of Diverting Works: 9. POINT(S) OF RETURN The amount of water consumed is _____ cis or ____ ac-it. The water will be returned to the natural stream/source at a point(s):

ca llame are to be completed by Division of Water Rights.

10. NATURE AND PER	IOD OF USE	Dec 31			
Stockwatering:	Erom w Lall	10 Dec 31			
Domestic	From				
Municipal:	From		•		
Mining:	From	In			
Power:	From Ton	10 Dec 31		•	
Others	From April 1	10 Oct 31			
Irrigation		•	·	•	
11. PURPOSE AND E	CTENT OF USE	250 Livestock Un	its		
Stockwatering (n	TENT OF USE umber and kind): — -	Persons.		•	
Domestici	Families and/or	1010000			Mine.
Municipal (name]:	Mining	District in the		TATILO.
Mining:				0	
Ores mined:	10:		Type:	Locations Tie	La Culture
		(() 1) 1 D (() L L L L L L L L L L L L L L L L L	- VI - III-IV		
Other (describe)	5.7 acres. Sole	supply of	acres		
				1	
12. PLACE OF USE	n of areas of use other	than irrigation by 40	acre tract:r	x/a	
Legal descriptio	n of areas of use other	- HILLIAN TAXABULAN O			
			·		
13. STORAGE	DI_ Um	i amed Si	orage Period: from	1-/1-1	3-3/
Reservoir Nam	01	Aran acres		-	
Capacity: 4'	O ac-it. Inundated	Vica:			- 40
Height of dami	[eet on of inundated area t	WATERCE NWA	6 Sug 27, 1	115 ROW 251	X * ///
Legal descripti	on of infingated area r	uy 40 trautr			
	A THE FO	TO THE PROPERTY OF THE PROPERT	GARE PROPOSED	*************	*****
*********	«ቀቅቅቅቅቅ	DETOMING CHYMAE	5 AMBINOTONAL		•
		- 41	. ALL ACOLO		
14. QUANTITY OF	WATER:	Remaining	g Waler:50	me	
15. SOURCE:	Sin lancing				
16. COUNTY:	Duchesne	50 me			
17. POINT(S) OF I)[VERSION:				
50.0.000					
	f Diverting Works:				•
Description o	1 Disating storms				
18. POINT(S) OF	REDIVERSION			at a point:	
The water w	REDIVERSION Il be rediverted from .				
					,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
	of Diverting Works:				
Description	of Diverting works: -	1			

	· •
and the second s	
The amount of water consumed to	2-11
The amount of water returned is cfs or ac- The water will be returned to the natural stream/source	[[
The amount of the returned to the natural stream/source	e at a point(s):
The water will be recommended	
NATURE AND PERIOD OF USE	
Clockwatering: From W -	•
DIOCKARTOTING.	
Domouro.	
Tunni 10	•
Power: From to Dec 31	
Other: From Jan 10 Description	
Irrigation: Fromto	·
. PURPOSE AND EXTENT OF USE	
condemnating (number and kind):	
Familles and/or retsolls	
Municipal (name):	Mining District in the Mine
Mining:	Mining District in theMine
Mining:	on of oil wells
Power Plant name:	of oil wells
Other (describe): drilling and complete	ion of the second
Other (describe):acros. Sole supply of	
	•
22. PLACE OF USE	(
22. PLACE OF USE Logal description of areas of use by 40 acre tract:	
	by water trucks as needed
Other: hauled to locations	by Water
23. STORAGE	Storage Period: Iromto
Reservoir Name:	peres
Reservoir Name: oc-it. Inundated Area: _	HOLOU
Height of dam:teet Legal description of inundated area by 40 tract:	
Fogat descributor of many	
mains axiaTODV	the state of the s
24. EXPLANATORY	e full purpose of this application. Include any supplements ional pages of same size if necessary):
The following is set forth to define more. (Use addit	e full purpose of this application. Include any supplementational pages of same size if necessary):
water rights used for the same Fair	
alexand in for oilfiel	
- Change 15 15	L. R. C. L.
Approximately 4 acre.	ftwill be taken from
Approximately 7 acte	
	od: used for oilfield purposes
irrigation purposes av	na lasta son and
Acres to be irrigated will	change from 55.7 to 30 deres
(!_\)	• • •

8-92 WED 10:53

ndersigned hereby acknowledges that even though he/she/they may have been assisted in the preparation above-numbered application through the courtesy of the employees of the Division of Water Rights, all insibility for the accuracy of the information contained herein, at the time of filing, rests with the cani(s).

Signature of Applicant(s)

DATE RECEIVED: 09/17/92

operator acct no: N-9890 OPERATOR: BALCRON OIL WELL NAME: BALCRON MONUMENT FEDERAL 23-11 API NO. ASSIGNED: 43 -013 -31369 LEASE TYPE: FED LEASE NO: U- 09 6550 LOCATION: NESW 11 - TO9S - R16E DUCHESNE COUNTY FIELD: MONUMENT BUTTE FIELD CODE: \05 LOCATION AND SITING: RECEIVED AND/OR REVIEWED: R649-2-3. Unit: Plat Bond Potash (Y/N) R649-3-2. General. R649-3-3. Exception. Oil shale (Y(N)) Water permit (Number 13-9974 0-14089 Drilling Unit. RDCC Review (Y/N) Board Cause no: Date: (Date: COMMENTS: CQWNFIDENT4A PERIOD EXPIRED STIPULATIONS:

NOV 1 6 1993

UTAH DIVISION OF OIL, GAS AND MINING EQUIPMENT INVENTORY

DIVISION OF OIL, GAS & MINING

Operator: <u>EQUITABLE RESOURCES</u>		Lease: State:	Federal: Y
Indian:Fee:			
Well Name: BALCRON MONUMENT FED	#22-11	APT Number: 4	3-013-31369
Well name: Balchon nonunent FED	*23-11		<u> </u>
Section: 11 Township: 95 R	ange: 16E Co	ounty: <u>DUCHESNE</u>	
Field: MONUMENT BUTTE Well Status: POW We	11 Type: Oil:	: <u>Y</u>	
PRODUCTION LEASE EQUIPMENT: Y	CENTRAL BA	ATTERY:	
Y Well head Boiler(g)(Compressor	
Separator(s)	/_\ ¥ 1	· in Tankania)	Vonted
Dehydrator(s) Shed	(B) <u>I</u>	Tue meacer(s)	neaceu
Separator YRU Heater	Treater(s)		
PUNPS:			
Triplex C	hemical	Centrifu	gal
MBB1100			
LIFT METHOD:	4	Submersible	
Y Pumpjack Hydraul		DODMET BIDIE	
Flowing			
GAS EQUIPMENT:			
N Gas Neters N Purchas	e Meter	N Sales Meter	
TANKS: NUMBER		SIZE	
Y Oil Storage Ta	nk(e) 2	-400 BARREL OIL TA	NKS
OII Storage is	11111111	100 philipp 0-2	BBLS
Y Water Tank(s)		-130 BARREL PIT TA	NK
			BBLS
Power Water Ta	nk		
		<u> </u>	BBLS
Condensate Tan	k(g)	BBLS	·
(2) Propane Tank			
F1-Opane lank			
REMARKS: LINE HEATER IS HEATED	BY EXHAUST M	JFFLER ON PUMP MOT	OR; PIT
TANK WITH WIRE COVER; NO SALES			
Location central battery: Qtr/G	ita. C.	action. T	avashia:
Range:	C1:; 56		O#119117b.
nanae •			
Inspector: DENNIS 1	NGRAM	Date:	11/5/93



Dee C. Hansen
Executive Director

Dianne R. Nielson, Ph.D.
Division Director

Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340

September 21, 1992

Balcron Oil P.O. Box 21017 Billings, Montana 59104

Gentlemen:

Re: Balcron Monument Federal #23-11 Well, 1787 feet from the south line, 2147 feet from the west line, NE 1/4 SW 1/4, Section 11, Township 9 South, Range 16 East, Duchesne County, Utah

Pursuant to Utah Admin. R. 649-3-2, Location and Siting of Wells and Utah Admin. R. 649-3-4, Permitting of Wells to be Drilled, Deepened or Plugged-Back, approval to drill the referenced well is hereby granted.

In addition, the following specific actions are necessary to fully comply with this approval:

- 1. Compliance with the requirements of Utah Admin. R. 649-1 et seq., Oil and Gas Conservation General Rules.
- Notification within 24 hours after drilling operations commence.
- 3. Submittal of Entity Action Form, Form 6, within five working days following commencement of drilling operations and whenever a change in operations or interests necessitates an entity status change.
- 4. Submittal of the Report of Water Encountered During Drilling, Form 7.
- 5. Prompt notification prior to commencing operations, if necessary, to plug and abandon the well. Notify Frank R. Matthews, Petroleum Engineer, (Office) (801)538-5340, (Home) (801)476-8613, or R.J. Firth, Associate Director, (Home) (801)571-6068.

Page 2
Balcron Oil
Balcron Monument Federal #23-11 Well
September 21, 1992

6. Compliance with the requirements of Utah Admin. R. 649-3-20, Gas Flaring or Venting, if the well is completed for production.

Trash and sanitary waste should be properly contained and transported to approved disposal locations, not retained in or disposed of in pits on location or downhole. Prior to the commencement of drilling operations, the operator should consult the local/county sanitarian and/or the Department of Environmental Quality, Division of Drinking Water/Sanitation, regarding appropriate disposal of sanitary waste.

This approval shall expire one year after date of issuance unless substantial and continuous operation is underway or a request for an extension is made prior to the approval expiration date. The API number assigned to this well is 43-013-31369.

Sincerely,

Associate Director, Oil and Gas

ldc

Enclosures

cc.

Bureau of Land Management

J.L. Thompson

WOI1



EQUITABLE RESOURCES ENERGY COMPANY, BALCRON OIL DIVISION

1601 Lewis Avenue P.O. Box 21017 Billings, MT 59104 (406) 259-7860 FAX: (406) 245-136\$

March 4, 1993

State of Utah Uintah County 152 East 100 North Vernal, UT 84078

Gentlemen:

Effective March 1, 1993, the name of our company has changed from Balcron Oil Company to Equitable Resources Energy Company, Balcron Oil Division.

Please make the necessary changes in your records and let me know if there is anything else we need to do in order to effect the change for the 1993 Uintah County Business License.

Sincerely,

Bobbie Schuman

Coordinator of Operations,

Environmental and Regulatory Affairs

/rs

RECEIVED

MAR D 8 1993

DIVISION OF OIL GAS & MINING



355 West North Temple, 3 Triad Center, Suite 350, Salt Lake City, Ut 84180-1203. ●(801-538-5340)

Page 7 of 7

MONTHLY OIL AND GAS PRODUCTION REPORT

Operator name and address	:				
• BALCRON OIL		ŧ			Month/Year)
				Amended Repor	t ∟
Well Name	Producing	Days	Production Volum	е	
API Number Entity Location	1	,	Oil (BBL)	Gas (MSCF)	Water (BBL)
BALCRON MONUMENT FED 42-6					
43-013-31364 11431 9S 17E 6	GRRV		$-\omega \iota \omega$		
BALCRON MONUMENT FED 41-15					
43-013-31367 99999 9S 16E 15					
BALCRON MONUMENT FED 32-15					
43-013-31368 99999 9S 16E 15					
BALCRON MONUMENT FED 23-11	:				
<u>43-013-31369 99999 9S 16E 11</u>					
BALCRON MONUMENT FED 13-5					
43-013-31370 99999 9S 17E 5					
BALCRON MONUMENT FED 23-15					
<u>43-013-31373 99999 9S 16E 15</u>					
BALCRON MONUMENT FED 14-11					
<u>43-013-31374 99999 9S 16E 11</u>					
BALCRON MONUMENT FED 24-5					
43-013-31375 11445 9S 17E 5	GRRV				
	T	OTAL			, , , , , , , , , , , , , , , , , , ,
Comments (attach separate sheet if neces	ssary)				alara arang ar
					kraik mar daga di mara daga gana daga gana kraik da mar ya raman na mara da na h
				_	
I have reviewed this report and certify the	information	to be	accurate and compl	ete. Date	
				Talanhona	
Authorized signature		······································		rerephone	

OPERAT	of 0:1, Gas and Mining OR CHANGE WORKSHEET		•	Routing:
	Il documentation received by the ceach listed item when completed.			2-DTS//58-LEGY 3-VLC 4-RJF
□ Chan □ Desi	ge of Operator (well sold) gnation of Operator	□ Designation XXX Operator Na	of Agent me Change Only	5-RWM 6-ADA
The ope	erator of the well(s) liste	d below has changed (EF	FECTIVE DATE: 3-1-9)
TO (nev	w operator) EQUITABLE RESOUR (address) BALCRON OIL DIVI PO BOX 21017 BILLINGS MT 591 phone (406) 259 account no. N 9	1SION 104 9-7860	(address) PO BOX BILLING phone (
Well(s)) (attach additional page if neede			
Name:_ Name:_ Name:_ Name:_ Name:_	**ALL WELLS** API: API: API: API: API: API: API: API	Entity:Entity:Entity:Entity:Entity:Entity:Entity:	SecTwpRng_ SecTwpRng_ SecTwpRng_ SecTwpRng_	Lease Type: Lease Type: Lease Type: Lease Type:
<u>μ/</u> Α 1.	OR CHANGE DOCUMENTATION (Rule R615-8-10) Sundry of operator (Attach to this for (Rule R615-8-10) Sundry or	orm)		
Lec 3.	(Attach to this form). Che	ed 3-8-93) has been contacted if	the new operator abo	ve_is not currently
4	(For Indian and Federal h (attach Telephone Documen comments section of this changes should take place	tation Form to this form. Management revi prior to completion of	report). Make note lew of Federal and I r steps 5 through 9 bel	of BLM status in ndian well operator ow.
	Changes have been entered listed above. (3-19-93)			/IBM) for each well
Jec 6.	Cardex file has been update	ed for each well listed	l above. (3-19-93)	
Jec 7.	Well file labels have been	updated for each well	listed above. [3-19-93]	
٨	Changes have been included for distribution to State	Lands and the Tax Commi	ission. (3-19-93)	
Jec 9.	A folder has been set up f placed there for reference	for the Operator Change during routing and pro	e file, and a copy of ocessing of the origin	this page has been al documents.

UNITED STATES DEPARTMENT OF THE INTERIOR

SUBMIT IN TRIE (Other instruct reverse side)

DOGMA Form approved. Budget Bureau No. 1004-0136 Expires August 31, 1985

	•	JOF LAND MANAC				U-096550
A DDL ICATION				N, OR PLUG B	ACK	6. IF INDIAN, ALLOTTEE OR TRIBE NAME
a. TYPE OF WORK				•	i	n/a 7. UNIT AGREEMENT NAME
	LL 🖾	DEEPEN		PLUG BAC	к 🗀	n/a
b. TYPE OF WELL OIL X WE	S OTH	DR.		NGLE MULTIPE	· 🗀	8. FARM OR LEASE NAME
NAME OF OPERATOR	<u> </u>	· .		CUUEIUEU	ТІДІ	Balcron Monument Federal
EQUITABLE RES	OURCES ENER	GY COMPANY			11116	9. WELL NO. #23-11
ADDRESS OF OPERATOR	7. Dillings	MT 50104		10)12(C]3[[V	SIN	10. FIELD AND POOL, OR WILDCAT
P.O. BOX 2101 LOCATION OF WELL (Re	port location clear	y and in accordance with	th any S	tate requirements.*)	AM	Monument Butte/Green Rive
At surface 1787' FSL, 2	147' FWL	NE SW		MAY 0 6 199	3	11. SEC., T., B., M., OR BLK. AND SURVEY OR AREA
At proposed prod. zone		-	,		J	NE SW Sec. 11, T9S, R16E
4. DISTANCE IN MILES A		. 013-3136 9 m nearest town or pos		DIVISION OF	;	12. COUNTY OR PARISH 13. STATE
		from Myton, UT		e EXHIBAS &BAIN!		Duchesne UTAH
5. DISTANCE FROM PROPO	SED*			. OF ACRES IN LEASE	17. No. 0	OF ACRES ASSIGNED HIS WELL
PROPERTY OR LEASE L (Also to nearest drig	ine, ft.			10 acres		40
18. DISTANCE FROM PROP	OSED LOCATION* RILLING, COMPLETE			,750'		RY OR CABLE TOOLS
OR APPLIED FOR, ON THE 21. ELEVATIONS (Show whe	S LEASE, FT.		1 3	,730	<u> </u>	Otary 22. APPROX. DATE WORK WILL START*
GI 5.622	ther Dr. RI, GR.	· ·				November 15, 1992
[6] 5,022 3.		PROPOSED CASI	NG ANI	CEMENTING PROGRA	.м	
SIZE OF HOLE	SIZE OF CASIN			SETTING DEPTH		QUANTITY OF CEMENT
12-1/4"	8-5/8"	24#		260'	250 s	x G w/3% CaCl
See attached	Drilling Pr	ogram for prod	<u>uctio</u>	n casing.	<u> </u>	RECEIVED
"B" Proposed "C" Geologic "D" Drilling "E" Evidence "F" Archeolo NOTE: In acco EXHIBIT SELF CERTIFICATION: operations associat being provided by E surety under BLM Bo with all of the ter	e of Bond Co ogy Report ordance with ordance with ordance with F" Arched E I hereby cered ted with the a countable Resound No. MT 057 ons and condit ordance program drill or deepen div.	se Program using Diagram overage request by the ology Report is rtify that I am au- opplication. Bond ources Energy Compan 6 (Nationwide Oil di ions of that portion	thorize covera ny as i & Gas i on of pea or at data	Existing Well Drillsite Lay nal BLM represe uded with this ed, by proper lease ge pursuant to 43 Corincipal and Safect Bond #5547188) who withe lease associated by the lease as the	and E's/Plands (Mapout/Curntative permit interes R 3104 or Insuration of Market Production of	ned Access (Maps A & B) C) t and Fill Diagrams e, only one copy of t owner, to conduct these for lease activities is ance Company of America as responsible for compliance his application ductive sone and proposed new productive ed and true vertical depths. Give blowout mental
(This space for Fede	` a la			APPROVAL DATE ASSISTANT DISTRICE MANAGER MINERAL	ī	MAY 0 3 1993
APPROVED BY CONDITIONS OF APPROV		NOTICE OF AF		VAL	CONDITI	IONS OF APPROVAL STTACHED TO CORREATURE OF A

WELL LOCATION INFORMATION



Company/Operator Equitable Resources Energy Co. API Number ______43-013-31369 Well Name & Number Balcron Monument Federal No. 23-11 Lease Number _____<u>U-096550</u> Location NESW Sec. 11 T. 9S. R. 16E. Surface Ownership ___Federal Date NOS Received August 13, 1992

NOTIFICATION REQUIREMENTS

Location Construction

at least forty-eight (48) hours prior to construction of location and

access roads.

Date APD Received September 17, 1992

Location Completion

prior to moving on the drilling rig.

Spud Notice

at least twenty-four (24) hours prior to spudding the well.

Casing String and Cementing

at least twenty-four (24) hours prior to running casing and cementing all

casing strings.

BOP and Related **Equipment Tests**

at least twenty-four (24) hours prior to initiating pressure tests.

First Production

Notice

within five (5) business days after new well begins or production

resumes after well has been off production for more than ninety (90)

days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Company Equitable Resources Energy Company Well No. Monument Federal 23-11

Location NESW Section 11, T9S, R16E Lease No.U - 096550

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Orders, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report <u>ALL</u> water shows and water-bearing sands to Tim Ingwell of this office. Copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a 2M system and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

The Vernal District Office shall be notified, at least 24 hours prior to initiating the pressure tests, in order to have a BLM representative on location during pressure testing.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

As a minimum, the usable water and oil shale resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the base of the usable water zone, identified at \pm 2,586 ft. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

The Vernal District Office shall be notified at least 24 hours prior to the running and cementing of all casing strings, in order to have a BLM representative on location while running and cementing all casing strings.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vaporproof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

A cement bond log (CBL) will be run from the production casing shoe to \pm 2,386 ft. and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

The Vernal District Office shall be notified, during regular work hours (7:45 a.m.-4:30 p.m., Monday through Friday except holidays), at least 24 hours <u>prior</u> to spudding the well.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-2, 3162.7-3, and 3162.7-4 shall be submitted to the appropriate District Office within thirty (30) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-4.

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling onlease or off-lease will have prior written approval from the AO.

Gas meter runs for each well will be located within 500 feet of the wellhead. The gas flowline will be buried or anchored down from the wellhead to the meter and within 500 feet downstream of the meter run or any production facilities. Meter runs will be housed and/or fenced.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted monthly for the first three months on new meter installations and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to $43~\mathrm{CFR}$ 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, please contact one of the following individuals:

Gerald E. Kenczka Petroleum Engineer (801) 781-1190

Ed Forsman

(801) 789-7077

Petroleum Engineer

(801) 789-3634

BLM FAX Machine

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES While the following wastes are nonexempt, they are not necessarily hazardous.

Unused fracturing fluids or acids

Gas plant cooling tower cleaning wastes

Painting wastes

Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spend solvents, spilled chemicals, and waste acids

Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste

Refinery wastes

Liquid and solid wastes generated by crude oil and tank bottom reclaimers

Used equipment lubrication oils

Waste compressor oil, filters, and blowdown

Used hydraulic fluids

Waste solvents

Waste in transportation pipeline-related pits

Caustic or acid cleaners

Boiler cleaning wastes

Boiler refractory bricks

Incinerator ash

Laboratory wastes

Sanitary wastes

Pesticide wastes

Radioactive tracer wastes

Drums, insulation and miscellaneous solids.

SURFACE USE PLAN OF OPERATIONS

CONDITIONS OF APPROVAL

Construction/upgrading shall include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well constructed safe road.

If a plastic nylon reinforced liner is used, it will be a minimum of 12 mil thickness with sufficient bedding (either straw or dirt) to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash, scrap pipe, etc., that could puncture the liner will be disposed of in the pit.

Reclamation of unused disturbed areas on the well pad/access road no longer needed for operations, such as cut slopes, and fill areas will be accomplished by grading, leveling and seeding as recommended by the Authorized Officer.

Full seeding will be done after September 15 and before the ground freezes. Spring seeding will be done prior to April 15.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

A complete copy of the approved APD and ROW grant, if applicable, shall be on location during construction of the location and drilling activities.

The operator or his/her contractor shall contact the BLM Office at (801)789-1362 forty-eight (48) hours prior to construction activities.

The BLM Office shall be notified upon site completion prior to moving on the drilling rig.

The requested emergency pit is hereby approved under NTL-2B, Section VI, subject to the following Conditions of Approval:


- 1. If emergency use occurs, the emergency pit shall be emptied and the liquids disposed of in accordance with applicable State and/or Federal regulations within 48 hours following its use, unless such time is extended by the authorized officer.
- 2. As much as practicable, the emergency pit shall be located on level ground, and away from drainage patterns and unstable ground.
- 3. The emergency pit shall be fenced and the fence maintained for safety, and to prevent livestock and wildlife entry. The pit shall be fenced according to the same minimum standards listed for the drilling reserve pit under Point 9E of the Multi-point Surface Use and Operation Plan. The fence shall be maintained in a taut condition. Fences shall not be built on berms.
- 4. Produced water drain lines shall not go to the emergency pit.

5. The pit shall be bermed or otherwise constructed and maintained to prevent entrance of surface water.

- 6. Turn downs shall be put on the ends of pipes to direct fluids downward instead of against the wall of the pit.
- 7. The pit shall be kept free of trash.

Balcron shall contract a Utah BLM certified Paleontologist to survey the location and access road prior to surface disturbance to determine the presence of paleontological resources.

If historic, archaeological, or paleontological resources are uncovered during ground disturbing activities, Balcron will suspend all operations that would further disturb such materials and immediately contact the BLM Authorized Officer.



BALCRON OIL

Balcron Monument Federal #23-11

NE SW Section 11, T9S, R16E, SLB&M

Duchesne County, Utah

PALEONTOLOGY REPORT
WELLPAD LOCATION AND ACCESS ROAD

BY

ALDEN H. HAMBLIN PALEONTOLOGIST 235 EAST MAIN VERNAL, UTAH 84078

JULY 1, 1993

RESULTS OF PALEONTOLOGY SURVEY AT BALCRON MONUMENT BUTTE FEDERAL #23-11

Description of Geology and Topography-

This well location is on the bench approximately 1/2 mile north of Castle Peak Draw, 11 miles south and 2 miles west of Myton, Utah. A small side canyon to Castle Peak Draw lies between the location and Castle Peak Draw. The wellpad is located on a surface that slopes gently to the north and north east into the drainage of another side canyon of Castle Peak Draw. The access road enters the wellpad location immediately after leaving an existing road.

All rock outcrops in the area are of the Upper Eocene Uinta Formation, known for its fossil vertebrate fauna of mammals, turtles, crocodilians, and occasional fish remains.

Rocks in the immediate area of the proposed wellpad are composed of interbedded sandy limestone, limy sandstone, shale, and sandstone. Some chert is associated with this material also. Probably represents shallow lacustrine (lake) and fluvial (stream) deposits.

Paleontological material found -

No fossil vertebrate material was found on the wellpad location or access road.

Some of the pieces of dark brown chert found on the surface with limestone fragments appear to have ostracods (fresh water crustaceans) in them. This is a small invertebrate shelled animals common in some layers of the Uinta Formation is this area. Because ostracods are small and so common in these rocks, construction of wellpads and access road poses no threat to that paleontological resource.

Recommendations-

No other recommendations are made for this location.

Alden H. Humblin

Date // 3,1993



1601 Lewis Avenue P.O. Box 21017 Billings, MT 59104 Office: (406) 259-7860 FAX: (406) 245-1365 [] FAX: (406) 245-1361 []

July 7, 1993

RECEIVED

DIVISION OF C'L GAS & MININC

Bureau of Land Management 170 South 500 East Vernal, UT 84078

Gentlemen:

Enclosed are Paleontology Reports which were required for the following wellpad locations and access roads:

Balcron Monument Federal #13-5 NW SW Section 5, T9S, R17E Duchesne County, Utah FLS #U-020252 43-012-31370

Balcron Monument Federal #23-11 NE SW Section 11, T9S, R16E Duchesne County, Utah FLS #U-096550 43-013-31369

Balcron Monument Federal #14-11 43-013-3/374 SW SW Section 11, T9S, R16E Duchesne County, Utah FLS #U-096547

If you have any questions, please give me a call.

Sincerely,

Bobbie Schuman

Coordinator of Operations,

Environmental and Regulatory Affairs

/rs

Enclosures

cc: Utah Division of Oil, Gas and Mining



1601 Lewis Avenue P.O. Box 21017 Billings, MT 59104 Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361

August 5, 1993

State of Utah Division of Oil, Gas & Mining 355 West North Temple Salt Lake City, UT 84180

Gentlemen:

Enclosed are sundry notices requesting an extension for the APDs for the following wells:

Balcron Monument Federal #14-11 Balcron Monument Federal #23-15 Balcron Monument Federal #23-11 Balcron Monument Federal #32-15 Balcron Monument Federal #41-15

All of these APDs expire in September 1993 and our drilling program has these wells scheduled to begin after the expiration dates. If you need to hold these requests until closer to the expiration dates, please do so.

If you have any questions or need further information, please give me a call.

Sincerely,

Bobbie Schuman

Coordinator of Operations,

Environmental and Regulatory Affairs

/rs

Enclosures

DEGETALET

DIVISION OF OIL GAS & MINING ,EORM 9 ₽

DIVISION OF OIL, GAS AND MINING

·		5. Lease Designation and Serial Number:				
		Federal # U-096550				
SUNDRY NOTICES AND REPORTS (6. If Indian, Allottee or Tribe Name:					
Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for sur		7. Unit Agreement Name: Jonah Unit				
1. Type of Well: OIL X GAS OTHER:	:	8. Well Name and Number: Balcron Monument Fed. #23-11				
2. Name of Operator: Equitable Resources Energy Company, Balcron Oil Division		8. API Well Number: 43-013-31369				
3. Address and Telephone Number: P.O. Box 21017; Billings, MT 59104	(406) 259-7860	10. Field and Pool, or Wildcat: Monument Butte/Grn.River				
4. Location of Well Footages: 1787' FSL, 2147' FWL		County: Duchesne				
αα, sec.,T.,R.,M.: NE SW Section 11, T9S, R16E		State: UTAH				
11. CHECK APPROPRIATE BOXES TO INDICATE N	ATURE OF NOTICE, REPOR	RT, OR OTHER DATA				
NOTICE OF INTENT (Submit in Duplicate)		UENT REPORT riginal Form Only)				
☐ Abandonment ☐ New Construction	☐ Abandonment *	☐ New Construction				
Casing Repair Pull or Alter Casing	Casing Repair	☐ Pull or Alter Casing				
☐ Change of Plans ☐ Recompletion	☐ Change of Plans	☐ Shoot or Acidize				
☐ Conversion to Injection ☐ Shoot or Acidize	Conversion to Injection	☐ Vent or Flare				
☐ Fracture Treat ☐ Vent or Flare	☐ Fracture Treat	☐ Water Shut-Off				
☐ Multiple Completion ☐ Water Shut-Off	K) Other Request for AP	D extension				
Other	· · · · · · · · · · · · · · · · · · ·					
	Date of work completion					
Approximate date work will start	Report results of Multiple Completions and COMPLETION OR RECOMPLETION AND LO	If Recompletions to different reservoirs on WELL.				
	* Must be accompanied by a cement verifical	tion report.				
DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.) This APD is scheduled to expire 9/21/93. We hereby request a one-year extension to this APD as our current drilling program has this well scheduled to begin after the expiration date. APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING DATE: DIVISION OF OIL GAS & MINING						
13. Name & Signature: Dobbie Schuman	Coordinator of	Environmental ry Affairs Date: 8/5/93				
Bobbie Schuman						

(This space for State use only)

DAILY OPERATING REPORT

BALCRON MONUMENT FEDERAL #23-11
Location: NE SW Section 11, T9S, R16E
Duchesne County, Utah
2100' FWL, 1980' FSL
PTD: 5,750' Formation: Green River
Monument Butte Prospect
Elevations: 5,622' GL
Contractor:
Operator: Balcron/EREC
Spud: 8/30/93
Casing:

8-31-93 WELL SPUDDED 12:30 PM, 8/30/93

DAILY OPERATING REPORT

BALCRON MONUMENT FEDERAL #23-11
Location: NE SW Section 11, T9S, R16E
Duchesne County, Utah
2100' FWL, 1980' FSL
PTD: 5,750' Formation: Green River
Monument Butte Prospect
Elevations: 5,622' GL
Contractor:
Operator: Balcron/EREC
Spud: 8/30/93
Casing:

8-31-93 WELL SPUDDED 12:30 PM, 8/30/93

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

NAME OF COMPANY: EQUIT	ABLE RESOURC	CES ENERG	Y 43-	·013-313	69
WELL NAME: MONUMENT FE	DERAL 23-11			·	
Section11 Towns			16E	County_	DUCHESNE
Drilling Contractor	MOLIN		<u> </u>	·	
Rig #1					
SPUDDED: Date 8/30/9	3		,		
Time 12:30 P	<u>M</u>				
How_DRY_HOLE	<u> </u>				
Drilling will commence					
Reported by <u>AL PLUNKE</u>	TT				
Telephone # <u>1-823-</u> 675	9				
Date 9/2/93	sid	SNED	JLI	1	



1601 Lewis Avenue P.O. Box 21017 . Billings, MT 59104 Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361

August 30, 1993



DIVISION OF OIL, GAS & MINING

Bureau of Land Management 170 South 500 East Vernal, UT 84078

Gentlemen:

Enclosed are sundry notices reporting that we are changing the drilling rig from the way it is shown in the APD for the following wells:

Balcron Monument Federal #32-11 SW NE Section 11, T9S, R16E Duchesne County, Utah

Balcron Monument Federal #23-11 NE SW Section 11, T9S, R16E Duchesne County, Utah

Sincerely,

Bobbie Schuman

Coordinator of Operations,

Environmental and Regulatory Affairs

/rs

Enclosures

cc: Utah Division of Oil, Gas and Mining

Form 3160-5 (June 1990) UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED Budget Bureau No. 1004-0135 Expires: March 31 1993

		Expires:	March	31, 19	93
₹	1 0250	Designat	on and	Serial	No.

		U-096550
	AND REPORTS ON WELLS	6. If Indian, Allottee or Tribe Name
Do not use this form for proposals to dri	Il or to deepen or reentry to a different reservoir.	
Use "APPLICATION FOR	R PERMIT—" for such proposals] n/a
OUDLUT	IN TRIOLICATE	7. If Unit or CA, Agreement Designation
SUBMIT	IN TRIPLICATE	Jonah Unit
1. Type of Well		Jonah Unit 8. Well Name and No.
Oil Gas Other		
Name of Operator Equitable Resources Energy Con	mnany Ralcron Oil Division	Balcron Monument Fed. #23-11
3. Address and Telephone No.	ipany, butter on our bittisten	43-013-31369
P.O. Box 21017; Billings, MT	59104 (406) 259-7860	10. Field and Pool, or Exploratory Area
4. Location of Well (Footage, Sec., T., R., M., or Survey De		Monument Butte/Grn.River
NE SW Section 11, T9		11. County or Parish, State
1787' FSL, 2147' FWL	•	Duchesne County, UTAH
12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION	TYPE OF ACTION	
		Character William
Notice of Intent	Abandonment	Change of Plans New Construction
[V]	Recompletion	Non-Routine Fracturing
X Subsequent Report	Plugging Back Casing Repair	Water Shut-Off
Final Abandonment Notice	Altering Casing	Conversion to Injection
Final Adandonment Notice	x Other change in drlg. rig	Dispose Water
•		(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)
Operator will be using Unic layout (EXHIBIT "G"), BOPE	on Drilling Rig #17 to drill this well diagram ("H"), and Drilling Program ("D") are attached.
		SEP 0 1 1993
•	01-93	And the second second
	9-000	HOLA DIVISION OF
	JAY Jan	OIL, GAS & MINING
		2.1—, 2.11 - 1
	,	
14. I hereby ceptify that the foregoing is true and correct	Coordinator of Environmental	Date 8-30-93
Signed John Schuman	Title <u>and Regulatory Affairs</u>	Date
(This space for Federal or State office use)		
	Title	Date
Approved by Conditions of approval, if any:		
43-013-31369		

Equitable Resources Energy Company Balcron Oil Division

DRILLING PROGRAM

WELL NAME: Monument Butte Area

PROSPECT/FIELD: Monument Butte

LOCATION: Twn.98 Rge.16E & 17E

COUNTY: Duchesne

STATE: Utah

TOTAL DEPTH: SEE APD COVER SHEET

INTERVAL HOLE SIZE

0 to 260' 12 1/4" 7 7/8" 260 to T.D.

DIVISION OF OIL, GAS & MINING

CASING	INTERVAL	CA	ASING	OIL, GAS & MININ 	
STRING TYPE	FROM TO	SIZE	WEIGHT	GRADE	
Surface Casing Production Casing	0 260 0 T.I (All Casin	0 8 5/8" 0. 5 1/2" ng will be new,	24 #/Ft 15.50#/Ft ST&C)	J-55 J-55	
CEMENT PROGRAM	· – – د ده نت ب نت ب ب س نت ر				
Surface	1/4 #/Sk]	75% Class "G" 2 Flocele. will be circula			
Production	250 sacks mix.	Thifty Lite a	nd 400 sac	ks 50-50 Poz	

PRELIMINARY DRILLING FLUID PROGRAM

TYPE	FROM	TO	WEIGHT	PLAS. VIS	YIELD POINT
Air and air mist Air/Air Mist/KCl Water	0	260 T.D.	N.A.	N.A.	N.A.

depending on the drilling contractor either:

- a.) Drilling will be with air from surface to as deep as hoheditions allow. 2% KCl fluid will be used for the remainder of the hole.
- b.) Drilling will be done using 2% KCl water and gel.

COMMENTS

1.) No cores or DST's are planned.



BALCRON OIL DIVISION

1601 Lewis Avenue P.O. Box 21017 Billings, MT 59104

September 1, 1993



Office: (406) 259-7860 FAX: (406) 245-1365 [_] FAX: (406) 245-1361

DIVISION OF OIL, GAS & MINING

-- VIA FEDERAL EXPRESS --

Bureau of Land Management 170 South 500 East Vernal, UT 84078

Gentlemen:

Enclosed are sundry notices changing the drilling source water for the following wells:

Balcron Monument Federal #23-11

Balcron Monument Federal #32-11

We are changing the source from the Owen Dale Anderson source to the Joe Shields source.

To confirm a discussion with Stan Olmstead of your office, our records indicate that we have currently used the Joe Shields source on five wells. A total of 7,395 bbls water has actually been used. This breaks down as follows:

bbls used on five wells: 11,040
bbls reused: - 3,645
TOTAL NUMBER OF BBLS FROM SOURCE: 7,395

We have been able to reuse water from each well we drill which is allowing us to keep well under the allotted amount of 7000 bbls water per well.

Singerely,

Bobbie Schuman

Coordinator of Operations,

Environmental and Regulatory Affairs

/rs

Enclosures

cc: Utah Division of Oil, Gas and Mining

Form 3160-5 (June 1990)

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM APPROVED						
Budget Bure	cau No.	1004-0135	i			
Expires:	March	31, 1993				

	-	aget Dan	C44 1.0.		
		Expires:	March	31, 19	93
5.	Lease	Designat	ion and	Serial	No.

U-096	550
-------	-----

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT—" for such proposals

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

MII IN IRIPLICATE		
	7	11

Type of Wel	ıl		,	Jonah	Unit
N Oil	Gas	Other	8.	. Well Nam	ne and N

2. Name of Operator Equitable Resources Energy Company, Balcron Oil Division

3. Address and Telephone No. P.O. Box 21017; Billings, MT 59104 (406) 259-7860

4. Location of Well (Footage, Sec., T., R., M., or Survey Description) NE SW Section 11, T9S, R16E

1787' FSL, 2147' FWL

Balcron Monument Fed. #23-11 9. API Well No.

43-013-31369

10. Field and Pool, or Exploratory Area

Monument Butte/Grn.River

11. County or Parish, State

Duchesne County, UTAH

CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION								
X Notice of Intent	Abandonment	Change of Plans							
X Subsequent Report	Recompletion Plugging Back Casing Repair	New Construction Non-Routine Fracturing Water Shut-Off							
Final Abandonment Notice	Altering Casing Altering Casing Change in drilling	Conversion to Injection Dispose Water							
	water source	(Note: Report results of multiple completion on Well							

We plan to use Joe Shields water source for drilling this well. A copy of Permit #47-1674 (Application 57708) is attached.

SEP 0 2 1993

DIVISION OF OIL, GAS & MINING

Coordinator of Environmental Title and Regulatory Affairs Date Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

^{13.} Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

MCATION TO APPROPRIATE WATER

NOTE:—The information given in the following blanks should be free from explanatory matter, but when necessary, a complete supplementary statement should be made on the following page under the heading "Explanatory."

For the purpose of acquiring the right to use a portion of the unappropriated water of the State of Utah, for uses indicated by (X) in the proper box or boxes, application is hereby made to the State Engineer, based upon the following showing of facts, submitted in accordance with the requirements of

	aws of Utah.
1.	Irrigation Domestic Stockwatering Municipal Power Mining Other Uses
2.	The name of the applicant is Joe Shields
3.	The Post Office address of the applicant is Myton, Utah 84052
4.	The quantity of water to be appropriatedsecond-feet and/oracre-feet
5.	The water is to be used for Stockwatering & Other fromto
	(Major Purpose) (Month) (Day) (Month) (Day)
	other use period Irrigation from Apr. 1 to Oct. 31 (Minor Purpose) (Month) (Day) (Month) (Day)
	·
	and stored each year (if stored) from (Month) (Day) (Month) (Day)
6.	The drainage area to which the direct source of supply belongs is
	(Loave Blank)
7.	The direct source of supply is* Drain (Name of stream or other source)
	which is tributary to, tributary to
,	Photo Where water to be diverted from a well a tunnel, or drain, the source should be designated as "Underground Water" in the
firat i space may	space and the remaining spaces should be left blank. If the source is a stream, a spring, a spring area, or a drain, so indicate in the link, ; giving its name, if named, and in the remaining spaces, designate the stream channels to which it is tributary, even though the water sink, evaporate, or be diverted before reaching said channels. If water from a spring flows in a natural surface channel before being ted, the direct source should be designated as a stream and not a suring.
.8 266	The point of diversion from the source is in Duchesne County, situated at a point* t 900 ft. South 1100ft. from E½ Cor. Sec. 15, T4S, R2W, USB&M (3½ Miles SW of Myton)
*****	M. Lou Dina
• • • • • •	*Note.—The point of diversion might be located definitely by course and distance or by giving the distances north or south, and cast on
west at a diver	with reference to a United States land survey corner or United States mineral monument, if within a distance of six miles of either, or if greater distance, to some prominent and permanent natural object. No application will be received for filing in which the point of some is not defined definitely.
9.	The diverting and carrying works will consist of a collection ditch to place of use
10.	If water is to be stored, give capacity of reservoir in acre-feetheight of damheight of dam _
II. NE ½	If application is for irrigation purposes, the legal subdivisions of the area irrigated are as follows: SE ¹ ₄ Sec. 15, T4S,R2W, USB&M
	·

	Is the land owned by the applicant? Yes X No If "No," explain on page 2.
13.	Is this water to be used supplementally with other water rights? YesNoX
	If "yes," identify other water rights on page 2,
	If application is for power purposes, describe type of plant, size and rated capacity.
	If application is for mining, the water will be used in
	the mine, where the following ores are mined
16. in	If application is for stockwatering purposes, number and kind of stock watered 320 Cattle
•••••	NEWSEN Sec. 15, 145, KZW, USBAM If application is for domestic purposes, number of persons,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
•	If application is for municipal purposes, name of municipality.
	If application is for other uses, include general description of proposed uses 011 Field use
	If application is for other uses, metude general description of proposed uses
	Give place of use by legal subdivision of the United States Land Survey for all uses described in paragraphs 14 to 19, incl. Myton 011 Field in Pleasant Valley
21.	The use of water as set forth in this application will consume
	stream or source at a point described as follows:

EXPLANATORY

	tion:	e grande a company of the company	and the state of t		
					y, 199 errem <u>enter</u>
		,	ک جداد کمیشگری <u>دار دیدار دیدار با استوان به برای پستون می</u> ر	t Was and it was a second desired the second desired to the second	
. .		The state of the s			
		The state of the s	4.444	, , , , , , , , , , , , , , , , , , ,	
		95.5 x 6 x 7 x 7 x 7 x 7 x 7 x 7 x 7 x 7 x 7		A. C.	nan arin da makadarrajan jingg mjakasa bar manasa min na ma
	لِلْكُمْ الْمُنْ الْمُن	The state of the s			
					The same of the sa
	, 28:5	Startis	Charles and a Proper		
	• i • · · · · · · · · · · · · · · · · ·	is de la participa de la company de la compa			
		VI. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1.			
			AND THE PROPERTY OF THE PROPER	and or safely lightly i. S. 1985 Marrier	P. P. (19)
		anne de la	**************************************	The second secon	<u></u>
	1941-1971 - August 1981-1981			and the second s	
		N to 1		and manager of the second of the least of the second of th	20 may 20
					The same are the s
	u.a.	And the state of t			
	<u></u>				
	- All States			defecting that the state of the	and the second s
		PP MARK TO THE TAXABLE PARK TO THE TAXABLE PAR			
		. 6 apr. 674 - 177			
	and the second				
				And the second s	المعادمة المرابعين العادم والراحية الإسهامين المستند المستثنية ويستان والمستارة
		ستوريب ويسود وريد ورواد و داد د و ستند مدخور در استوريد		and the bits of the second second	
				and the second s	. d'16.
والمرابع والمرابع والمواوي والمواوي					
		24-5-24-6-5-4-V *** *******************************			
		and the second s			
		The state of the s		the second section is a second of the second	
والمعارض المناشف المساديات الأوار		and the second s		ما المراجعة المستقدمة المراجعة المراجعة المراجعة المراجعة المستقدمة المستقدمة المستقدمة المستقدمة المستقدمة	
		(Use page 4 if	additional explanate	ory is needed.)	which
	The quanti can	ty of water sought t be beneficially u	sed for the purpo	ted is limited to that, se herein described	***************************************
			·	Signature of App	A.
*If app	licant is a corpora	ation or other organized name of the partners	ntion, signature muship by one of the pa	it be the name of such courtners, and the names of , be filled in. If there is the Application,	poration or organize
ba listed. I	f a corporation or attorney, authoriz	partnership, the affi sing one to act for all	davit below need not , should accompany	the Application.	more than one appro
-					
	•	DECLAR	ATION OF CITIZ	ZENSHIP	
STATE OF	UTAH, VINTO	ah } **			
County of	1,44		. May	declared that he is a cit	lly appeared before
On the notary pub	lic for the State of	of Utah the above as	philip who, on oath	, declared that he is a citi	zen of the United S
or has decl	ated us intention	W. Kor		Meder Bal	1 1
W.,t	seinn synines	101 A W) , R	/	

STATE OF UTAH DIVISION OF OIL, GAS AND MINING ENTITY ACTION FORM - FORM 6

Equitable Resources Energy Company, OPERATOR Balcron Oil Division

OPERATOR ACCT. NO. N 9890

SEP 0 3 1993

ADDRESS P.O. Box 21017

Billings, MT 59104

DIMICIONI OF

		_		ISION OF							
ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER G	AS & MININGELL NAME	QQ	sc	WELL	LOCATIO RG	N COUNTY	SPUD DATE	EFFECTIVE
Α	99999	11518	43-013-31369	Balcron Monumnent Federal #23-11	NE SW	11	98	16E	Duchesne	8/30/93	8/30/93
Į	COMMENTS: Spud of ne	ew well.	Entity added	19-7-93 p			<u>I</u>	<u></u>			1
WELL 2 (COMMENTS:										
WEEL &	OMMENIS.										
WELL 3 C	OMMENTS:						* ****			<u> </u>	
				·	Ì	-					
WELL 4 C	OMMENTS:				_!!	7					1
WELL 5 C	OMMENTS:								1		· · · · · · · · · · · · · · · · · · ·
A - B - C -	– Establish – Add new we – Re—assign	new entity ell to exist	on back of form) for new well (sing ing entity (group existing entity)	gle well only) or unit well) y to another existing entity					Soblie of Signature Coordinator	Schum of Enviro	

D - Re-assign well from one existing entity to a new entity
 E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

DATE: August 31, 1993

Phone No. (406) 259-7860

1 (3/89)

EQUITABLE ENERGY COMPANY

BALCRON OIL DIVISION

1601 Lewis Avenue P.O. Box 21017 Billings, MT 59104 Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361

August 31, 1993

SEP 0 3 1993

State of Utah Division of Oil, Gas & Mining 355 West North Temple Salt Lake City, UT 84180 DIVISION OF OIL, GAS & MINING

Gentlemen:

RE: Balcron Monument Federal #23-11

NE SW Section 11, T9S, R16E

Duchesne County, Utah

Enclosed is our Entity Action Form along with a copy of the Federal sundry notice reporting spud of the referenced well.

Sincerely,

Bobbie Schuman

Coordinator of Operations,

Environmental and Regulatory Affairs

/rs

Enclosures

orm 3160-5 une 1990)

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM APPRO	OVED
Budget Bureau No.	1004-0135
Expires: March	31, 1993

Budget Bure	cau No.	1004-0135
Expires:	March	31, 1993

	Expi	res:	M	irch	31,	אאנ	٠,
case	Desi	enati	OR	and	Ser	ial	No.

		U-096550
SUNDRY NOTICES	AND REPORTS ON WELLS	6. If Indian, Allottee or Tribe Name
Do not use this form for proposals to dr	ill or to deepen or reentry to a different reservoir.	
Use "APPLICATION FO	R PERMIT—" for such proposals	
QÜDMIT	IN TRIPLICATE	7. If Unit or CA, Agreement Designation
•	in the close	Jonah Unit
Type of Well Oil Gas Well Other		8. Well Name and No.
Name of Operator		Balcron Monument Fed. #23-11
Equitable Resources Energy Co	mpany, Balcron Oil Division	9. API Well No.
Address and Telephone No. P.O. Box 21017; Billings, MT	59104 (406) 259-7860	43-013-31369 10. Field and Pool, or Exploratory Area
Location of Well (Footage, Sec., T., R., M., or Survey D		Monument Butte/Grn.River
NE SW Section 11, TS		11. County or Parish, State
1787' FSL, 2147' FWL	· -	Duchesne County, UTAH
CHECK APPROPRIATE BOX	(s) TO INDICATE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION	TYPE OF ACTION	
Notice of Intent	Abandonment	Change of Plans
	Recompletion	New Construction
Subsequent Report	Plugging Back	Non-Routine Fracturing
	Casing Repair	Water Shut-Off Conversion to Injection
LJ Final Abandonment Notice	Altering Casing X Other Spud of well	Dispose Water
	Other	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)
	12:30 p.m. 8/39/93 by Leon Ross Drill	ing.
•		Street Part Remarks &
•		SEP 0 3 1993
•		•
		DIVISION OF
•		OIL, GAS & MINING
•		
0		
. I hereby ceelify that the foregoing of true and correct Signed Status Status And Statu	Coordinator of Environmental Title and Regulatory Affairs	Dac Luguet 31, 1993
(This space for Federal or State office use)		V
Approved by	Title	Date
Conditions of approved to adj.		

Balcron Oil DAILY OPERATING REPORT

DATE

9-13-93

JONAH UNIT PARTNER' DAILY REPORT

BALCRON MONUMENT FEDERAL #13-5

--TIGHT HOLE--

Operator: EREC/Balcron

Location: NW SW Section 5, T98, R17E

Duchesne County, Utah

Prospect: Jonah Unit, Monument Butte

9-11-93 Completion

Csg vac psig. TIH w/BP retrieving tool, 1 jt 2-7/8" tbg, 5-1/2" HD packer, seat nipple & 2-7/8" tbg. Tag sand fill @ 4727' KB, RU to circ, clean out to 4869'KB. POOH & set packer @ 4581' KB. made 30 swab runs. last 4 runs 2% oil. Fluid level 3200' last 4 runs. No sand. Release packer, tag sand fill @ 4850' KB. Clean out to BP, release BP, Tooh w/tbg & btm hole assembly. SDFN. Load recovered 175 BOW, load to recover 659 BOW. DC: \$1,965

BALCRON MONUMENT FEDERAL #23-5 Opera

Operator: EREC/Balcron

Location: NE SW Section 5, T98, R17E

Duchesne County, Utah

Prospect: Jonah Unit / Monument Butte PTD: 5700' Green River Oil - Dev.

9-12-93 TD: 1,840' (1,246') Day 2

Formation: Green River MW 8.3 VIS 26 pH 10

Present Operation: Drilling

Drill, survey, clean & paint, & level derrick.

DC: \$15,050 CC: \$45,977

BALCRON MONUMENT FEDERAL #23-11 Operator: Balcron/EREC

Location: NE SW Section 11, T98, R16E

---TIGHT HOLE--- Duchesne County, Utah

Prospect: Monument Butte

PTD: 5750' Green River Oil - Dev.

8-25-93 Start location.

8-26-93 Work on location.

8-27-93 Finish location.

8-30-93 Move on Ross air rig. Spud 12:30 8-30-93. Drill 12-1/4" hole to 268'.

Balcron Oil DAILY OPERATING REPORT

DATE:

9/14/93

JONAH UNIT PARTNERS' DAILY REPORT

BALCRON MONUMENT FEDERAL #13-5

--TIGHT HOLE--

Location:

Operator:

EREC/Balcron

NW SW Section 5, T98, R17E

Duchesne County, Utah

Jonah Unit, Monument Butte Prospect:

Completion 9-13-93

CP - 75 psig. TIH w/1 jt 2-7/8" EUE, J-55, 8RD - 31.50'; 1 perf sub 2-7/8" x 3' - 3.20'; 1 seating nipple - 1.10'; 178 jts tbg 2-7/8" EUE, J-55, 8RD, 6.5# - 5532.38'; total - 5568.18' + KB 13' = 5581.18'. ND BOP, NU wellhead. TIH w/1 BHP, $2-1/2 \times 1-1/2 \times 16'$ BHAC W/ring plunger; six 1'x25' rods EL w/2-1/2 riton guides; 214 3/4"x25' rods grade D plain; two 3/4" x 6' pony; two 3/4"x4' pony; one 3/4"x2' pony; one 1-1/4 x 16' polish rod SM. Clamp rods off. RDMO.

DC: \$6,873

BALCRON MONUMENT FEDERAL #23-11

Operator: EREC/Balcron

Location: NE SW Section 11, T98, R16E

Duchesne County, Utah

Prospect: Jonah Unit - Monument Butte

PTD: 5750' Green River Oil - Dev.

TD: 476' (25') Day 2 9-14-93

Formation: Uintah MW 8.4 VIS 27 pH 9

Present Operation: WO parts.

Drill, pull main drum out of draw-works & sent to machine shop to

replace bearings.

DC: \$676

CC: \$24,442

Balcron Oil DAILY OPERATING REPORT

DATE:

9/15/93

JONAH UNIT PARTNERS' REPORT

BALCRON MONUMENT FEDERAL #23-11

Operator: Balcron/EREC

Location: NE SW Section 11, T98, R16E

Duchesne County, Utah

Prospect: Monument Butte

9-15-93 TD: 476' (0') Day 3

Formation: Uintah

Present Operation: WO repairs. DC: \$972 CC: \$25,414

BALCRON MONUMENT FEDERAL #22-5

--TIGHT HOLE--

---TIGHT HOLE---

Operator: EREC/Balcron

Location: SE NW Section 5, T98, R17E

Duchesne County, Utah

Prospect: Jonah Unit, Monument Butte Field

9-14-93 Completion

PU & RIH w/bit, scraper, & 2-7/8" tbg to PBTD. Circ hole clean w/160 STB 2% KCl wtr. TOOh w/2-7/8" tbg, scraper & bit. RU Schlumberger to perf. 1st run perf from:

4890', 4894', 4895' KB one shot each 4900', 4903', 4906' KB one shot each

5041', 5042', 5043', 5044', 5048' KB one shot each (total 10 shots) 90° phase.

Top gun did not fire, Tooh w/gun. 2nd run - rerun for top perfs @ 4890', 4894', & 4895' KB & Tooh w/gun. RIH w/tail jt 2-7/8" tbg, Model R=3 Backer packer, SN, & 2-7/8" tbg, set packer @ 4838' KB w/30,000# compression. RU Western to breakdown perfs above. Start puming, pressure to 2000 psig & csg annulus communicated, packer failed, reset packer @ 4838', pressure failure @ 800 psig, pull up hole & reset packer @ 4832' KB, pressure failure @ 700 psig. Tooh w/2-7/8" tbg, SN, Model R-3 packer, & tail jt. LD Model R-3 packer

& PU 5-1/2" Arrow HD packer. RIH w/tail jt, HD packer, SN & 2-7/8"

tbg. Set packer @ 4838' KB w/30,000# compression. SDFN DC: \$14,481

BALCRON MONUMENT FEDERAL #23-5

Operator: EREC/Balcron

Location: NE SW Section 5, T98, R17E

Duchesne County, Utah

Prospect: Jonah Unit, Monument Butte

9-15-93 TD: 4,010' (540') Day 5

Formation: Green River MW 8.4 VIS 26 pH 10

Present Operation: Drilling

Drill, survey, trip for bit #2. Drill ahead.

DC: \$7,673 CC: \$75,845

Balcron Oil DAILY OPERATING REPORT

DATE 9/16/93

JONAH UNIT PARTNERS' REPORT

BALCRON MONUMENT FEDERAL #13-5 EREC/Balcron Operator:

--TIGHT HOLE--NW SW Section 5, T98, R17E Location:

Duchesne County, Utah

Jonah Unit, Monument Butte Prospect:

9-15-93 Completion

Reserve pit restoration. Start surface equipment hookup.

DC: \$13,074

BALCRON MONUMENT FEDERAL #23-5 Operator: EREC/Balcron

Location: NE SW Section 5, T98, R17E

Duchesne County, Utah

Prospect: Jonah Unit, Monument Butte

9-16-93 TD: 4,649' (639') Day 6

Formation: Green River MW 8.4 VIS 27 pH 10

Present Operation: Drilling

Drill, survey, clean & paint. Unload rest of 5-1/2" csq.

CC: \$84,259 DC: \$8,414

BALCRON MONUMENT FEDERAL #23-11 Operator: Balcron/EREC

Location: NE SW Section 11, TSS, R16E

Duchesne County, Utah

Prospect: Monument Butte

TD: 476' (0') Day 4 9-16-93

Formation: Uintah

Present Operation: Repair rig.

DC: \$400 CC: \$25,814

BALCRON MONUMENT FEDERAL #22-5 EREC/Balcron Operator:

--TIGHT HOLE--SE NW Section 5, Tos, Ri7E Location:

Duchesne County, Utah

Prospect: Jonah Unit, Monument Butte Field

9-15-93 Completion

---TIGHT HOLE---

CP - 40 psig, TP - 0 psig. RU Wetern to break down. Pressure test surface equip to 5000 psig - OK. Initial break 3100 psig to 2400 psig @ 4 BPM, start ball. Balls on perfs. Ball off, surge balls back, pump for rate 6 BPM @ 3000 psig, ISIP - 1500 psig. w/tbg & packer. RU Western to frac, pressure test surface equip to 6000 psig - OK.

	<u>Max Rate</u> <u>Max PSI</u>	BOS	
Pad	10.8 3000		1600 ISIP
Sand #2 20/40	Shut frac down	13	
3# 20/40	Will acidize	14	
4# 20/40	9-17-93	41	
5# 20/40		58	
6# 20/40		61	
6# 16/30		45	
7# 16/30	Load to rec 128 BOW		
8# 16/30		32	
Flush		116	
DC: \$13,142			

Balcron Oil DAILY OPERATING REPORT

DATE:

9/17/93

Jonah Unit Partners' Report

BALCRON MONUMENT FEDERAL #23-11

Operator: Balcron/EREC

Location: NE SW Section 11, T98, R16E

Duchesne County, Utah

Prospect: Monument Butte

9-17-93

--TIGHT HOLE--

---TIGHT HOLE---

TD: 1,825' (1,349') Day 5 Formation: Green River MW 8.3 VIS 27 pH 11

Present Operation: Drilling

Repair rig, drill, survey, & clean on rig.

DC: \$19,986

CC: \$42,800

BALCRON MONUMENT FEDERAL #23-5

Operator: EREC/Balcron

Location: NE SW Section 5, T98, R17E

Duchesne County, Utah

Prospect: Jonah Unit, Monument Butte

9-17-93 TD: 5,215' (566') Day 7

Formation: Green River MW 8.4 VIS 26 WL 10.5

Present Operation: Drilling Drilling, survey, clean & paint. DC: \$8,885 CC: \$93,144

Balcron Oil DAILY OPERATING REPORT

DATE:

9/21/93

Jonah Unit Partners' Daily Report

BALCRON MONUMENT FEDERAL #32-11 --TIGHT HOLE--

Operator: EREC/Balcron

Location: SW NE Section 11, T98, R16E

Duchesne County, Utah

Prospect: Jonah Unit, Monument Butte Field

9-20-93 Completion

---TIGHT HOLE---

CP -0. TIH w/5-1/2" HD packer, set packer @ 5105' KB. RU Dowell to do breakdown. Pressure test surface equipment to 4500 psig -OK. Start breakdown, initial break @ 1500 psig, back to 1100 psig. Start balls, 2 balls per bbl, ball off, surge back. Pump for rate 6 BPM @ 1700 psig, ISIP - 590 psig. RD Dowell. Load used 64 BW. Unset packer & TOOH w/tbg & packer. RU Dowell to frac (frac tank ruptured), replace tanks. Pressure test surface equipment. Frac well w/43,460# 16/30 sand; ISIP 1635, 5 min 1490, 10 min 1425, 15 min 1350. Averate rate 20 BPM, average psi 1800 psi. SDFN. see Treatment Report attached - 2 pages.

DC: \$21,860

BALCRON MONUMENT FEDERAL #23-11

Operator: Balcron/EREC

Location: NE SW Section 11, T98, R16E

Duchesne County, Utah

Prospect: Monument Butte

9-21-93 TD: 5,507' (567') Day 9

BALCRON MONUMENT FEDERAL #23-11

Operator: Balcron/EREC

Location: NE SW Section 11, T98, R16E

Duchesne County, Utah Prospect: Monument Butte

---TIGHT HOLE---

9-18-93

TD: 3,118' (1,293') Day 6 Formation: Green River MW 8.4 VIS 27 pH 10.5

Present Operation: Drilling Drill, survey, & clean on rig.

DC: \$16,322 CC: \$59,122

9-19-93 TD: 3,956' (838') Day 7
Formation: Green River
MW 8.4 VIS 27 pH 10.5
Present Operation: Drilling

Drill, survey, change airhead rubber.

DC: \$10,931 CC: \$70,053

9-20-93 TD: 4,940' (984') Day 8
Formation: Green River
MW 8.4 VIS 27 Ph 10.5
Present Operation: Drilling
Drill, survey & clean on rig.
DC: \$15,461

CC: \$85,514

BALCRON MONUMENT FEDERAL #23-5

Operator: EREC/Balcron

Location: NE SW Section 5, T95, R17E Duchesne County, Utah

Prospect: Jonah Unit, Monument Butte

9-18-93 TD: 5,800' (585') Day 8
Formation: Green River
MW 8.4 VIS 26 pH 10.5
Present Operation: Circ for logs.
Drill, survey, grill steaks & circ for logs. TD 4:45 a.m. 9-18-93.
DC: \$7,882 CC: \$101,026

9-19-93 TD: 5,800' (0') Day 9
Formation: Green River
Present Operation: Cementing
Circ, TOH for logs. Log Well, TIH & circ. LD drill pipe & collars. Run 5-1/2" csg & cmt w/Western. Guide shoe - .70', 1 jt 5-1/2" 15.5 K-55 shoe jt - 44.41', float collars - 2.45', 133 jts 5-1/2" 15%, K-55 pipe 5713.01', landing jt - 12'. Set @ 5772.57'.
PBTD - 5725.01'. 20 centralizers. Cmt by Western w/154 Exs Thirfty lite & tail w/258 sxss 50-50 POZ. Plug down @ 6 a.m. 9-19-93. Release rig @ 10 a.m. 9-19-93.
DC: \$60,480 CC: \$161,506

9-20-93 TD: 5,800' (0') Day 10
Present Operation: RDMO
Nipple down BOP, set slips, & clean mud tank.
DC: \$1,100 CC: \$162,606

Balcron Oil DAILY OPERATING REPORT

DATE:

9/22/93

Jonah Unit Partners' Daily Report

BALCRON MONUMENT FEDERAL #22-5

Operator: EREC/Balcron

Location: SE NW Section 5, T98, R17E

Duchesne County, Utah

Jonah Unit, Monument Butte Field Prospect:

Completion 9-21-93

--TIGHT HOLE--

TIH W/1 jt 2-7/8" tbg - 29.95'; 1 perf sub 2-7/8" - 3.2'; 1 seat nipple - 1.10'; 166 jts 2-7/8" tbg EUE, J-55 - 5076.45: landed at 5089' KB. ND BOP, NU wellhead. TIH w/1 BHP 2-1/2 x 1-1/2 x 16' RHAC w/PA plunger; 202 rods 3/4" x 25' plain; one 3/4" x 8' pony; two 3/4" x 6' pony, one 1-1/4" x 16' polish rods SM. Clamp rods off. RDMO.

DC: \$7,000

BALCRON MONUMENT FEDERAL #32-11 --TIGHT HOLE --

EREC/Balcron Operator:

Location:

SW NE Section 11, T98, R16E

Duchesne County, Utah

Prospect: Jonah Unit, Monument Butte Field

Completion 9-21-93

Csg vac. TIH w/5-1/2" packer & tbg. Tag sand fill @ 5513' KB. Set packer @ 5105'. Made 5 swab runs, packer leaking. Reset packer @ 5074', made 3 swab runs, packer leaking. TOOH w/tbg & packer. TIH w/1 jt 2-7/8" tbg, one 5-1/2" packer & 2-7/8" tbg, set packer @ 5105' KB. Made 16 swab runs. Recovered 126 BF, last 2 runs 2% oil. SDFN. Load to recover 450 BW.

DC: \$5,543

BALCRON MONUMENT FEDERAL #23-11

Operator: Balcron/EREC

Location: NE SW Section 11, T98, R16E

Duchesne County, Utah

Prospect: Monument Butte

---TIGHT HOLE---

9-22-93

TD: 5,750' (243') Day 10 Formation: Green River MW 8.4 VIS 27 pH 10.5

Present Operation: RU loggers.

Trip for bit, drill, circ for logs, survey & TOH.

CC: \$98,694 DC: \$5,175

Balcron Oil DAILY OPERATING REPORT

DATE:

9/23/93

JONAH UNIT PARTNERS' REPORT

BALCRON MONUMENT FEDERAL #13-5 --TIGHT HOLE--

Operator: EREC/Balcron

Location: NW SW Section 5, T98, R17E

Duchesne County, Utah

Prospect: Jonah Unit, Monument Butte

9-22-93 Completion

Pit reclamation. Continue to hookup surface equipment.

DC: \$2,662

BALCRON MONUMENT FEDERAL #22-5 --TIGHT HOLE--

Operator: EREC/Balcron

Location: SE NW Section 5, T98, R17E

Duchesne County, Utah

Prospect: Jonah Unit, Monument Butte Field

9-22-93 Completion

Start reclamation of pit. Start surface equipment hookup.

DC: \$12,201

BALCRON MONUMENT FEDERAL #32-11 --TIGHT HOLE--

Operator: EREC/Balcron

Location:

SW NE section 11, T98, R16E

Duchesne County, Utah

Prospect: Jonah Unit, Monument Butte Field

9-22-93 Completion

---TIGHT HOLE---

CF - 50 psig. Made 8 runs, recovered 38 BF, 7 oil - 32 wtr. Release packer, RIH, tag sand fill @ 5497' KB. Circ clean to 5711' (PBTD). TOOH w/tbg & packer. RU Cutter Wireline to perf 4740'-4744' 2 SPF. RD Cutters Wireline. TIH w/5-1/2" BP set @ 5063' KB, 5-1/2" HD packer set @ 4667' KB. SDFN.

DC: \$7,027

BALCRON MONUMENT FEDERAL #23-11

Operator: Balcron/EREC

Location: NE SW Section 11, T9S, R16E

Duchesne County, Utah

Prospect: Monument Butte

9-23-93 TD: 5,750' (0') Day 11 Formation: Green River

Present Operation: RDMO

Log well, had to run Density log over. TIH & circ, LD drill pipe & collars. Run 5-1/2" csg & cmt. ND, set slips & clean mud tanks. Plug down @ 2:30 a.m. 9-23-93. Rig released @ 6 a.m. 9-23-93. Csg: Guide shoe .75'; 1 jt 15.50 shoe jt - 44.19'; float collar - 2.65'; 135 jt 5-1/2" 15.5# K-55 - 5174.08'; landing jt - 9'; Csg set @ 5730.67'. PBTD - 5683.08'. 20 centralizers. Cmt'd by Halliburton w/90 sxs hifill & tail w/350 sxs 50-50. Plug down @ 2:30 a.m. 9-23-93.

DC: \$63,363

CC: \$162,057

OPERATOR Balcion Oil	
ADDRESS P.O. BOY 21017	
Billings mt 59104	

Phone No. (404) 259-78(00)

CODE ENTITY NO. ENTITY NO.	API NUMBER	A C WELL NAME		UELL AG			,	
0 11492	31369	Cont	QQ SC	WELL LO	RG RG	COUNTY	SPUD	EFFECTI
C 11518 11992	43013	M. Butte 23-11	NE			COUNTY	DATE	DATE
HELL 1 COMMENTS:	· · · · · · · · · · · · · · · · · · ·	1111 100000 23-11	5W 11	95	166	Duchesne	8-30-93	8/,/
~		Entrines added 9-2493. D			<u> </u>	Ducines ja	150 15	11/9.
Jonah	Unit	Entropies added 9-24-93. L	3					
C 1150 11492		A. F.						
- 11912 H 2H	43013 31386	M. Butte 32-11	SW ,					
ELL 2 COMMENTS:			NE	95/1	6E	Duchesne	8-27-93	8/10
Jonah Unit					·	700.00	00101	11/9
Jonan Unit								
		Walter	Billing					
								
LL 3 COMMENTS:					.	1.	-	
		SEP	2 3 1993					
		UIVIS	ON OF					
		OIL, GAS	& MINING					
LL 4 COMMENTS:					_	1	}	
	T							
					T			
L 5 COMMENTS:		·		<u> </u>				
	•		•					
ION CODES (See instructions on A - Establish new entity for	back of form							
B - Add now well to	new well (sing)	e well only)						
B - Add new well to existing C - Re-assign well from one D - Re-assign well from one E - Other (explain in commen	, encicy (group o	r unit well)			7 :	Dawn s	Schind	los
· D Po-300i 33 6	and a sure of the	to dilliner existing entity			Si	onature.		

NOTE: Use COMMENT section to explain why each Action Code was selected.

(3/89)

Balcron Oil DAILY OPERATING REPORT

DATE

9/30/93

JONAH UNIT PARTNERS' REPORT

BALCRON MONUMENT FEDERAL #23-11 Operator:

Balcron/EREC

BOD WI: 79.78%

Location: NE SW Section 11, T98, R16E

---TIGHT HOLE---Duchesne County, Utah

Prospect: Monument Butte

9-29-93 Completion

Csg - vac psig. TIH w/BP retrieving head, 1 jt 2-7/8" tbg, packer, SN & 162 jts 2-7/8" tbg. Tag sand fill @ 5095' KB. Circ sand out ot BP, set packer @ 5095' KB. Made 22 swab runs, recovered 79 BF, 1 all, 78 water. Last 3 runs stable @ 5050, oil trace. SWIFN. Load to recover 542 BW.

DC: \$19,679

BALCRON MONUMENT FEDERAL #14-11 Operator: Balcron/EREC

BOD WI: 100%

Location: SW SW Section 11, T98, R16E

Duchesne County, Utah Prospect: Monument Butte

---TIGHT HOLE---

9-30-93

TD: 5,720' (0') Day 7 Formation: Green River MW 8.6 VIS 30 pH 10

Present Operation: Circ 5-1/2" csg. Finished logging #1 DIL-MSFL-GR, #2 - LDT-CNL-GR, #3 - RFT-GR. TIH, circ & cond to run 5-1/2" csg. LD string, run 5-1/2" csg. Ran 132 jts new 15.5#, K-55, R-3, 8RD LT&C csg - 5687.92 @ 5699.92

KB. PBTD @ 5663.56' KB. 132 jts 5687.921 Guide Shoe 1.00' Float Collar 1.00' Ria KB 10.00' 5699.92' KB

Shoe Jt - 36.36' PBTD 5663.56' KB

Cmt'd w/136 sxs "G" + additives. Tailed w/206 sxs 50-50 POZ +

additives. Displaced w/134.8 bbls fresh water.

DC: \$53,875 CC: \$155,404

...

Page 1 of 1

Balcron Oil DAILY OPERATING REPORT

DATE: 9/29/93

---TIGHT HOLE---

JONAH UNIT PARTNERS' REPORT

BALCRON MONUMENT FEDERAL #14-11 Operator: Balcron/EREC

BOD WI: 100%

Location: SW SW Section 11, T9S, R16E

Duchesne County, Utah

Prospect: Monument Butte

9-29-93 TD: 5,720' (660') Day 6 Formation: Green River

MW 8.6 VIS 30 pH 10

Present Operation: Logging

Drill & survey. Drilled to 5721' @ 9:30 p.m. 9-28-93. Circ & cond

hole. TOH to log, strap out.

DC: \$10,868 CC: \$101,529

BALCRON MONUMENT FEDERAL #23-11 Operator: Balcron/EREC

BOD WI: 79.78%

Location: NE SW Section 11, T98, R16E

Duchesne County, Utah

Prospect: Monument Butte

BALCRON MONUMENT FEDERAL #23-11

9-27-93 Completion

---TIGHT HOLE---

Completion
MIRU, TIH w/4-3/4" drag bit, 5-1/2" scraper & 182 jts 2-7/8" EUE,
J-55 tbg. Tag PBTD @ 5671' KB. Circ hole clean w/2% KCL wtr, TOOH
W/tbg & tools. RU Schlumberger to perf 5155'-5162', 5171'-5181' KB
2 SPF. RD Schlumberger. TIH w/5-1/2" BP, 5-1/2" packer & 165 jts
2-7/8" tbg, set BP @ 5204' KB, set packer @ 5167' KB. RU Western
to break down pressure test surface equipment to 5000 psig - OK.
Start break down, initial 1600 psi, back to 800 psi, 2 BPM.
Communicated between perfs, reset packer @ 5122' KB. Start break
down initial break 1000 psi, back to 800 psi, 2.5 BPM. No ball
off, ISIP - 800 psi. Pump for rate 6.6 BPM @ 2200 psi, ISIP 800.
BDFN. Load to recover 124 BW. see treatment report attached.
DC: \$18.068

9-28-93 Completion

Csg vac, tbg vac. TOOH w/tbg & packer. RU Western to frac. Pressure tets surface equipment to 4000 psi - OK. Load hole 66 bbls, fluid level. Frac well using 28,200# 20-40 sand & 29,180# 16-30 sand. Average treating rate 25.1 BPM, average treating pressure - 1800 psi. See treatment report attached.

DC: \$22,368

BALCRON MONUMENT FEDERAL #23-5

Operator: EREC/Balcron

BOD WI: 79.78%

Location: NE SW Section 5, T9S, R17E

Duchesne County, Utah


Prospect: Jonah Unit, Monument Butte

---TIGHT HOLE---

9-28-93 Completion

CP - 795 psi. Flowed back 70 BW. TIH w/1 jt 2-7/8" tbg, 5-1/2" packer, SN, 177 jts tbg. Tag sand fill at 5505', circ to 5726', set packer 5426', EOT 5464'. Made 38 swab runs, recovered 228 BF. Last 4 runs fluid stable @ 3600', 5% oil, good gas. SWIFN.

DC: \$1.787





,							···								7
Date	<u> «تد-جي</u>	<u>· 93 </u>	_Distric	1 1/2	1.11.7	F. F	Receipt	داراتهم	029		Operato	v 3		**	.67.
														C	
Coun	A TOPTER	- 100	21816	<u></u>	+	Sta	ge Num	ber 🙎			This Zo	ne 🔯	This	Well (3
WELL	DATA	OGD N	GD I	NOD.	OOD V	/na	18 <i>870</i>	Mar M	Charact 1	TO .O.					
Casin	Size _	5.5	WT. 🔟	55	Set From	Sint	ra.	o 7	<u> </u>	lype Ider	- Ciat - Ciat	<u> </u>	\$ 9	At	
Liner !	Set From ,	·	To	Op	en Hole: S	ize		From	-22	To	William Party State	Casing F		nne: Gir	16 472
Pigles	Per Foot	****	li	ntervajs	<u> </u>	7 -	. 51 <u>%</u>	1 3	y Ci	آم/يا	17	weeling i	SI (A) MI) 113. 312	(e <u>(U)</u>
L: 440	us ireaim	16M	and the state of t	ALK.	The last of the la	Parameter in the second	rior Pro	duction_		10					1.0 db.m.pg.pg.cza
Control of the second	the state of the s	667.8535/5					فالمتابع والمتابع					· · · · · · · · · · · · · · · · · · ·	8882400000		edinio philosoposopos
			auno mi	uid IVn	Not Pad	Minimal	W A 4:45) ^\			4.		101111111111111111111111111111111111111	D/C/AE	PUMPED AN LES IN BBLS.
															ES IN BEL 3.
													Tubing	Cap.	
,,== .	Shar amili	##1 717 `	۷ (سوا	7F-JL	BAUX.L	(Jiha	1 -2/1/			20	ماد			Cap.	1000
													Annula	r Cap.	
4 4 miles (F)	mercand till	11			1 1 4 4 4 1	1/16: Tu	ikiaa 🗂		Ani	il.Q	Tubing !	Anul.	Fluid to	Load	4. <u></u>
													ILSO AC	Nume	127 %
a ypveilini Allvilini	eniu ivunc u Mataria	MIDIMUM Maria	ps U\$⊕(∕\~	<u>. ت</u> ۍ د	1300 7 n	^		كلاردني				and desired to the second	Treatin	g Fluid	3&డ
, 100 Pt. 177 [Aj	7 113 E 1 E 1 7 C	· · · · · · · · · · · · · · · · · · ·	* CAC-	hard are	ونه		, , , , , , , , , , , , , , , , , , ,						Oveq!	sh	31
PROG	BOURE				·			A Partition in the same	.		-		Fluid to	Recov	er 507
	VARY			.,,					***************************************	 - ·	······································		TOTAL N	ř	Gina
		.,5			in Bull in Annyag pi Name		,, 						i ciai C	O ₅	rice came - merencularis
Tims	Tressing Pr	rossure-Pài		face BBLS.	Sturry Rate	Şu	riace	CO, Raje	Surfa		Nº Rate		<u> </u>		
M/PM		A		rped	BPM	Put	BBLS. Mped	ВРМ	Nº MS Pump		SCFM		•	ommenu	;
.,	419	Annulus	Stage	Total	-		Total		Stage						78700
1.37	=	- .				j					Charles and the state of	Town /		يحراره ف	シアヘセ
43				٥	17.0				-	* * * * * * * * * * * * * * * * * * *	A Company of Party and Par	5 (2,	A Par		
7.18	2090 2110	White property	<u>-</u>	-//-3	25_0			And the same of th				<u>\$</u> √61	+ 2 1	<i>و سر</i> د	Luc
180	2/30	e 		135 158	25.1 25.L			Artista el terra y escuespay.	· —				4 3	ز سر	Eufer.
101	2220	****		2160	25				 			ينا جي	<u> </u>	*	2.1.10
1.53				277	25 /							<u>→</u> *•	1 1 0	7 <u>7</u>	3 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
-35	1690			327	- Z- L	7						4	4 620 4 620		1/2-
57	1660		A Water has a placed as	2/4								54a.	7	el /	4/10
	1670			507	Z5 2		-		Mirror Charles Street	.		5,40,	1 61	17313	
					25.7-						·	tade.	Dur		5 y chart
$- \mathbb{I}$										 F	-	<i>-</i>			*
					**************************************	redking.					\-\- -		٠, ٨,	<u>'5")</u>	}
-												/0 / /		14/60	
	··········											147,	4.74	-/43	ů
								mada at the test of the purpose, the							
		· ·											and his day that had shaded be spe		
											 -		-		* '
eating	Pressure:	Min.	(651)		ير . Max		Avo.	· / ይ/አ/ን		Cirate.	mar B	A B A A 4 - 4 !		,	
															it for
<u> </u>					, , , , , , , , , , , , , , , , , , , ,	∠ F*(U.%)	11 LANGE	10 /09	X 44 1	1164711	ution Ution	一点 マイ・・ジャー		t Indies at	25/
(AMDI MAILIA	முரார் (ஹ.ஜ.ஜ .	W: W	- ·/.	22	147	· 1100 Page 2 14 12	<u> Μ</u>	nutes	* 1		-+/WIL W	<u> Zirikili Vi</u>	7/1	77.	
erator	s Maximu	m Pressur	0	<u> </u>	PSI			FMX+112/44					\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	**************************************	#1. T
Job N	A . In the district of the same of the sam			•	-										,
1916 1880		Hecomm	endalio	n ID#_	* i		marina in the same of the same						··· •· ••· ••		

The Western Company—Treatment Report

			·										
Date	2-2	<u>/-93</u> p	istrict _	يو بيول ا	· Apple	F, F	Receipt	<u> 261'</u>	235		Operator	<i> :A</i> _	CNOW
											Location.		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
County	Ourbie	3.4 <u>-</u> 8	iale _	_15)	\$ta	ge Nun	nber			This Zone	Æ	This Well 💆
									ستربي فالتساكيب إما				
WEIT	SATAL O	GO NGI		ם מכ	00 1	NDO	IWD	Misc.D	Depth	TO/PB		Formation	
	T	ubled Size	77	6 V	VT /	•	Set	at: .57	22	Type	Packer		Set At
A	ا ابتاستان اع دونه	14.1 E			'''	. ان		TA *1	P ~')	liner	Size		Wt.
Casing	<u>. ت. </u>		· <u> </u>	ت. <u>. ور</u>	MAK LIGHT	<u>```````````````````````````````````</u>	<u> </u>			TA		neigo De	forstions: Size
Liner Se	et From			Obe	n Moje: :	5/2e	. *** /	rom		,,1U		watta o	forations: Size
Holes P	er Foot		int	ervals "	ا	<u> </u>	15_/	13131					,
Previou	s Treatme	Λt	MI	<u>{</u>		***	Prior Pr	oduction		<u> </u>	**************************************		112
						· · · · · · · · · · · · · · · · · · ·		1.0			,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		
	VENT DA	A Pad (lead.	Yes D	do b / Pa	d Type		-	•				LICUIDIGAS PUMPED AND
IT/#AII	VEN! PA	Treat	yφφφ, in= Eliz	id Turk	· Enami	TI Water	M Asid	<u>л </u>	Treat F	luid Vol	1 11 11 11 11 11 11 11 11 11 11 11 11 1	Gal	CAPACITIES IN BBLB.
Median Statement		1/98)	ILIO LID	ig i Aba	. ("Wan)	M AAGTA:	داددئ≈ داددئ≈	- i - i	11/20/444	- 1010-101	 		
Base F	uid Type "	27	\mathcal{L}	Ch_	· · · · · · · · · · · · · · · · · · ·		riują vi	OI		<u> </u>		Qq;,	Tubing Cap.
Foam C	}∪al.:	% Mit	chell□	Slurry	O Surf	ace[]	Downho	oT Delc	ial Prop	Qty		Lbs.	Casing Cap.
Prop TV	oe: Sand	□ WP-1	0 W	P-3D	Baux.C) Oth	er						Annular Cap.
D 14	ant Cines	Tumbe ser	1 Auton	iliae		-							Open Hole Cap.
Linia i a	AND THE STATE	. 'ypub ai'.' ' ン .	4		Tros	i Viar T	ubled	Casi	naC) A	\nul.□	Tubina &	Anul.D	Fluid to Load
LIONA CO	SOBO AAITI			-	4	Diames	. 4 W 11 12 SE				,		Pad Volume
Ball Se	alers:	<u> </u>	- iU			ខានពិសភ	্র —	_3/		- H		4	Treating Fluid
TAbes :	Kirinaki Diji	קונוט 17 19 ול ה	o Venu					تنتسب	حيدي /-				riusn
Auxiliar	y Material:	<u>ئــــــــــــــــــــــــــــــــــــ</u>	<u>o c</u>	AUS		J. S	<u>ي د .</u>	- 4	2		- k		Overflush
													Fluid to Hecover
20500	DURE	OKAN	Bull	le ile	Xch	EL	den	70 B	Maun	286	<u> </u>		Total N ²
0.000	State of the latest and the latest a			A Paris Company of P. 1						,			Total CO ₂
SUMI	AARY.			· · · · · · · · · · · · · · · · · · ·		nvir W		**********	·····				
1000000 p			Bite	ace	Slucry	Śúr	face	00.0-1	Su	ia ca	N' Rate	ľ	
Time	Treating Pr	essure-Pei		BBLS.	Rate		BBLS.	CO, Rate		ASCF			Comments
AMOD	*	Ì		1ped	BPM	Púr	nped	MAB	Pur	nped	SCFM	}	
	STP	Annulus	Stage	Total		Suge	Total		Stage	Total			
6:22	6000	· · · · · · · · · · · · · · · · · · ·		44.6			,					PKAS	succ iosi
				94 ph	H.#			7	7	7	7	مام	
		- -/		14	حد	~ f	1	<i> </i>	 / 	1/	17		
777	/ CO()	- 		12.5		\ /	 	f.v	-/-	 	1		BKCeK DOWD
6:32	1500		- -	100	30./	 	╁	 	 - 	-{- -/	++		DIUNI COMIMENTAL
6.36	1500				5.0	 	╫┈┈		+/-	{ <i>{</i>	++		
<u> </u>	1000			100	<u>, , , , , , , , , , , , , , , , , , , </u>	\	.∤.↓	 	┼╀─ ┈		┿┷┈	LETAKT	Titelion Tos7
655	500						1	<u> </u>	17	Ц		12 15 T.	Is soorst Bolls
658	1000			30.5	4.0	<u> </u>	<u> </u>	17	11-	 		_574K	1. 154/15
705	1200	\		***	****	<u> </u>	$\perp \lambda$			17		BALL	sou Pere:
714	7800			37.0	4.0	1			1			Shu	TODOW SAKO BAILS
1721					6.6					1"\		STAK	T RATE TEST
1.23	27,20,200			<u> </u>		1	1"7		 				
-				 		† <i> </i>	 	 	 	1	· · · · / · ·	'	
			 	 		† 	 	 	-	+ +		-	
				-	rm 197 12 \$ 1100 mm	 /	 	<i> </i>	 / -	 	- /	-	
<u></u>	 				 	 		 	+/	/-	 		
					<u>'</u>	<u> </u>		 	₩	\ 		·	i ·
						1	11-			1./	· 		· · · · · · · · · · · · · · · · · · ·
				<u> </u>	. 44,500		 	1-1-	11	11	 - - - - - - -	 	
7]			<u> </u>	l							1	
		T	1]]"	1	1 1	1					
	J		<u>, 1 </u>		j.,	- de	**************************************	- Artin		_			De Daria
Treating	g Pressure	e: Min	100	<u>a</u>	_Max	2200	Av(). <u>L 8</u> 5	20	ǵ:	stomer Rep	presentati	VO DALE BRIFFIELD
Inj. Rat	e on Treat	ing Fluid		4.0			Rate on	Flush	4.0	We	ștern Repr	esentativ	A KOX CHWARES
Ava In	Rate	9.0		1.8.1) P. Ø	ו ניש	Flush f	ens. ih./	cal P.	Die	tibution		Taule
Sinal O	hurda Bee	COLUMN TARREST	ه بنداد م معاملات	,,,,,,,,	میکنده مرا	£	(P#)	Minute	a ••				1
Cinal S	rigit III F188	sure um Pressi	- 	LI A	_{11	The state of the s						and a feet of the feet of the same	
Operati	or's Maxim	um rressi	ir 6		<u> دے تر</u>	ian der den en							** *** *** ** *** *** *** *** *** ***
ه المستقد الم	Market Control of the												



The Western Company—Treatment Report

Date	9-21	1-93 p	istrict _	Uek.	unt.	F. F	leceipt	2619	235		Delator _	_[]A_	1CKOLL 1/1/2
Lease _	CACKA	<u>L</u> V	√ell No.	23:	1/3	Field	d <u> <i>P7.</i></u>	<u>BASALI</u>	Ual	'•9 -	ocation_1	<u> </u>	1 1 95 13. 16C This Well \$
County	Duche	<u> </u>	late			Stag	3e Iyum	ber	/	· · · · · · · · · · · · · · · · · · ·	IIIS ZONA	<i>y</i> u	11115 11011 /2
		0m NO		\C \	OD V	VDD	IWO	Misc D	Depth	TD/PB	F	ormatio	n
300000000000000000000000000000000000000	98933933 🕨 🖛	L	0 "	87 1A	it /	ζ.	SAL	at: '.\ / d		IADAL	ackei		361 VI
	. ~	pr 111	· / /	~ ~	-1	C	<i>a</i> 7	آم <i>ال</i> آ	' <i>1</i> ')	Liner S	128		W
Filler 26	or goot It Libiti ""		lot	Opoi		2 13/1	15 /	13/3)		A115			
Provious	errout _	ntTo	NI	/ /	······································		Prior Pro	oduction	N	14			
													MARINDAN DUMPEN AN
TOFATE	MENT DA	TA Pad	Used: \	Yes□ N	lo Pa	d Type_		-					LIQUID/GAS PUMPED AN
200		Tras	tina HIII	IN I VOA:	י והמאחוו) vvater	MI ACIUI		Treat. Fl	uid Vol.	LA	Gal.	CAPACITIES IN BBLS.
Rago FI	uid Type	. 7	$Z_{\lambda} \times X$	e L		Base	riuid va	OI					Tubing Can
Foem C	lual · 🛶	→ % Mi	tchellO	Slurry	Surf	ace[] [Downho	ole 🗌 Tol	ial Prop	uty		Lbs.	Casing Cap.
Prop Ty	ne: Sand	□ WP-1	□ W	P-30	Baux.C) Oth	19						Annular Cap.
						****							Open Hole Cap.
Hole Lo	aded With	` ` ` `	cl_		Trea	ıt Via: T	ublng[]	Casir	ng□ A	nul.🏻	Tubing &	Anul.[]	Fluid to Load
Ball Se	alers:	65	In	700		Stages	of	3/_				,,,,	Treating Fluid
TABAR 6	Unit Du	Types and X	ıs Usad				م <u>نبرسار</u>	ر روز المراجعة					riusn
Auxiliar	y Material	s	<u> 10 (</u>	2115	<i></i>	3s,	<u> ۱۵۲ د</u>	2 1/4	? <u> </u>		•n*•		Overflush
													Fluid to Recover Total N ²
PROC	EDURE	OKO;	BAL	15 141	rch		ush	10 130	Houn	HER.	·		Total CO,
000000000000000000000000000000000000000	MARY		-,		 								
Y	UCAA.						iaco		Sur	lace	NA Davis		
Time	Treating P	ressure-Psi		iace BBLS.	Slurry Rate		BBLS.	CO, Rate		ISCF	Nº Rate		Comments
AMOD	1700000			nped	ВРМ	Pún	npod	ВРМ		nped	SCFM		
	STP	Annulus	Stage	Total		Stage	Total		Stago	Total		210	An 14 - 74 - 7
6:22	5000			1	-34t		 / 						ssuke lost
4.36	-		<u> </u>		47,0		 / -	 /	/-	 /	/ -		
	- 10 to			1/20	50-	<i>\-</i>	 / −	<i>f.</i>	 /	 	 		T BREEK DOWD
6.32	1500	 -/		12.5	3		 	 	† <i> </i>	1		لاداک	1 DIMM COMINATURE
6.36	1000	 	╢┪		5.0	1\	 	1	17	17		STAK	TITESTIVE TEST
655	SOU	 	-	750				Λ				75121	13 is soursz
6:58	1000			30.5	4.0			17	₽	11	 	SZA	J 1341/5
708	1200	1				\bot	<u> </u>		 	17	 	1241	Is ON PERCY IT DOWN SARY BALL KT RATE TEST
.711	7800			37.0	4.0	 		 		 	 	274	KT KATO TOST
721	2200		 	111. E.	6.6	 -	. }-	 }	 -	 \			11 110 10 1
	ļ		 -	-	}	<i>├}-</i> -	 -	-	 }	 	 		
	<u> </u>	 }-	 		<u> </u>	<i>├~─/</i> ─	 	 /	 /-		 /		
	ļ	 - -	 	 		 /-	 	\ <i>\-</i>	-/		1		
	 	 	 		 	 / - 	17	11	1/	1/_			
			 		-	1-1							·
 			17						1	Ц	 	<u> </u>	
							\Box	1	17-	 _\	 \	ļ	
]	1 1		<u></u>		<u> </u>	1	L	
Trootio	a Diagonii	a: Min	100		Max	2200) Ave	a. 180	20	Çus	lomer Rep	resenta	Nive Dale BRIFFII) VO REX ELECTRICAS S TAINE
ineann	U CIBSSUL	tion Etrid	740	<u>U</u> . 1	,. IYIAA	<u> </u>	Rate on	Flush	4.0	Wes	tern Repr	esentati	VO KEN ESTELLISES
IIII. Mai	: DV,V A DII 118ġ	HILLY PIOLO		191	DP Ø	()()	Flush [Dens. lb./	gal. R.	CDist	ribution	Ri	TANK
Elaci O	y. ⊓ate but.io D. ∩	ssure			عد اما	اسسىلىك مىسىپ		Minute	s				
Coara	arie Masia	num Press	ure	40	a''' —							'	AND THE STATE OF T
					، .) w 1 · ·							magratish to 64 i sq. r
1233 Late	Ministra		,										



The Western Company—Treatment Report

Date _	9-2x	93	District	Ven	<u>e</u>	_F. Re	ceipt _	كالمات	739	Operato	r <u>- B</u> za	CRON C.L CO
												<u>リ・アラッ・パリング</u> This Well 🗓
County	عجب محمد	<u> </u>	Siale _	42		5(ឧពួទ	Mumo	er <u>#</u> /		1 nis 201	16 FA	Tuis Astr 17
WELL	DATAC	OGE NO	SO N	ou (DOD WI)[] [V	V (1)	/lisc.□	Depth TD	РВ <u>>́С;; і</u>	_Formatic	on Breen River
	1	lubina Sizo	9	. \	WΥ.		Set a	:	.Ty	pe Packer_		Set At
Casing	Size 5	. S N	Π. 15	5 -	Set From_	Sustin	To	7 %	Lir	er Size	**	Wt
Liner S	et From _	T		Ope	n Hole: Siz	e		_From	T(· ——	Casing P	erforations: Size , 40
Holes F	er Foot _		Int	ervaļs .	<u> </u>	<u>S:-</u>	<u> 518</u>	<u> </u>	<u>+ < H</u> >	(6.7)		۵۰ محمده د در پرسیبه دادر و ۵۰ مربوریه در در <u>در در د</u>
Previou	s Treatme	ent	ه پوه ده د به در پارون د ده ده ده	ALK	ata Apilopina 4- Yannada Salam -agit a Ya Pilang	Pri	or Proc	luction	N/A			
		- O - J	ا امماد ا	V-ally	Noth Dod	runa Tuna	(11)		٠ بــا			LIQUID/GAS PUMPED AND
IREAT	MENT DA	Tras	usea: Lina Flu	id Tyne	vo∐ rad i	Naterix Vaterix		ئىسىسىدىد انات ⊤دە	at Fluid	/ol. //. 2	ا Gal	CAPACITIES IN BBLS
Basa F	uid Type	1111/2	υιι <u>γ</u> ιιμ \$ ~ 1 _	C. tq io i i i i i	. 1 Oani 1	Base Flu	ıid Vol.	U	الام المارة المارة المارة المارة	2	Gal.	
Foam C	lual.:	% M	itcheli[]	Slurry	M Surface	e Do	wnhole	☐ Total	Prop Qty.		Lbs.	Tubing Cap
Prop Ty	pe: Sand	MP-	ID W	P-3D	Baux.	Other	20/	(C)		16/30		Annular Cap
Prop M	esh Sizes,	. Types an	d Quan	tities d	20/cm	£8.5	 }}	16/30	221	1 <i>6/3</i> 0 30		Open Hole Cap
Hole Lo	aded With	1			V taesT	ia: Tub	ing□	Casing	Y Anul.[] Tubing	& Anul.	Fluid to Load 66
Ball Se	alers:		ln		Sta	ages of	-	****				Pad Volume 123
					Coo Tim							Treating Fluid 386
Auxiliar	v Matorial	S Cart	PRILC .	Crite	20	,						Flush /2\ Overflush ————
	•											Fluid to Recover 501
PROC	DURE											Total N ²
30.273.00573	MARY		~		~~~~~					,		Total CO ₂
31.24	1000000	/						, ,				
Time	Treating Pr	essure-Pŝi	Surt Slurry		Slurry Rate	Sur! CO, E	lace anis	CO, Raie	N² M3Cl	Nº Rate		Comments
AM/PM	1100011911	907019 T WI	Pur		врм	nuq	ped	ВРМ	Pumped	1 0000	ŀ	
	-								-			
	918	Annulus	Stage	Total		Stage	Total	ll	Stage To	tal		
4:37	418	Angulus	Stage	Total		Stage	Total		Stage To	tal		INDER TO YOURSE
4:37	- <	Annulus	Stage		· 17.0	Stage 	Total		Stage To			of Pas
4:37		Annulus	Stage		!7.0 25.0	Stage 	Total		Stage To		5 (= 5 fr	1 700 24/19
3.18 1.18 1.19	- - - -	Angulus	Stage	<u>-</u> ن	<u> 25.0</u> 25.1	Stage	Total		Stage To		5 (= 5+k) 5+k)	1 700 24/10 1 200 24/10 11 318 EU/14
4.50 4.43 4.43	- 2090 2119 2130	Annulus	Stage	 	25.0 25.1 26.2	Stage	Total		Stage To		5(= 5+x1 5+4 5+4	1 700 24/10 1 200 24/10 1 318 21/10
4 01 4 00 4 43 4 43	- 2090 2119 2130 2230	Angulus	Stage	 	25.0 25.1 25.2 25.1	Stage	Total		Stage To		5(2 54x 54x 54x 54x	1 700 24/10 1 200 24/10 1 218 21/10 1 40/1 21/10 1 50# 2/40
443	- 2090 2119 2130 2220 2090	Annulus	Stage	 	25.0 25.1 25.2 25.1 25.1	Stage	Total		Stage To		5 (+ 50# 24/10 + 50# 24/10 + 50# 24/10 + 50# 24/10 - 4 60# 24/10
7 52 4 60 4 7 4 7 14 7 14 7 14 7 14	- 2090 2110 2130 2220 2070 1690	Angulus	Stage		25.0 25.1 25.1 25.1 25.1 25.1	Slage	Total		Stage To		5/2 5/4 5/4 5/4 5/4	1 20N 24/10 H 31F EU/10 H 30H 2-/10 H 50H 20/10 H 50H 10/10 H 60H 16/50
4 43 4 43 4 50 4 61 4 53 4 55 4 57	- 2090 2110 2130 2220 2070 1680 1660	Annulus	Stage		25.0 25.1 26.2 25.1 25.1 25.1 25.1 25.3	Stage	Total		Siage To		5 (2. 5 4 6. 5 4	1 1 2 0N 24/10 H 31 F 24/10 H 50 F 24/10 H 50 F 24/10 H 60 F 16/30 H 70 F 16/30
4 43 4 43 4 50 4 61 4 53 4 55 4 57 5 00	- 15 - 2090 - 2119 - 2130 - 2220 - 2070 - 1690 - 1600 - 1670	Annulus	Stage		25.0 25.1 25.1 25.1 25.1 25.1 25.3 25.2	Stage	Total		Stage To		5/2 5/4 5/4 5/4 5/4	1 700 24/10 1 300 24/10 1 318 21/10 1 50 # 21/10 1 60# 16/50 1 73 # 16/30
4 43 4 43 4 50 4 61 4 53 4 55 4 57	- 2090 2110 2130 2220 2070 1680 1660	Annulus	Stage		25.0 25.1 26.2 25.1 25.1 25.1 25.1 25.3	Stage	Total		Stage To		5 (2) Star Star Star Star Star Star Star Star	1 700 24/10 H 348 24/10 H 348 24/10 H 50# 24/10 H 50# 24/10 H 60# 16/50 H 70# 16/50 H 70# 16/50
4 43 4 43 4 50 4 61 4 53 4 55 4 57 5 00	- 15 - 2090 - 2119 - 2130 - 2220 - 2070 - 1690 - 1600 - 1670	Annulus	Stage		25.0 25.1 25.1 25.1 25.1 25.1 25.3 25.2	Stage	Total		Stage To		5/2 5/2 5/2 5/2 5/2 5/2 5/2 5/2	1 700 24/10 1 300 24/10 1 318 21/10 1 50 # 21/10 1 60# 16/50 1 73 # 16/30
4 43 4 43 4 50 4 61 4 53 4 55 4 57 5 00	- 15 - 2090 - 2119 - 2130 - 2220 - 2070 - 1690 - 1600 - 1670	Annulus	Stage		25.0 25.1 25.1 25.1 25.1 25.1 25.3 25.2	Stage	Total		Stage To		5/2 5/2 5/2 5/2 5/2 5/2 5/2 5/2	1 700 24/10 H 318 24/10 H 318 24/10 + 30# 2/10 + 30# 2/10 + 30# 16/30 + 30# 16/30 - 16/45 Down All ilving
4 43 4 43 4 50 4 61 4 53 4 55 4 57 5 00	- 15 - 2090 - 2119 - 2130 - 2220 - 2070 - 1690 - 1600 - 1670	Annulus	Stage		25.0 25.1 25.1 25.1 25.1 25.1 25.3 25.2	Stage	Total		Stage To		5/4 5/4 5/4 5/4 5/4 5/4 5/4 5/4	1 700 24/10 H 318 24/10 H 318 24/10 H 30 H 2/10 H 50 H 2/10 H 50 H 16/50 H 70 H 16/50
4 43 4 43 4 50 4 61 4 53 4 55 4 57 5 00	- 15 - 2090 - 2119 - 2130 - 2220 - 2070 - 1690 - 1600 - 1670	Annulus	Stage		25.0 25.1 25.1 25.1 25.1 25.1 25.3 25.2	Stage	Total		Stage To		5/4 5/4 5/4 5/4 5/4 5/4 5/4 5/4	1 700 24/10 H 318 24/10 H 318 24/10 H 30 H 26/10 H 50 H 26/10 H 50 H 16/50 H 70 F 16/50 H 70 F 16/50 H 70 F 16/50 M 16/00 M 15/00 M 15/00 M 15/00 M 15/00 M 15/00 M 15/00
4 43 4 43 4 50 4 61 4 53 4 55 4 57 5 00	- 15 - 2090 - 2119 - 2130 - 2220 - 2070 - 1690 - 1600 - 1670	Annulus	Stage		25.0 25.1 25.1 25.1 25.1 25.1 25.3 25.2	Stage	Total		Stage To		5/4 5/4 5/4 5/4 5/4 5/4 5/4 5/4	1 700 24/10 H 318 24/10 H 318 24/10 H 30 H 2/10 H 50 H 2/10 H 50 H 16/50 H 70 H 16/50
4 43 4 43 4 50 4 61 4 53 4 55 4 57 5 00	- 15 - 2090 - 2119 - 2130 - 2220 - 2070 - 1690 - 1600 - 1670	Annulus	Stage		25.0 25.1 25.1 25.1 25.1 25.1 25.3 25.2	Stage	Total		Stage To		5/4 5/4 5/4 5/4 5/4 5/4 5/4 5/4	1 700 24/10 H 318 24/10 H 318 24/10 H 30 H 2/10 H 50 H 2/10 H 50 H 16/50 H 70 H 16/50
4 43 4 43 4 50 4 61 4 53 4 55 4 57 5 00	- 15 - 2090 - 2119 - 2130 - 2220 - 2070 - 1690 - 1600 - 1670	Annulus	Stage		25.0 25.1 25.1 25.1 25.1 25.1 25.3 25.2	Stage	Total		Stage To		5/4 5/4 5/4 5/4 5/4 5/4 5/4 5/4	1 700 24/10 H 318 24/10 H 318 24/10 H 30 H 2/10 H 50 H 2/10 H 50 H 16/50 H 70 H 16/50
4.43 4.40 4.50 4.53 4.53 4.57 5.00 5.00	 2090 2110 2130 2220 2070 1690 1600 1650			21/2 135 135 138 21/0 277 325 386 507	25.0 25.1 25.2 25.1 25.1 25.1 25.3 25.2 25.2						5 (2)	1 FAN 1 20N 24/10 1 34 20/10 1 40 1 20/10 1 60 1 16/30 1 60 1 16/30 1 70 1 16/30 1 70 10 10 1 DUNE ALL TURNED
4.43 4.50 4.50 4.53 4.57 5.00 5.00		: Min.	/650	21/2 138 138 21/0 277 325 38/0 507	25.0 25.1 25.2 25.1 25.1 25.1 25.2 25.2 25.2	250	Avg.	/80Q	C	uslomer Re	Star Star Star Star Star Star Star Star	1 Pan 1 20N 24/10 1 19 1 20/10 1 19 1 20/10 1 10 1 20/10 1 10 1 10/10 1 10 10 10/10 1
4 43 4 480 4 60 4 61 4 53 4 55 4 57 5 00 5 00 Treating	7 2090 2119 2130 2270 1690 1690 1650 1650 1650 1650 1650 1650 1650 165	: Min.	1650	2 /13 /35 /35 216 277 325 386 507	25.0 25.1 25.2 25.1 25.1 25.1 25.3 25.2 25.2 25.2	2-5/2) Rate	Avge on Fl	ush <u> Z</u> "	C & V	ustomer Re /estern Rep	Star Star Star Star Star Star Star Shor Shor Shor Shor Shor Shor Shor Sho	1 700 24/10 H 718 EU/10 H 718 2/10 H 708 2/10 H 708 16/50 H 708 1
4.43 4.50 4.50 4.53 4.57 5.00 5.00 Treating Inj. Rate	7 2090 2119 2130 2230 2070 1630 1600 1650 1650 17 50	: Mining Fluid _	1650	216 216 277 327 386 507	Z5.0 25.1 Z5.2 25.1 Z5.1 Z5.1 Z5.2 Z5.2 Z5.2 Z5.2	250 Ratio	Avge on Flish Den	ush <u> </u>	0 (ustomer Re /estern Rep	Star Star Star Star Star Star Star Shor Shor Shor Shor Shor Shor Shor Sho	1 Pan 1 20N 24/10 1 19 1 20/10 1 19 1 20/10 1 10 1 20/10 1 10 1 10/10 1 10 10 10/10 1
4 43 4 53 4 57 5 00 5 00 Treating Inj. Rate Avg. Inj. Final St	7 2090 2110 2130 2220 2070 1690 1690 1650 1650 1650 1650 1650 1650 1650 165	: Mining Fluid	/65U)	1 1.5.0 2.10 2.77 3.25 3.86 507	25.0 25.1 25.2 25.1 25.1 25.1 25.2	250 Ratio	Avge on Flish Den	ush <u>Z</u> s, lb./gal. linutes	0 (ustomer Re /estern Rep	Star Star Star Star Star Star Star Shor Shor Shor Shor Shor Shor Shor Sho	1 700 24/10 H 718 EU/10 H 718 2/10 H 708 2/10 H 708 16/50 H 708 1
4 43 4 50 4 50 4 57 4 57 5 00 5 00 Treating Inj. Rate Avg. Inj. Final St Operato	7 2090 2110 2130 2220 2070 1690 1690 1650 1650 1650 1650 1650 1650 1650 165	: Mining Fluid	/65U)	1 1.5.0 2.10 2.77 3.25 3.86 507	Z5.0 25.1 Z5.2 25.1 Z5.1 Z5.1 Z5.2 Z5.2 Z5.2 Z5.2	250 Ratio	Avge on Flish Den	ush <u>Z</u> s, lb./gal. linutes	0 (ustomer Re /estern Rep	Star Star Star Star Star Star Star Shor Shor Shor Shor Shor Shor Shor Sho	1 700 24/10 H 718 EU/10 H 718 2/10 H 708 2/10 H 708 16/50 H 708 1


To the	The	West	lern	C	pan	v— T	reatr	ment l	Ranc	nrt (
Date _ Lease County	1.30 M.E	1-43 FCO	District	30	RNA	F	Receip	o1 <u>2</u> 26	1950	1,	_Operator _Location _This Zon	BA 311-	195-12/6E This Well &
WELL	DATA	OGD No Tubing Siz	GD N	NY X	000 WT. 4	WDD 5	IWD Se	Misc.	Dep	th TD/PI	5018	Formati	on
Liner S	et From		<u>-</u>	Op	en Hole:	Size _		From		Line: To	Size	Casing P	wt. —
1 20100 1	OI LOUL,	ent	11 (101A412		1 - 1	1.7.0	(A) h	10116				Supplied to the supplied to th
Base F Foam (luid Type Dual.:	Pad Trea '' M WP-	ating Flu ∴c. L itcheli□	od Type	e: Foam	□ Wate Base face□	rix Acid Fluid V Downh	d Oil ol.	tal Prop	Otv.		Gal	Casing Cap.
Prop M Hole Lo Ball Se Types a	lesh Sizes paded Wit alers: and Numb	s, Types an h <u>K.C.</u> 1.7 per of Pump	nd Quan LIn ps Used	nities _	Tres	at Via: Stages	TubingÇ of	K Cash	ngD /	Anul.[]	Tubina &	Anul.	Annular Cap. Open Hole Cap. Fluid to Load Pad Volume Treating Fluid Overflush 5.5
PROC	EDURE MARY	Fluit		17 F.	V// v	<u>α</u>	5 EE C		XCT D	21 ALL	8 Ar	` ('	Fluid to Recover 52.9 Total N2 Total CO2
Time AM/PM	Treating P	ressure-Pei	Slurry Pun	ace BBLS. ped	Slutry Rate BPM	CO, I	face BBLS. nped	CO, Rato BPM	Nº N Pun	face ISCF nped	Nº Rate SCFM		Continents
24	517	Annulus	Stage	LOUI		Stage	Total		Stage	Total		 -,	
6:3	8	i			5.0	 -	 			ļ			1 M T-ST & 5000
6	1800			12	775		- 			 	 		T 1120
0:37				18	-1-0						ļ		المين ٦
1.10	1/1/00			36	1-	ļ. 	 					SIART	
6:15				300	50						ļ	34.00	DOWN DUTYE
654	1600 2000			52.7	F. 4							Shur	Me Flush Down All Flush
							,						
													
										,		~	
	Descri		1600		Max. <u> </u>	11/00		2500					Cuickin
inj. Rate Avg. Inj. Final Shu	Pressure on Treation Rateut-in Press	ng Fluid D (C	11. UD	I.S.D.	Max. <u>* /</u> P in	. R	ate on f ush De	lush lush ons. lb./ga Minutes	5 . W al. <u>X. Y</u>	West		entativo	SEARLE
Operator J///	's Maximu	m Pressur Recomm	e(LCO LD#	·		ŧ	-					
"AFI (£)	MAN HOLD	1		•				 ;				•••••	•

	Q ''								,		<u> </u>	ME Z	
Lea	se 6 6	2-75	Distr	rict _/	EISNU	<u> </u>	F. Rece	1026/	954	,	Operat	or 15A	1 CRON - 795 - /2/6 E This Well
Cou	inly (")c	lucasa	11977	No. ∠	3-11	ر	Field \\	LB.			Locatio	in 5 1/	-795.1816E
Estate Service A			, Olale	·	Ţ <u> </u>		Stage N	lumber _			This Zo	ne 🔀	This Well
I.WEL	L DATA	ogn	NGU:	NAM	000						_		·
2000000		Tubing S	Size 🚄	71/8	WT	۷. ۵	,s	i ivilou Set at:	יע טי	אַעו חוק⊌ ~~~	18.2.7 <u>//</u>	Formati	onSet At <u>4750</u>
Casi	ng Size	72	_WT. <u>/</u>	5.5	_Set Fi	om	, _	To	TID	Iyp	e Packer_		Set At
Liner	Set From)	_To	0	pen Hol	e: Size		Fro)m	To	3129	Casing D	Wt.
Previ	s rer roo: ious Treat	ment	<u></u>	Interval	ls	162	- 49	68		2. Hol	es	Todailiñ L	Wt
538000700MH		ment	17/17	<u></u>			Prior	Producti	on	MA			
TREA	TMENT	ATA Pa	haeU bi	l· Vac⊓	Note t	T boC			***************************************				Madestance
	The second second	Tex	aatina E	ひいしん アンノ	A a (P		- L7	AD ONE	······································	51 111	<u> </u>		LIQUID/GAS PUMPED AN CAPACITIES IN BBLS
Base	Fluid Typ	2%	150	<u> </u>		Bas	e Fluid 1	Vol	i ireat.	. Plula Vo	·!	Gai.	CAPACITIES IN BBLS.
										op Qtv.		Gal.	Tubing Cap. 28.6
Prop	iyye. Sal Mesh Sizo	ndD WP	'-1 <u></u>	WP-3D	Baux	.0 0	lher						Casing Cap
	111001 UIL	ID. IVUHS A	IDA C 1110	10111100									Annular Cap Open Hole Cap
Ball S	ealers: 1	ith KC L 12 ber of Pun	In 5	7	I re	at Via:	Tubing	Cas	ing[]	Anul.	Tubing 8	& Anul.□	Fluid to Load
Types	and Num	ber of Pun	nos Use		(2)	្ទនេង	s 01		2				Fluid to Load 7 Pad Volume 75.1
		als]	Treating Fluid 8 Flush 97/28.7
	·												Overflush 4
PROC	EDURE												Fluid to Recover FOR
SUM	MARY						_						Total N ²
-	******				1								Total CO ₂
Time AM/PM	Treating F	ressure-Psi		riaco / BBLS.	Sluriy - Rate		riace BBLS.	CO, Rai		ırlace	Nº Raie		
AMIFIN	STĖ	Annulus	Pur	nped	ВРМ		npod	ВРМ		MSCF mped	SCFM	ĺ	Comments
1	†*************************************	I MINUIUS	Stace	Total	}	Stace	Total		-		1	1	
17:1/2	'l ^	1	3.500	-	 		-		Stage	Total			
7:113	2300				4				Stage	Total		24.41	
7:16	2300			8.1	1/.0				Stage	Total		HAR	T 13 A 115
2:16	2300			8.1	1.0				Stage	Total		JAR.	T /3 A / 15 T FIUSh
2:16	2300			8.1 10.1 10.3	1.0				Stage	Total		JAR.	T 13 A 115
2:16	2300			-8.1 10.1 2/0.3	1.0 7.8 1.2 1.8			. 110	Stage			JAR.	T /3 A / 15 T FIUSh
2:16	2300		8 4C	8.1 10.1 10.3	1.0 7.8 1.2 1.8		PA	· HO	Stage		<i>30</i>	JAR.	T /3 A / 15 T FIUSh
2:16	2300 2300 2100 — Te			-8.1 10.1 2/0.3	1.0 7.8 1.2 1.8			10 /10 /10 /10 /10 /10 /10 /10 /10 /10 /	Stage		30	HAR HAR 3 hust	T BATIS COUN ATT Flus
7:46	2300 2300 2100 70 0 2100		8 <i>40</i> T.D.	8.1 10.1 (0,3	11.0 2.8 11.2 7.5 4.0 4.0			JCER	Stage			JAR.	T /3 A / 15 T FIUSh
7:46	2300 2300 2100 7e 5 2100 2100		8 <i>90</i> T D	8.1 10.1 4/6.3 	11.0 2.8 11.2 4.8 2.5 4.0 4.0 5.2			HO	Stage		30	HAR HAR 3 hust	T BATIS COUN ATT Flus
7:46	2300 2300 2100 76 0 2100 2100 1200		8 <i>90</i> T D	8.1 10.1 (0,3	1/0 7/8 1/8 7/5 4/0 5/2 (/.V		PA	ICE R	Stage		<i>30</i>	JAR JAR JAR JAR JAR	T BATIS COUN ATT Flus
7:46	2300 2300 2100 7e 5 2100 2100		8 <i>90</i> T D	8.1 10.1 40.3 	1/0 7/5 4/0 4/0 4/0 4/0 4/0 4/0 4/0 4/0 4/0 4/0		PA	HO JCER	Stage		30	HART Shud Shud Shart Shart Shart Shart Show	HZO BALLS ALLS HZO BALLS FILISM SMIGE BALLS TIUSK
7:46	2300 2300 2100 2100 2100 2100 1200		8 <i>90</i> T D	8.1 10.1 4/6.3 	1/0 7/8 1/8 7/5 4/0 5/2 (/.V		PA	, HO JCER	Stage		<i>≥</i> 0	ARE STARE	FILSH COUND ATT FIUS PALLS FILISH SMIGE BALLS TO HELSE TO SHIPTUS ATT FIUS DOWN ATT FIUS
7:46	2300 2300 2100 2100 2100 2100 1200		8 <i>90</i> T D	8.1 10.1 40.3 	1/0 7/5 4/0 4/0 4/0 4/0 4/0 4/0 4/0 4/0 4/0 4/0		PA	Jeer	Stage		30	HART Shud Shud Shart Shart Shart Shart Show	HZO BALLS ALLS HZO BALLS FILISM SMIGE BALLS TIUSK
7:46	2300 2300 2100 2100 2100 2100 1200		8 <i>90</i> T D	8.1 10.1 40.3 	1/0 7/5 4/0 4/0 4/0 4/0 4/0 4/0 4/0 4/0 4/0 4/0		PA	, HO JCER	Stage		30	HART Shud Shud Shart Shart Shart Shart Show	FILSH COUND ATT FIUS PALLS FILISH SMIGE BALLS TO HELSE TO SHIPTUS ATT FIUS DOWN ATT FIUS
7:46	2300 2300 2100 2100 2100 2100 1200		8 <i>90</i> T D	8.1 10.1 40.3 	1/0 7/5 4/0 4/0 4/0 4/0 4/0 4/0 4/0 4/0 4/0 4/0		PA	ICE R	Stage		30	HART Shud Shud Shart Shart Shart Shart Show	FILSH COUND ATT FIUS PALLS FILISH SMIGE BALLS TO HELSE TO SHIPTUS ATT FIUS DOWN ATT FIUS
7:46	2300 2300 2100 2100 2100 2100 1200		8 <i>90</i> T D	8.1 10.1 40.3 	1/0 7/5 4/0 4/0 4/0 4/0 4/0 4/0 4/0 4/0 4/0 4/0		PA	140 JCER	Stage		30	HART Shud Shud Shart Shart Shart Shart Show	FILSH COUND ATT FIUS PALLS FILISH SMIGE BALLS TO HELSE TO SHIPTUS ATT FIUS DOWN ATT FIUS
7:16 7:46 7:64 8:17 8:17 8:20 8:21 8:21 8:21	2300 2100 2100 2100 2100 2100 2100 2100	0 - 4	8 Y/O T D	8.1 10.3 40.3 4/8	1/0 2/8 1/8 7/5 4/0 4/2 4/2 4/2 4/2 4/2 4/2 4/2 4/2 4/2 4/2	04	PA	,	Zes .	4/8		START START START START START START	PAILS PA
7:46 7:44 7:44 8:27 8:27 8:27 8:27 8:27	2300 2300 2100 2100 2100 2100 2100 2100	Min. 26	8 Y/O	8.1 10.3 	1/.0 2/8 1/2 7/5 4.0 1/2 1/2 1/2 1/2 1/2 1/2 1/2 1/2 1/2 1/2	600	PA	2000	7150	4/8		STARE SHARE SHARE STARE	HZO BALLS PLUSH PAUSH
7:06 7:04 8:20 8:27 8:27 8:27 8:27 8:27 8:27 8:27 8:27	2300 2300 2100 2100 2100 2100 2100 2100	Min. 26	8 Y/O	8.1 10.3 	1/.0 2/8 1/2 7/5 4.0 1/2 1/2 1/2 1/2 1/2 1/2 1/2 1/2 1/2 1/2	600	PA	2000	7150	4/8		STARE SHARE SHARE STARE	PAILS PA
7: 1/6 7: 5/ 8: 17 8: 20 8: 21 5: 27 5: 27 5: 27 Final Shu	Pressure: on Treatin Rate // It-in Press	Min. 20	8 Y/O T D	8.1 10.3 (/K) 7 (/o.3 (/o.3 (/o.6)	1/.0 2/8 1/2 7/5 4.0 1/2 1/2 1/2 1/2 1/2 1/2 1/2 1/2 1/2 1/2	600	PACAVO. Avg. Ale on Firsh Den	(;;) () () () () () () () () () () () () (7150	4/8	ner Repre	STARE SHARE SHARE STARE	HZO BALLS PLUSH PAUSH
7: 1/6 7: 5/ 8:17 8:20 8:21 5:27 5:27 5:27 Final Shu	Pressure: on Treatin Rate // It-in Press	Min. 26	8 Y/O T D	8.1 10.3 (/K) 7 (/o.3 (/o.3 (/o.6)	11.0 2.8 1.2 1.2 1.2 1.2 1.2 1.2 1.2 1.2	600	PACAVO. Avg. Ale on Firsh Den	2000	7150	4/8		STARE SHARE SHARE STARE	PRIFFIN SEARLE
7: 1/6 7: 5/ 8: 17 8: 20 8: 21 5: 27 5: 27 5: 27 Final Shu	2300 2300 2100 2100 2100 21700	Min. 20	8410 TD	11/10 A	11.0 2.8 1.2 1.2 1.2 1.2 1.2 1.2 1.2 1.2	600	PACAVO. Avg. Ale on Firsh Den	(;;) () () () () () () () () () () () () (7150	4/8		STARE SHARE SHARE STARE	PRIFFIN SEARLE





Date of Treatment: 9-30-93SEC. // TWN. 95 RNG 168 Well Name MONUMENT FED, 23-115 Field MONUMENT BATTE County DUCHESNE State ATHI Formation/Perforations: GREEN RIVER 1 TE BREAK DOWN 4984-4998, 6 HOLES. 12 BALLS
220 // // 4962-4968, 2 HOLES. 4 //
320 // // 4840-4864, 6 HOLES. 12 // NO BALL OFF Treatment type: 2% KCL BREAR'S Down Total Number of Holes: 14 Treatment Company: WESTERN Sand Characteristics Conc._ Volume Size Fluid Volume BBL. 2% KCL WATER 53 BBL, Gal. 2% KCL WATER BBLI DO 1. 2% KCL WATER _____ Gal. _____ _____ Gal. _____/___ # ____ Gal. ___ # ___ Gal. ___ Gal. ____ . Mai britania _____ Gal. _____/_____/ # # Gal. ____ TOTAL FLUID PUMPED:_____ gal. Acid fluid ____ gal.___ lbs. _____sand TOTAL SAND VOL. : lbs. _____/ sand lbs. _____/_ sand _____/ bauxite _____ gal, of ____ Flushed well with _ ball sealers were pumped. Was ball action seen? Barrels of Load to Recover ______ BLTR. Avg. Treating Pressure = _____ psi, max = ____ psi, min = ____ psi. Avg. Treating Rate = ______bpm, max = _____bpm, min = _____bpm. ISIP = _____ psi, 5 mln. = _____ psi, 10 mln. = _____ psi, 15 mln. = _____ psi. Well will be shut in for _____ hrs. before bringing back fluid. REMARKS: 1 2 Break Down initial Break it 2,5 BPM, 2500 PS' BACK TO 1700 PS' PUMP FOR RATE. 5.5 BPM OF 2500 PSI. ISIP 700 PSI. 2 BREAK DOWN, INITIAL BREAK AT 2 BPM 3000 PSI, BACK TO 2000 PSI, PUMP FOR BATE 4,0BPM AT 2000 PSI. ISIP 600, 3rd Breek Elow, INITIAL BREAK 15 TOO BPM BOW PS; BACK TO 1600 PSi, PUMP FOR RATE, 6, 2 BPM ATROOD PS1, 151P 600 PS1 Well site Supervision: Dale 9





Well Name Monument hed 23 Field Monument Butte Co	ו מינונים	11710-11	7/7 0	· SPF
Formation/Perforations: <u>C-13 EEN</u>	151000	, 4770-4		
Treatment type: BREAK Down	/	Total Number	of Holes:_	14
Treatment Company : <u>WESTERIN</u>	<u> </u>		and Chara	
Volume Fluid	Conc.	Slze		Volume
Gal	, , , , , , , , , , , , , , , , , , ,			
Gal		704 Avenue de la Constantina del Constantina de la Constantina de la Constantina de la Constantina de la Constantina del Constantina de la		
Gal				
Gal,		a como hi principal	<u>/·</u>	#
Gal,			/	#.
Gal	and allowing districts and the second and the secon		<u> </u>	#
Gal			<u> </u>	#
Gal	1 11111111111111111111111111111111111		/	#
Gal	-		<i></i>	#
Gal,			<u> </u>	#
Gal			<u> </u>	#
TOTAL FLUID PUMPED:	ga <u>l.</u>	%	Α	cld
1979	gal. 2% /5	ch	fl	uld
TOTAL SAND VOL.:	lbs	1	sand	
	lbs		sand	
200 action described in the contract of a co	lbs	1 de la decembra de la compansa del compansa de la compansa de la compansa de la compansa de la	sand bauxite	
Per calculation of a control of the state		Kch WATE		
Flushed well with (gal, of <u>AZZ</u> iped. Was bal	laction seen? L	, H14+11 [[[I BALL OFF
Barrels of Load to Recover <u>47</u>		BUR.		1000
Avg. Treating Pressure = $\frac{2600}{}$	psl, max =	4000 psi	, mln ≔_∠	psl.
	_bpm, max =	ngd <u>ヘップ</u>	n, mln =	<u>9, 2</u> bpm. psl.
	psl, 10 mli	n. = psi, ging back fluld.	1011111. =	
		T 2,5 BPM	•	
KEIVIAKKS: ATTOMET RESERVED	P DOL DT	U.S. RPM		<u> </u>



TREATMENT REPORT

Volume Fluid Conc. Size — Gal. — Gal	Conc. Size Volume 8 PAD. 2420 at 19.9 2	Volume Fiuld Conc. Size Volume Gal. Gal. Gal. 550 Gal. // // 2 /6/30 /100 600 Gal. // // 3 /6/30 /1800 600 Gal. // // 3 /6/30 /800 600 Gal. // // 4 // 16/30 2400 900 Gal. // // 5 /6/30 4500 1000 Gal. // // 5 /6/30 4500 1000 Gal. // // 7 /6/30 4200 Gal. // // 7 /6/30 4200 Gal. // // 7 /6/30 4200 TOTAL FLUID PUMPED: gal. 200. 200. Acid	Sand Characteristics	Sand Characteristics
Gal. Gal. Gal. Gal. S50 Gal. 600 Gal. 11 1 2 16130 600 Gal. 11 1 1 16130 900 Gal. 10 10 Gal. 10 10 Gal. 10 11 11 11 16130 Gal. Gal. Gal. Gal. Gal. Gal. Gal. Gal. 10 10 Gal. 10 10 Gal.	8PAD, $2420 at 19.9$ 2	Gal. Gal. Gal. Gal. S50 Gal. 2% KcL WATER PAD. 2420 at 19.9 600 Gal. 11 1 2 16.30 1.00 600 Gal. 11 1 1 16.30 2.400 900 Gal. 1000 Ga	No. 16kma	Alan Value
Gal. 5 2800 Gal. 2%	$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	Gal. 6 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal.		Volume Fluid Conc. Size Will
15; 2800 Gal. 2% KCL WATER PAD. 2420 at 19,9 550 Gal. 11	$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	S 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal.	Volume Fluid Conc. Size Willing	
550 Gal. // // 2 /6/30 600 Gal. // // 3 /6/30 600 Gal. // // // 16/30 900 Gal. // // 5 /6/30 1000 Gal. // // 6 /6/30 Gal. // // 7 /6/30	$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	550 Gal.	Volume Pidid Control	Gal
550 Gal. 11 11 2 16 30 600 Gal. 11 11 11 16 130 900 Gal. 11 11 15 16 30 1000 Gal. 11 11 1 1 16 16 30 600 Gal. 11 11 7 16 130 Gal. 11 11 7 16 130	$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	550 Gal.	Gal	Gal
600 Gal. // // // // // // // // // // // // //	1/ 16 30 2400 5 16 30 4500 6 16 30 6000 7 16 30 4200 agl. — % — Acld	600 Gal. // // 5 /6/30 2400 900 Gal. // // 5 /6/30 4500 1000 Gal. // // 6 /6/30 6000 600 Gal. // // 7 /6/30 4200 Gal. // // 7 /6/30 4200 10TAL FLUID PUMPED: gal. 2% KCK WOTER fluid	Gal	Gal
600 Gal. 11 11 15 16 30 900 Gal. 11 11 6 16 30 1000 Gal. 11 11 7 16 30 Gal. 11 11 7 16 30	5 6 30 4500 6 6 30 6000 7 6 30 4200 	600 Gal.	Gal	Gal
900 Gal. 11 11 5 16130 1000 Gal. 11 11 7 16130 Gal. 11 11 7 16130	6 16130 6000 7 16130 4200 1 1 Acid	900 Gal. 11 11 6 16130 4300 1000 Gal. 11 11 7 16130 4200 Gal. 11 11 7 16130 4200 Gal. 1 11 7 16130 4200 10TAL FLUID PUMPED: gal. 2% KCK WATER fluid	Gal. Gal. Gal. 5/ 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100	Gal. 5/2800 Gal. 2% KCL WATER PAD. 2420 at 19,9 550 Gal. "" 2 16130
1000 Gal. 11 11 7 16 16 30 6 1	7 16 30 4200 4200 1 4200	1000 Gal.	Gal. ———————————————————————————————————	Gal. 5/2800 Gal. 2%/SCLWATER PAD. 2420 at 19,9 550 Gal. 11 11 2 16130 11 600 Gal. 11 11 3 16130 25
600 Gal. 11 11 7 16 30 6	agl. — % — Acid	600 Gal. // // 7 /6/30 4/200 — Gal	Gal. Gal. Gal. 5/ 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 3 16130 2400 600 Gal. 11 11 11 16130 2400	Gal. 6/ 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 12 600 Gal. 11 11 11 16130 25
Gal/		Gal.	Gal. Gal. Gal. 61, 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 3 16130 2400 600 Gal. 11 11 4 16130 4500 900 Gal. 11 11 5 16130 4500	Gal. 5/ 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 12 600 Gal. 11 11 11 11 16130 25 900 Gal. 11 11 5 16130 45
9 <u>/ FND</u> Gal		TOTAL FLUID PUMPED: gal. % — Acld Acld gal. 2% KCK WBTER fluid	Gal. Gal. Gal. 6/ 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 4 16130 2400 1000 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 6 16130 4500	Gal. 5/ 2800 Gal. 2% KCL WATER PAD. 2420 at 19,9 550 Gal. 11 11 2 16130 15 600 Gal. 11 11 11 11 16130 25 900 Gal. 11 11 5 16130 45 1000 Gal. 11 11 6 16130
		TOTAL FLUID PUMPED: gal. 90 % — Acld Acld gal. 2% KCK WBTER fluid	Gal. Gal. Gal. Gal. 5/ 2800 Gal. 2%/SCLWATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 4 16130 2400 900 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 6 16130 4500 600 Gal. 11 11 7 16130 4200	Gal. 5/ 2800 Gal. 2%/5/5CL WATER PAD. 2420 at 19.9 550 Gal. 11
	and 2 % KCK WATER fluid	11634 gai. 2% KCK WATER fluid	Gal. Gal. Gal. S1 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 4 16130 2400 900 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 6 16130 4000 600 Gal. 11 11 7 16130 4200 Gal. 11 11 7 16130 4200 Gal. 11 11 7 16130 4200	Gal. 5/ 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 12 6 30 16 600 Gal. 11 11 16 900 Gal. 11 11 5 16 30 45 1000 Gal. 11 1 6 16 30 42 Gal. 11 1 7 16 30 42 Gal. 11 1 7 16 30 42
11634 gal. 290 KCK WATER fluid	Man Additional Control of the Contro		Gal. Gal. Gal. Gal. Si 2800 Gal. 2% KcL wATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 3 16130 2400 600 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 7 16130 4200 TOTAL FLUID PUMPED: Gal. Acid	Gal. 5/ 2800 Gal. 2% KcL wATER PAD. 2420 at 19,9 550 Gal. " " 2 6 30 /6 600 Gal. " " 3 6 30 /6 600 Gal. " " 1/1 /1 /1 /6 30 /6 900 Gal. " " /6 30 /6 1000 Gal. " " /6 /6 30 /6 Gal. " /7 /7 /6 30 /6 Gal. /7 /7 /6 30 /7 Gal. /7 /7 /6 30 /7 TOTAL FLUID PUMPED: gal. % — Acld
TOTAL SAND VOL.: 20,000 lbs. 16130 sand	lbssand	TOTAL SAND VOL.: <u>20,000</u> lbs. <u>16130</u> sand	Gal. Gal. Gal. Gal. Si 2800 Gal. 2% KcL wATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 3 16130 2400 600 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 6 16130 4500 1000 Gal. 11 11 7 16130 4200 Gal. Gal. Gal. TOTAL FLUID PUMPED: gal. 6 Acld	Gal. 6/ 2800 Gal. 2% KcL wATER PAD. 2420 at 19,9 550 Gal. " " 2 6 30 /6 600 Gal. " " 3 6 30 /6 600 Gal. " " 1/1 /1 /1 /6 30 /6 900 Gal. " " /6 30 /6 30 /6 1000 Gal. " " /6 /6 30
lbs,sand		lbssand	Gal. Gal. Gal. SI 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 S50 Gal. 11 11 2 6 30 100 600 Gal. 11 11 14 16 30 2400 600 Gal. 11 11 15 16 30 4500 900 Gal. 11 11 1 6 16 30 4500 1000 Gal. 11 11 7 16 30 4200 Gal. 11 7 16 30 4200 19 FND Gal. TOTAL FLUID PUMPED: gal. 20 KCK WATER fluid	Gal. 6/ 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16/30 12 600 Gal. 12 11 3 16/30 25 600 Gal. 11 11 5 16/30 25 900 Gal. 11 11 5 16/30 45 1000 Gal. 11 11 7 16/30 42 Gal. 11 11 7 16/30 42 FIND Gal. 11 11 7 16/30 42 TOTAL FLUID PUMPED: gal. 250 KCK WATER fluid
Personal property by Ann Ann Ann Ann Ann Ann Ann Ann Ann An			Gal. Gal. Gal. Gal. Gal. St. 2800 Gal. 26 KcL wter PhD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 14 16130 2400 600 Gal. 11 11 15 16130 4500 1000 Gal. 11 11 7 16130 4200 600 Gal. 11 11 7 16130 4200 Gal. Gal. Gal. TOTAL FLUID PUMPED: 1000 Gal. 20,000 lbs. 16130 sand lbs. 1 sand	Gal
117011	lbssand	Commence parameter for folla secretarial fractions of the control	Gal. Gal. Gal. Gal. St. 2800 Gal. 2% tsct water PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 4 16130 2400 900 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 7 16130 4200 600 Gal. 11 11 7 16130 4200 Gal. FIND Gal. TOTAL FLUID PUMPED: Gal. 105. 105. 105. 105. 105. 105. 105. 105. 105. 1000 105. 105	Gal. Gal.
Flushed well with 7/07 gal, or 2/0 // 22 day/15/1	lbssand lbsbauxite	lbsbauxite	Gal. Gal. Gal. Si 2800 Gal. 2% KcL WATER PAD. 2420 at 19.9 550 Gal. // // 2 //6/30 //00 600 Gal. // // 3 //6/30 2400 600 Gal. // // 4 //6/30 2400 900 Gal. // // 5 //6/30 4500 1000 Gal. // // 6 //6/50 6000 600 Gal. // // 7 //6/30 4/200 Gal. // // 7 //6/30 4/200 FOTAL FLUID PUMPED: gal. // 7 //6/30 sand sand lbs. // sand sand lbs. // sand sand should be duxitie	Gal
Filished Well With udi, or udi, or	lbssand lbsbauxite	lbsbauxite	Gal. Gal. Gal. Gal. St. 2800 Gal. 2% KcL water PAD. 2420 at 19,9 550 Gal. 11 2 16130 110 600 Gal. 11 11 4 16130 2490 900 Gal. 11 11 5 16130 4550 1000 Gal. 11 11 6 16130 6000 600 Gal. 11 11 7 16130 4200 1010 Gal. 11 11 7 16130 4200 8(FND Gal. TOTAL FLUID PUMPED: gal. 250 Kck water fluid TOTAL SAND VOL.: 20,000 lbs. 16130 sand lbs. 1 sand lbs. 1 sand lbs. 1 sand	Gal
Flushed well with 9/09 gal, of 2/6 h 2 WATEA	lbs sand lbs bauxite	lbsbauxite	Gal. Gal. Gal. Gal. Gal. Gal. S50 Gal. // // 2 //6/30 //6/3	Gal
FIUSDECI WEIL WILL TO THE GOLD TO THE FIUSDECI WEIL WILL TO THE GOLD TO THE GOLD TO THE FIUSDECI WEIL WILL TO THE GOLD TO THE	lbssand lbsbauxite	lbsbauxite	Gal. Gal. Gal. Gal. Gal. Gal. S50 Gal. 100 600 Gal. 11	Gal
ball sealers were pumped. Was ball action seen?	lbssand lbsbauxite gal. of 2% Kc2 WATER oumped. Was ball action seen?	Flushed well with 4704 gal. of 2% KcL WATER ball sealers were pumped. Was ball action seen?	Gal. Gal. Gal. Gal. Gal. 6/2800 Gal. 2%/ScLw8TER PAD. 2420 aT 19, 9 550 Gal. 11 2 16130 1100 600 Gal. 11 11 14 16130 2400 900 Gal. 11 11 15 16130 4500 1000 Gal. 11 17 16130 4200 600 Gal. 11 17 16130 4200 1000 Gal. 11 17 16130 4200 91 FND Gal. TOTAL FLUID PUMPED: Gal. 16130 sand lbs. 1 sand lb	Gal. 380 Gal. 276 K C L W T E P D 2420 E T 9 9 9 9 9 9 9 9 9
lbs,sand		lbs,sand	Gal. Gal. Gal. SI 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 S50 Gal. 11 11 2 6 30 100 600 Gal. 11 11 14 16 30 2400 600 Gal. 11 11 15 16 30 4500 900 Gal. 11 11 1 6 16 30 4500 1000 Gal. 11 11 7 16 30 4200 Gal. 11 7 16 30 4200 19 FND Gal. TOTAL FLUID PUMPED: gal. 20 KCK WATER fluid	Gal. 6/ 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16/30 12 600 Gal. 12 11 3 16/30 25 600 Gal. 11 11 5 16/30 25 900 Gal. 11 11 5 16/30 45 1000 Gal. 11 11 7 16/30 42 Gal. 11 11 7 16/30 42 FIND Gal. 11 11 7 16/30 42 TOTAL FLUID PUMPED: gal. 250 KCK WATER fluid
	the / sand		Gal. Gal. Gal. St. 2800 Gal. 256 KcL w8TER PAD. 2420 at 19.9 550 Gal. 11 12 16130 1800 600 Gal. 11 11 14 16130 2400 900 Gal. 11 11 15 16130 4500 1000 Gal. 11 11 16 16130 4500 1000 Gal. 11 17 17 16130 4200 Gal. 11 17 17 16130 4200 Gal. 11 11 7 16130 4200 91 FND Gal. TOTAL FLUID PUMPED: gal. 250 Kck w8TER fluid TOTAL SAND VOL.: 20,000 lbs. 16130 sand	Gal. Gal. G
	المرابع		Gal. Gal. Gal. System of the control of the cont	Gal. 300 Gal. 2% KcL WATER PAD. 2420 at 19.9 550 Gal. 2 6 30 16 30
lbssand		Ibssand	Gal. Gal. Gal. 5/2800 Gal. 2% KcL wATER PAD. 2420 at 19,9 550 Gal. 11 2 16130 1800 600 Gal. 11 11 4 16130 2400 600 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 7 16130 4500 1000 Gal. 11 11 7 16130 4200 Gal. 11 7 1 16130 4200 FND Gal. 11 11 7 16130 4200 Gal. 11 11 7 16130 4200 TOTAL FLUID PUMPED: gal. 2% Kck wATER fluid TOTAL SAND VOL.: 20,000 lbs. 16130 sand	Gal. 2800 Gal. 2% KcL WATER PAD. 2420 at 19.9 550 Gal. "
			Gal. Gal. Gal. Gal. Store Gal. 2800 Gal. 2% KCL WATER PAD. 2420 at 19,9 550 Gal. 11 11 2 16 30 1800 600 Gal. 12 11 3 16 30 2400 600 Gal. 11 11 5 16 30 4500 1000 Gal. 11 11 5 16 30 4500 1000 Gal. 11 11 7 16 30 4200 Gal. TOTAL FLUID PUMPED: gal.	Gal. 2800 Gal.
			Gal. Gal. Gal. Gal. Store Gal. 2800 Gal. 2% KcL WATER PAD. 2420 at 19,9 550 Gal. 11 12 16 30 1800 600 Gal. 12 11 3 16 30 2400 600 Gal. 11 11 4 16 30 2400 900 Gal. 11 11 5 16 30 4500 1000 Gal. 11 11 7 16 30 4200 600 Gal. 11 11 7 16 30 4200 1000 Gal. 11 7 11 7 16 30 4200 1000 Gal. 11 7 7 16 30	Gal. 12800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 2 6 30 16 600 Gal. 3 16 30 29 600 Gal. 4 16 30 29 900 Gal. 4 5 16 30 45 1000 Gal. 1 7 16 30 42 600 Gal. 1 7 16 30 42 Gal. 7 7 6 30 42 TOTAL FLUID PUMPED: gal. 290 KCK WATER fluid
TOTAL DATE OF THE PROPERTY OF		TOTAL ON TO WITH THE PARTY OF T	Gal. Gal. Gal. Gal. Store Gal. 2800 Gal. 2% KCL WATER PAD. 2420 at 19,9 550 Gal. 11 11 2 16130 180. 600 Gal. 11 11 14 16130 2400. 900 Gal. 11 11 5 16130 4500. 1000 Gal. 11 11 7 16130 4200. Gal. 11 11 7 16130 4200. Gal. 11 11 7 16130 4200. TOTAL FLUID PUMPED: gal. gal. gal. Gal. TOTAL FLUID PUMPED: gal. gal. gal. Acid fluid	Gal. 2800 Gal.
TOTAL SAND VOL: 20,000 lbs. 16130 sand	lbs, 16130 sand	TOTAL SAND VOL. $10,000$ lbs. 16130 sand	Gal. Gal. Gal. Gal. 5/2800 Gal. 2%/5cLw8/68 PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 4 16130 2400 900 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 7 16130 4200 600 Gal. 11 11 7 16130 4200 Gal. FIND Gal. TOTAL FLUID PUMPED: Gal. Gal. Gal. Acid	Gal. 300 Gal. 2% 15 1420 at 19.9 550 Gal. 2
		TOTAL SAND VOL.:	Gal. Gal. Gal. Soc Gal. 2% KcL wATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 4 16130 2400 600 Gal. 11 11 4 16130 4500 1000 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 7 16130 4200 Gal. 11 7 16130 4200 Cal. TOTAL FLUID PUMPED: Gal. 6000 Acid	Gal. 2800 Gal. 2% KcL wATER PAD. 2420 at 19.9 550 Gal.
			Gal. Gal. Gal. Strong Gal. 2% KcL water PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 4 16130 2400 600 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 7 16130 4200 Gal. Gal. Gal. TOTAL FLUID PUMPED: Gal. Acld	Gal. 3800 Gal. 2% KCL WATER PAD. 2420 at 19,9 550 Gal. " " 2 6 30 16 600 Gal. " " 3 6 30 25 600 Gal. " " " 16 30 25 900 Gal. " " 5 16 30 45 1000 Gal. " " 5 16 30 42 600 Gal. " " 7 16 30 42 Gal. Gal. I I I I I I I I I
		70.74 0.4 0.70 0.70 0.70 0.70 0.70 0.70	Gal. Gal. Gal. Strong Gal. 2% KcL water PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 4 16130 2400 600 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 7 16130 4200 Gal. Gal. Gal. TOTAL FLUID PUMPED: Gal. Acld	Gal. 3800 Gal. 2% KCL WATER PAD. 2420 at 19,9 550 Gal. " " 2 6 30 16 600 Gal. " " 3 6 30 25 600 Gal. " " " 16 30 25 900 Gal. " " 5 16 30 45 1000 Gal. " " 5 16 30 42 600 Gal. " " 7 16 30 42 Gal. Gal. I I I I I I I I I
		TOTAL DANID VOL. 20.000 lbs 161.30 sand	Gal. Gal. Gal. Gal. 5/2800 Gal. 2%/5cLw8/ERPAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 4 16130 2400 600 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 7 16130 4200 Gal. Gal. TOTAL FLUID PUMPED: Gal. Gal. TOTAL FLUID PUMPED: Gal. Acld	Gal. 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 2
TOTAL SAND VOL: 20,000 lbs. 16130 sand	lbs. 16130 sand	TOTAL SAND VOL: 20,000 lbs. 16/30 sand	Gal. Gal. Gal. Strong Gal.	Gal. 6/ 2800 Gal. 2% KCL WATER PAD. 2420 at 19,9 550 Gal. " " 2 6 30 /6 600 Gal. " " 3 6 30 /6 600 Gal. " " " 16 30 /6 900 Gal. " " 5 16 30 /6 1000 Gal. " " 6 16 30 /6 600 Gal. " 7 16 30 /6 1010 Gal. 1/7 1/7 /6 Gal. 1/8 1/8 /6 10TOTAL FLUID PUMPED: Gal. Acld
TOTAL SAND VOL.: 20,000 lbs. 16130 sand	lbssand	TOTAL SAND VOL.: 20,000 lbs. 16130 sand	Gal. Gal. Gal. Gal. Strong Gal. 2% KcL water PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 4 16130 2400 600 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 7 16130 4200 Gal. Gal. Gal. TOTAL FLUID PUMPED: Gal. Gal. Gal. Acid	Gal. 300 Gal. 2% KCL WATER PAD. 2420 at 19,9 550 Gal. "
TOTAL SAND VOL.: 20,000 lbs. 16130 sand	lbssanasana	TOTAL SAND VOL.: 20,000 lbs. 16130 sand	Gal. Gal. Gal. Gal. St. 2800 Gal. 2% KcL wATER PAD. 2420 at 19.9 550 Gal. 11 12 16130 1100 600 Gal. 11 11 3 16130 1800 600 Gal. 11 11 5 16130 4500 900 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 7 16130 4200 Gal. Gal. 11 11 7 16130 4200 Gal. Gal. 11 11 7 16130 4200 Gal. Gal. 11 11 7 16130 H200 TOTAL FLUID PUMPED: Gal. TOTAL FLUID PUMPED: Gal. 2% Kck water fluid	Gal. 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 2
TOTAL DATE OF THE PROPERTY OF	IDS	101/16 0/1/16 V Out :	Gal. Gal. Gal. Gal. S50 Gal. 100 600 Gal. 11 1 2 16130 1100 600 Gal. 11 1 1 16130 2400 900 Gal. 11 1 1 1 16130 4500 1000 Gal. 11 1 1 1 1 16130 4200 1000 Gal. 11 1 1 1 1 1 16130 4200 10 0 Gal. 10 0 Gal. TOTAL FLUID PUMPED: 10 0 Gal. 11 0 Gal. 12 0 Gal. 13 0 Gal. 14 0 Gal. 15 0 Gal. 16 1 Gal. 17 0 Gal. 18 0 Gal. 19 0 Gal. 10 0 Gal. 1	Gal. 2800 Gal.
TOTAL DATE OF THE PROPERTY OF		101/16 0/1/16 V Out :	Gal. Gal. Gal. Gal. S50 Gal. 100 600 Gal. 11 1 2 16130 1100 600 Gal. 11 1 1 16130 2400 900 Gal. 11 1 1 1 16130 4500 1000 Gal. 11 1 1 1 1 16130 4200 1000 Gal. 11 1 1 1 1 1 16130 4200 10 0 Gal. 10 0 Gal. TOTAL FLUID PUMPED: 10 0 Gal. 11 0 Gal. 12 0 Gal. 13 0 Gal. 14 0 Gal. 15 0 Gal. 16 1 Gal. 17 0 Gal. 18 0 Gal. 19 0 Gal. 10 0 Gal. 1	Gal. 2800 Gal.
TOTAL DATE OF THE PROPERTY OF		101/LEO/110 VOIII	Gal. Gal. Gal. Gal. 5/2800 Gal. 2% KcL wATER PAD. 2420 at 19.9 550 Gal. 11	Gal. 12800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 2 6 30 16 600 Gal. 3 16 30 29 600 Gal. 4 16 30 29 900 Gal. 4 5 16 30 45 1000 Gal. 1 7 16 30 42 600 Gal. 1 7 16 30 42 Gal. 7 7 6 30 42 TOTAL FLUID PUMPED: gal. 290 KCK WATER fluid
101/100/11/10 / 04/1		TO IT TO	Gal. Gal. Gal. Gal. 72800 Gal. 2% KCL WATER PAD. 2420 at 19,9 600 Gal. 11 11 3 16130 1800 600 Gal. 11 11 4 16130 2400 900 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 7 16130 4200 600 Gal. 11 11 7 16130 4200 600 Gal. 11 11 7 16130 4200 1000 Gal. 11 11 7 16130 16100	Gal. 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 2 6 30 10 600 Gal. 11 11 11 16 30 29 16 30 29 16 30 29 16 30 29 16 30 29 16 30 29 16 30 16 3
TOTAL DATE OF THE PROPERTY OF		101/LEO/110 VOIII	Gal. Gal. Gal. Gal. Store Gal. 2800 Gal. 2% KcL WATER PAD. 2420 at 19,9 550 Gal. 11 12 16 30 1800 600 Gal. 12 11 3 16 30 2400 600 Gal. 11 11 4 16 30 2400 900 Gal. 11 11 5 16 30 4500 1000 Gal. 11 11 7 16 30 4200 600 Gal. 11 11 7 16 30 4200 1000 Gal. 11 7 11 7 16 30 4200 1000 Gal. 11 7 7 16 30	Gal. 12800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 2 6 30 16 600 Gal. 3 16 30 29 600 Gal. 4 16 30 29 900 Gal. 4 5 16 30 45 1000 Gal. 1 7 16 30 42 600 Gal. 1 7 16 30 42 Gal. 7 7 6 30 42 TOTAL FLUID PUMPED: gal. 290 KCK WATER fluid
101/10/11/0 VOGI :	IDa	TOTAL ON TO TOTAL	Gal. Gal. Gal. J 2800 Gal. 2% KCL WATER PAD. 2420 at 19,9 550 Gal. 11 11 2 16 30 1100 600 Gal. 11 11 14 16 30 2400 900 Gal. 11 11 5 16 30 4500 1000 Gal. 11 11 7 16 30 4000 600 Gal. 11 11 7 16 30 4200 1000 Gal. 11 11 7 16 30 4200 1000 Gal. 11 11 7 16 30 4200 1000 Gal. 11 11 7 16 30 4200 TOTAL FLUID PUMPED: 1001 Gal. 1002 Gal. 10034 gal. 2% KCK WATER fluid	Gal. 2800 Gal. 2%
TOTAL SAND VOL.: <u>20,000</u> lbs. <u>16130</u> sand	lbssand	TOTAL SAND VOL.: <u>20,000</u> lbs. <u>16130</u> sand	Gal. Gal. Gal. Gal. 5/2800 Gal. 2% KCL WATER PAD. 2420 at 19,9 550 Gal. 11 11 2 16 30 1800 600 Gal. 12 11 3 16 30 2400 600 Gal. 11 11 4 16 30 2400 900 Gal. 11 11 5 16 30 4500 1000 Gal. 11 11 7 16 30 4200 Gal. 11 7 16 30 4200 1000 Gal. 11 11 7 16 30 4200 TOTAL FLUID PUMPED: gal. gal. gal. gal. Acid fluid	Gal. 12800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 2 6 30 16 600 Gal. 3 16 30 29 600 Gal. 4 16 30 29 900 Gal. 4 5 16 30 45 1000 Gal. 1 7 16 30 42 600 Gal. 1 7 16 30 42 Gal. 7 7 6 30 42 TOTAL FLUID PUMPED: gal. 290 KCK WATER fluid
		TOTAL GAND VOL. 20.000 lbs. 16130 sand	Gal. Gal. Gal. Soc Gal. 2% KcL water PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 4 16130 2400 600 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 7 16130 4200 Gal. 11 7 16130 4200 Cal. TOTAL FLUID PUMPED: Gal. Gal. TOTAL FLUID PUMPED: Gal. Acid	Gal. 2800 Gal. 2% KcL wATER PAD. 2420 at 19.9 550 Gal.
		1/19/1 amad	Gal. Gal. Gal. Soc Gal. 2% KcL wATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 4 16130 2400 600 Gal. 11 11 4 16130 4500 1000 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 7 16130 4200 Gal. 11 7 16130 4200 Cal. TOTAL FLUID PUMPED: Gal. 6000 Acid	Gal. 2800 Gal. 2% KcL wATER PAD. 2420 at 19.9 550 Gal.
			Gal. Gal. Gal. J 2800 Gal. 2% KcL wATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 4 16130 2400 900 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 5 16130 4200 1000 Gal. 11 11 7 16130 4200 Gal. 11 7 16130 4200 Gal. 11 11 7 Acld	Gal. 2800 Gal. 2% KcL wATER PAD. 2420 at 19.9 550 Gal. "
11634 gal. 2% KCK WATER fluid	Mary Sylle principal and the state of the st		Gal. Gal. Gal. Soc Gal. 2% KcL wATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 4 16130 2400 600 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 5 16130 4200 1000 Gal. 11 11 7 16130 4200 Gal. 11 7 16130 4200 Cal. TOTAL FLUID PUMPED: Gal. 6000	Gal. 2800 Gal. 2% KcL wATER PAD. 2420 at 19.9 550 Gal.
			Gal. Gal. Gal. 5/ 2800 Gal. 2% KcL wATER PAD. 2420 at 19.9 550 Gal. 11 11 3 16130 1100 600 Gal. 11 11 5 16130 2400 900 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 7 16130 4200 Gal. 11 11 7 16130 4200 Gal. 11 11 7 16130 4200 Gal. 11 11 7 16130 1200	Gal. [1] 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11
			Gal. Gal. Gal. [7] 2800 Gal. 2% KcL WATER PAD. 2420 at 19.9 550 Gal. 11 11 3 16130 1800 600 Gal. 11 11 5 16130 2400 900 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 7 16130 4200	Gal. 2800 Gal. 2%
			Gal. Gal. [7] 2800 Gal. 2% KcL WATER PAD. 2420 at 19.9 550 Gal. 11 11 3 16130 1800 600 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 7 16130 4200	Gal. [1] 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11
	and 2 % KCK WATER fluid		Gal. Gal. Gal. J 2800 Gal. 2% KCL WATER PAD. 2420 at 19,9 550 Gal. 11 11 3 16130 1100 600 Gal. 11 11 3 16130 2400 600 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 6 16130 4000 600 Gal. 11 11 7 16130 4000 Gal. 11 11 7 16130 4200 Gal. 11 11 7 16130 4200	Gal. [1] 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. " " 2 6 30 1 600 Gal. " " 3 6 30 2 600 Gal. " " 1 1 16 30 25 900 Gal. " " 5 16 30 45 1000 Gal. " " 6 16 30 42 Gal. Gal. " 7 7 16 30 42 Gal. Gal. 1 1 7 16 30 42
TOTAL FLUID DUMPED. and % Acid		116,34 gal. 2% KCK WATER fluid	Gal. Gal. Gal. Gal. 600.	Gal. [12800 Gal. 2% KcL WATER PAD. 2420 at 19.9] 550 Gal. 11 11 2 16130 11 600 Gal. 11 11 11 11 16130 25 900 Gal. 11 11 15 16130 45 1000 Gal. 11 11 7 16130 42 Gal.
·		116.34 gal. 2% KCK WATER fluid	Gal. Gal. Gal. Gal. 72800 Gal. 2% KCL WATER PAD. 2420 aT 19.9 650 Gal. 11 11 3 16130 1800 600 Gal. 11 11 4 16130 2400 900 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 6 16130 4500 600 Gal. 11 11 7 16130 4200 Gal. 11 11 7 16130 4200 Gal.	Gal. 2800 Gal. 2% KcL WATER PAD. 2420 at 19.9 550 Gal. 2
I — Control of the Co		TOTAL FLUID PUMPED: gal. 2% KCK WBTER fluid	Gal. Gal. Gal. Gal. 72800 Gal. 270 KcL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 3 16130 2400 900 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 6 16130 4500 600 Gal. 11 11 7 16130 4200 Gal. 11 11 7 16130 4200 Gal.	Gal. 2800 Gal. 2% KcL WATER PAD. 2420 at 19.9 550 Gal. 2
1 <u>F/1/U</u> Gal		TOTAL FLUID PUMPED: gal. 2% KCK WBTER fluid	Gal. Gal. Gal. Gal. 6al. 72800 Gal. 2% KCL WATER PAD. 2420 at 19.9 650 Gal. 11 11 3 16130 1800 600 Gal. 11 11 4 16130 2400 900 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 7 16130 4200	Gal. 1 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. "" 2 /6130 /1 600 Gal. "" " 3 /6130 /2 600 Gal. "" " 1/1 /1 /1 /1 /16130 /25 900 Gal. "" " 5 /6130 45 1000 Gal. "" " 6 /6130 42
"/ <u>FND</u> Gal		TOTAL FLUID PUMPED: gal. 2% KCK WBTER fluid	Gal. Gal. Gal. 1/ 2800 Gal. 2% KcL wATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 11802 600 Gal. 11 11 3 16130 2400 900 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 5 16130 4500	Gal. [1] 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 12 600 Gal. 11 11 11 11 16130 25 900 Gal. 11 11 15 16130 45 1000 Gal. 11 11 16 16130 16130
?' <u>FND</u> Gal		7 FND Gal	Gal. Gal. Gal. 1/ 2800 Gal. 2% KcL wATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 11802 600 Gal. 11 11 3 16130 2400 900 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 5 16130 4500	Gal. [1] 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 12 600 Gal. 11 11 11 11 16130 25 900 Gal. 11 11 15 16130 45 1000 Gal. 11 11 16 16130 16130
, Gal /		7 FND Gal	Gal. Gal. Gal. 1/ 2800 Gal. 2%/SCLWATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 11802 600 Gal. 11 11 11 11 16130 2400 900 Gal. 11 11 5 16130 4500 1000 Gal. 11 11 6 16130 6000	Gal. 1 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. "" 2 /6/30 /1 600 Gal. "" " 3 /6/30 /2 600 Gal. "" " 1/1 /1 /1 /1 /1 /1 /1 /1 /1 /1 /1 /1 /1
Gal	agl. — % — Acld	Gal	Gal. Gal. [1 2800 Gal. 2%	Gal. 1/2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 12 600 Gal. 11 11 11 11 16130 25 900 Gal. 11 11 5 16130 45 1000 Gal 11 11 6 16130 600
Gal	agl. — % — Acld	Gal	Gal. Gal. Gal. [1] 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 11802 600 Gal. 11 11 11 16130 2400 900 Gal. 11 11 5 16130 4500	Gal. 1/ 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 12 600 Gal. 11 11 3 16130 29 600 Gal. 11 11 4 16130 29 900 Gal. 11 1 5 16130 45
600 Gal. // // 7 /6/30 Gal. Gal.	7 16 30 4200 	16 30 4200 4200 600 Gal.	Gal. Gal. Gal. 1/2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 3 16130 2400 600 Gal. 11 11 11 16130 2400	Gal. 1/2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 3 16130 12 600 Gal. 11 11 11 11 16130 25
1000 Gal. 11 11 6 16 30 600 Gal. 11 11 7 16 30	7	1000 Gal.	Gal. Gal. Gal. Gal. 72800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 1100 600 Gal. 11 11 3 16130 2400	Gal. [1 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 12 600 Gal. 11 11 4 16130 25
1000 Gal. 11 11 6 16 30 600 Gal. 11 11 7 16 30	6 16130 6000 7 16130 4200 1 Acid	1000 Gal.	Gal. Gal. Gal. Gal. 72800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 12 16130 1100 600 Gal. 11 1 3 16130 1800	Gal. 1/ 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 2 16130 12 600 Gal. 11 11 3 16130 12
900 Gal. 11 11 5 16130 1000 Gal. 11 11 6 16130 600 Gal. 11 11 7 16130	5 16 30 4500 6 16 30 6000 7 16 30 4200 16 30 Acld	900 Gal. // // 5 /6/30 4500 1000 Gal. // // 6 /6/30 6000 600 Gal. // // 7 /6/30 4200 Gal. // TOTAL FLUID PUMPED: gal. — % — : Acld 1/6/34/ gal. 2% KCK WATER fluid	Volume Fide Colo. Gal. Gal. Gal. 1/ 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. "" 2 16130 1100	Gal
600 Gal. // // // // // // // // // // // // //	$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	600 Gal. // // 5 /6/30 2400 900 Gal. // // 5 /6/30 4500 1000 Gal. // // 6 /6/30 6000 600 Gal. // // 7 /6/30 4200 Gal. // // 7 /6/30 4200 TOTAL FLUID PUMPED: gal. % Acld 1/6/34/ gal. 2% KCK WATER fluid	GalGal	Gal Gal
600 Gal. // // // // // // // // // // // // //	1/ 16 30 2400 5 16 30 4500 6 16 30 6000 7 16 30 4200 agl. — % — : Acld	600 Gal. // // 5 /6/30 2400 900 Gal. // // 5 /6/30 4/500 1000 Gal. // // 6 /6/30 6000 600 Gal. // // 7 /6/30 4/200 Gal. // // 7 /6/30 4/200 Gal. // // 7 /6/30 Acld TOTAL FLUID PUMPED: gal. 2% KCK WOTER fluid	GalGal	Gal
600 Gal. // // // // // // // // // // // // //	3 6 30 800 1/ 6 30 2400 5 6 30 4500 6 6 30 6000 7 6 30 4200 	600 Gal. // // 3 /6 30 /800 600 Gal. // // 16 30 2400 4500 1000 Gal. // // 6 /600 Gal. // // 6 /600 Gal. // // 7 /6 /6 /6 /6 /6 /6 /6 /6 /6 /6 /6 /6 /6	Gal	Gal
550 Gal. // // 2 /6/30 600 Gal. // // 3 /6/30 600 Gal. // // // 16/30 900 Gal. // // 5 /6/30 1000 Gal. // // 6 /6/30 Gal. // // 7 /6/30	$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	550 Gal.	Gal.	Gal
550 Gal. // // 2 /6/30 600 Gal. // // 3 /6/30 600 Gal. // // // // // // // // // // // // //	$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	550 Gal.	Volume Fidia Cono.	Gal
1 2800 Gal. 2% KCL WATER PAD. 2420 at 19,9 550 Gal. 11 11 2 16130 600 Gal. 11 11 3 16130 600 Gal. 11 11 5 16130 1000 Gal. 11 11 6 16130 1000 Gal. 11 11 7 16130 Gal. 11 11 7 16130 Gal.	$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 2 6 30 1000 600 Gal. 3 16 30 2400 600 Gal. 1 5 16 30 2400 900 Gal. 6 16 30 4500 1000 Gal. 1 7 16 30 4200 Gal. 7 6 16 30 4200 TOTAL FLUID PUMPED: gal. % Acld Acld 116 34 gal. 2.30 KCK WATER fluid	Volume Fidia Contr.	
Gal. 2800 Gal. 2%	$8PAD$, $2420 \text{ at } 19.9$ $2 \qquad 6 30 \qquad 100$ $3 \qquad 6 30 \qquad 800$ $4 \qquad 6 30 \qquad 2400$ $5 \qquad 6 30 \qquad 4500$ $6 \qquad 6 50 \qquad 6000$ $7 \qquad 6 30 \qquad 4200$ $16 30 \qquad 4200$	Gal. 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal.	Volume Fluid Conc. Size Willing	
Gal. 2800 Gal. 2%	8PAD, $2420 a7 19.9$ $2 6 30 100$ $3 6 30 2400$ $4 6 30 2400$ $5 6 30 4500$ $6 6 30 6000$ $7 6 30 4200$ $16 30 4200$	Gal. 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal.	Conc. Size William	volume · mid
Gal. Gal. Gal. 5/ 2800 Gal. 2% KCL WATER PAD. 2420 at 19.9 550 Gal. 11 11 3 16130 600 Gal. 11 11 11 16130 900 Gal. 11 11 5 16130 1000 Gal. 11 11 7 16130 Gal. 11 11 7 16130 Gal. 11 11 7 16130	8PAD, $2420 at 19.9$ 2	Gal. Gal. Gal. Gal. 6/2800 Gal. 2% KcL wATER PAD. 2420 at 19,9 550 Gal. 11	\hlima	Conc. Size Volum



TREATMENT REPORT

Volun	ment (Comp	Fluid	iesTern	<i>516E,</i> # Conc.	*) #* *	Sand Char	acteristics
1 76		Gal			Conc.			
		Gal					Size	Volume
		~~						
		Gal			ı		,	The state of the s
				WATER	0	PAD .	3,000 PS 1 OT	19000
(5	600	•		15	2		20140	1200
	000			//	3		20140	3000
	000	•		11	41	#150 B. C.	20140	4000
	00	-		11	5		20140	7500
	500			//	6		20140	15000
	000			//	E		16130	12000
	00			//	7		16130	17500
48	330	Gal	2% KCL	WATER	0	FLUGH		0
YIEN		DIIIA	IDED: 2	W ROOM	aal.			Acld
	\L "LQ	J - VIT		3604	gal. 270	KCL wally		_ _ fluid
` T/* \TA	AL CAN	ים ער		70700	_	20/40	sand	
IOIA	イドウイバ	יטע עו	تمنیت ۱۰- تر ک	29500	lbs.	16 130	sand	
				W			sand	
					IDS.		Dauxile	
Flusi	hed w	⊒ll will	1 43	30	_gal. of _ <i>2.2</i>	hall action see	<u>s</u> g	
	-1	b	all sealer	s were pu	mped. Was l	ball action see	n?	
Barre	eis of i	.000 T	O KACOV	27AM	مر مر	3000	nel min =	1200
Avg.	. Treat	ng Pre	988Ur⊖ = .to = 7	A. X. C. C.	psi, mai	x = <u>3000</u> x = <u>35</u>	poi, min =	1900 b
	, irean	ug ka	IU =		phur uid	^ <u></u>	" Mini	
AVG.	110	<i>[]</i>	~~! ~ ~ !	**	nel 10	min =	nsi. 15 min.	. =



Page 1 of 2

Balcron Oil DAILY OPERATING REPORT

DATE

10/5/93

JONAH UNIT PARTNERS' DAILY REPORT

BALCRON MONUMENT FEDERAL #14-5J

Operator: EREC/Balcron

BOD WI: 79.78%

Location: SW SW Section 5, T98, R17E Duchesne County, Utah

Prospect: Jonah Unit/Monument Butte PTD: 5,700' Green River Oil - Dev.

10-5-93

---TIGHT HOLE---

TD: 1,735' (1,256') Day 2 Formation: Green River

MW water

Present Operation: Drilling Drill, survey, & rig service.

DC: \$24,880

CC: \$55,774

BALCRON MONUMENT FEDERAL #14-11

Operator: Balcron/EREC

BOD WI: 100%

Location: SW SW Section 11, T98, R16E

Duchesne County, Utah

Prospect: Monument Butte

10-4-93

Completion

MIRU Cannon Well Service Rig #1. RU tanks & pump. Fill frac

tanks.

DC: \$13,927

BALCRON MONUMENT FEDERAL #23-11

Operator: Balcron/EREC

BOD WI: 79.78%

Location: NE SW Section 11, T98, R16E

Duchesne County, Utah

Prospect: Monument Butte

---TIGHT HOLE---

---TIGHT HOLE---

10-4-93 Completion

> Csg vac. TIH w/BP retrieving tool & tbg. Tag sand fill @ 4630' KB. Circ sand out to 4750' (BP), release BP & TOOH w/tbg & BP. TIH w/BP retrieving tool, 1 jt 2-7/8" tbg, 5-1/2" packer, SN & 2-7/8" tbg, tag sand fill at 4900' KB, circ sand out to 503=26', set packer @ 4656'. Made 6 swab runs, recovered 30 BW, trace of oil. SWIFN.

DC: \$7,435



DIVISION OF OIL, GAS & MINING BALCRON MONUMENT FEDERAL #14-11J

Operator: Balcron/EREC

BOD WI: 100%

Location: SW SW Section 11, T98, R16E

Duchesne County, Utah

Prospect: Monument Butte

10-6-93 Completion

---TIGHT HOLE---

CP - 15 psi. RU Western to frac 5553'-56' KB. Pressure test surface equipment to 4000 psi - OK. Refer to Treatment Report 1st Stage attached. Break @ 3000 psi .5 BPM, back to 2800 psi @ 5.0 BPM. Start pad, cross link quit, shut down. Start pumping, 3000 psi @ 0.2 BPM, shut down, call for 500 gals 15% HCL. Start acid, balance acid 500' above perforations. TOOH w/tbg, RU to break down w/acid & frac. Refer to Treatment Report. RU Cutter Wireline to set RBP @ 5210' KB & perforate 5175'-88' 2 SPF (26 holes). RD Cutters. TIH w/5-1/2" packer, SN & 2-7/8" tbg, set packer @ 5122'. SWIFN. Load to recover 486 BW. DC: \$23,686

BALCRON MONUMENT FEDERAL #23-11J

Operator: Balcron/EREC

BOD WI: 79.78%

Location: NE SW Section 11, T98, R16E

Duchesne County, Wtah

Prospect: Monument Butte

10-6-93 Completion

---TIGHT HOLE---

Csg - vac. TIH, tag sand @ 4995' KB, circ clean to BP @ 5045' KB,

retrieve BP, TOH w/tbg & BP. TIH w/the following:

Landed at KB Length 31.85' 5296.20' KB 1 jt 2-7/8" tbg EUE, J-55, 8RD, 6.5# 5264.35' KB 3.05 one 2-7/8" x 3' perf sub 5261.30' KB 1.15' one seat nipple 5260.15' KB. 168 jts 2-7/8" tbg EUE, J-55, 8RD 6.5# 5250.15' ND BOP, NU wellhead. TIH w/the following: BHP, 2-1/2" x 1-1/2" x 16' RHAC w/RA plunger 3/4" x 25' rods plain one 3/4" x 8' pony one 3/4" x 6' pony one 3/4" x 2' pony one 1-1/4" x 16' polish rods SM

Pressure test tbg to 500 psi - OK. RDMO

DC: \$7,118

Balcron Oil DAILY OPERATING REPORT

DATE:

10/25/93

JONAH UNIT PARTNERS' DAILY REPORT

BALCRON MONUMENT FEDERAL #14-5J

Operator: EREC/Balcron

79.78% BOD WI:

Location: SW SW Section 5, T98, R17E Duchesne County, Utah

Prospect: Jonah Unit/Monument Butte

10-22-93 Completion

---TIGHT HOLE---

CP - 900 psi. Flow back 40 BW. TIH w/1 jt 2-7/8" tbg, packer, SN, & 178 jts tbg. Tag sand fill @ 5480' KB, circ sand out to 5652', set packer @ 5410' KB. Made 22 swab runs. Recovered 100 BW. Last 5 runs 20% oil,

still getting sand back. SWIFN. Load to recover 445 BW.

DC: \$1,834

BALCRON MONUMENT FEDERAL #23-11

Operator: Balcron/EREC

BOD WI: 79.78%

Location: NE SW Section 11, T9S, R16E

Duchesne County, Utah

Prospect: Monument Butte

10-22-93 Completion

---TIGHT HOLE---

Change vent system on production tanks.

DC: \$595

BALCRON MONUMENT FEDERAL #41-15J

Operator: EREC/Balcron

BOD WI: 79.78%

Location: NE NE Section 15, T98, R16E

Duchesne County, Utah

Prospect: Jonah Unit / Monument Butte

10-22-93 Completion

---TIGHT HOLE---

TIH w/1 BHP 2-1/2" x 1-1/2" x 16' RWAC w/PA plunger; 222 3/4" x 25' plain rods; two 3/4" x 8' ponys; one 1-1/4" x 16' polish rod. RDMO.

Load to recover 787 BW.

DC: \$6,940

BALCRON MONUMENT FEDERAL #32-15

Operator: Balcron/EREC

79.78% BOD WI:

Location: SW NE Section 15, T98, R16E

Duchesne County, Utah

Prospect: Monument Butte

10-22-93 Completion

---TIGHT HOLE---

MIRU Cannon Well Service Rig #1. RU Schlumberger to run CBL. RD

Schlumberger.

DC: \$1,334

Page 1 of Tag

Balcron Oil DAILY OPERATING REPORT

DATE 10/26/93

JONAH UNIT PARTNERS' DAILY REPORT

BALCRON MONUMENT FEDERAL #14-5J

Operator: EREC/Balcron

BOD WI: 79.78%

Location: SW SW Section 5, T98, R17E

Duchesne County, Utah

Prospect: Jonah Unit/Monument Butte

10-25-93 Completion

---TIGHT HOLE---

CP - 0, TP - 350 psi. Flow 15 BO. Made 5 swab runs, recovered 40 BF, 35 oil, 5 wtr, & no sand. Release packer, tag sand fill @ 5630' KB. Circ clean to 5652' (PBTD), TOOH w/tbg, \$N, packer & 1 jt tbg. SWIFN.

DC: \$2,411

BALCRON MONUMENT FEDERAL #23-11 Operator: Balcron/EREC

BOD WI: 79.78%

Location: NE SW Section 11, 798, R16E

Duchesne County, Utah

Prospect: Monument Butte

10-25-93 Completion

---TIGHT HOLE---

Hook up frac tank for temp production tank.

DC: \$1,255

BALCRON MONUMENT FEDERAL #32-15

Operator: Balcron/EREC

BOD WI: 79.78%

Location: SW NE Section 15, T95, R16E

Duchesne County, Utah

Prospect: Jonah Unit / Monument Butte


---TIGHT HOLE---

10-25-93 Completion

TIH W/4-3/4" bit, csg scraper & 180 jts 2-7/8" tbg. Tag PBTD @ 556' KB, circ hole clean W/120 bbls 2% KCL wtr. TOOH w/tbg scraper & bit. Pressure csg & BOP 100 psi - OK. RU Schlumberger to perf 5496'=98' (2 SPF). RD Schlumberger. TIH w/1 jt 2-7/8" tbg, packer, SN & 175 jts tbg, set packer @ 5431' KB. EQT @ 5466' KR. RU Dowell to do acid breakdown - refer to treatment report attached. Pressure test surface equipment to 4850 psi - QK. Spot acid at perfs, could not breakdown w/4450 psi, packer failed, TOOH w/thg & packer, TIH w/new packer & thg, set packer @ 4691', pressure to 4025' psi for 10 min, no break, packer failed. POOH 8 stds. SWIFN. DC: \$33,153



1601 Lewis Avenue P.O. Box 21017 Billings, MT 59104



Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361

Sando (p. 1941) Ologano alamada

October 22, 1993

Bureau of Land Management 170 South 500 East Vernal, UT 84078

Gentlemen:

RE: Balcron Monument Federal #23-11

NE SW Section 11, T9S, R16E

Duchesne County, Utah

Enclosed is our Report of First Production for the referenced well.

Please feel free to contact me if you need any additional information.

Sincerely,

Molly M. Conrad

Operations Secretary

/mc

cc: State of Utah - Division of Oil, Gas, & Mining

Form 3160-5 (June 1990)

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31 1993

		Expires:	March	31, 199	73
5.	Lease	Designati	on and	Scrial	No.

U-096550 SUNDRY NOTICES AND REPORTS ON WELLS 6. If Indian, Allottee or Tribe Name Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT-" for such proposals 7. If Unit or CA, Agreement Designation SUBMIT IN TRIPLICATE Jonah Unit 1. Type of Well Oil Well 8. Well Name and No. Balcron Monument Fed. #23-11 2. Name of Operator Equitable Resources Energy Company, Balcron Oil Division 9. API Well No. 3. Address and Telephone No. 43-013-31369 P.O. Box 21017; Billings, MT 59104 (406) 259-7860 10. Field and Pool, or Exploratory Area 4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Monument Butte/Grn.River 11. County or Parish, State NE SW Section 11, T9S, R16E Duchesne County, UTAH 1787' FSL, 2147' FWL CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
Notice of Intent	Abandonment	Change of Plans	
X Subsequent Report	Recompletion Plugging Back Casing Repair	New Construction Non-Routine Fracturing Water Shut-Off	
Final Abandonment Notice	Altering Casing X Other Report of 1st	Conversion to Injection Dispose Water	
	Production	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

First production on this well was at 11:30 a.m. on 10-21-93.



Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Form 3160-5 (June 1990)

UNITED STATES DEPARTMENT OF THE INTERIOR

F	orm a	PPRO	OVE	D
Budget	Bureau	No.	1004	1-013
Expi	ires: M	arch	31, 1	993

	Expires:	Marc	:n 3	יעו, ו	13
5. Lease	Designat	ion ar	id S	erial	No

BUREAU OF 1	LAND MANAGEMENT	5. Lease Designation and Serial No.
Do not use this form for proposals to dr	AND REPORTS ON WELLS ill or to deepen or reentry to a different reservoir. R PERMIT—" for such proposals	U-096550 6. If Indian, Allottee or Tribe Name
SUBMIT	IN TRIPLICATE	7. If Unit or CA, Agreement Designation
Type of Well Oil Gas Well Well Other		Jonah Unit 8. Well Name and No.
Name of Operator Equitable Resources Energy Co	mpany, Balcron Oil Division	Balcron Monument Fed. #23-11 9. API Well No.
Address and Telephone No. P.O. Box 21017; Billings, MT	59104 (406) 259-7860	43-013-31369 10. Field and Pool, or Exploratory Area
NE SW Section 11, TS		Monument Butte/Grn.Rive
1787' FSL, 2147' FWL	•	Duchesne County, UTAH
CHECK APPROPRIATE BOX	s) TO INDICATE NATURE OF NOTICE, REPO	RT, OR OTHER DATA
TYPE OF SUBMISSION	TYPE OF ACTION	
Notice of Intent	Abandonment	Change of Plans New Construction
Subsequent Report	Recompletion Plugging Back	Non-Routine Fracturing Water Shut-Off
Final Abandonment Notice	Casing Repair Altering Casing	Conversion to Injection

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.) 13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

X Other Site Security Diagram

Attached is the Site Security Diagram for this well.




DIVISION OF OIL, GAS & MINING


Dispose Water

4. I hereby certify that the foregoing is true and correct Signed Shull Shuman	Coordinator of Environmental Title and Regulatory Affairs	Date
(This space for Federal or State office use)		
Approved by	Title	Date

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Equitorie Resources Energy Corpany Balcron Monument Federal 23-11 Production Facility Diagram





Form 3160-5 (June 1990)

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

	F	ORM	APPR	OVED	
	Budget	Bure	eau No.	1004-013	5
				31, 1993	
_					

5. Lease Designation and Serial No. U-17985

6. If Indian, Allottee or Tribe Name

Do not use this form for proposals to c Use "APPLICATION FO	irill or to deepen or reentry to a different reservoir OR PERMIT—" for such proposals	n/a
SUBMI	TIN TRIPOPATE I TO TAITIAL	7. If Unit or CA, Agreement Designation
1. Type of Well Soliton Gas Other	CUNHIDENTIAL	Jonah Unit 8. Well Name and No. Balcron Monument Federal #23-1:
Equitable Resources Energy Company	, Balcron Oil Division	9. API Well No.
3. Address and Telephone No.	(/00) 250 7000	43-C13-31369 10. Field and Pool, or Exploratory Area
P.O. Box 21017, Billings, MI 5910 4. Location of Well (Footage, Sec., T., R., M., or Survey	4 (406) 259–7860	Monument Butte/ Green River
NE SW Section 11, T9S, R16E	1787' FSL, 2147' FWL	11. County or Parish, State Duchesne County, Utah
2. CHECK APPROPRIATE BOX	((s) TO INDICATE NATURE OF NOTICE, REP	ORT, OR OTHER DATA
TYPE OF SUBMISSION	TYPE OF ACTIO	Ν
X Notice of Intent	Abandonment Recompletion	Change of Plans New Construction
X Subsequent Report	Plugging Back Casing Repair	Non-Routine Fracturing Water Shut-Off
Final Abandonment Notice	Altering Casing X Other NII 2B	Conversion to Injection Dispose Water
	all pertinent details, and give pertinent dates, including estimated date of star	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)
Any water produced by 7this well w commercial disposal facility. See	ill be held in a produced water tank and then Site Security Diagram for location of water t	hauled to a ank.
• •	· .	NOV 1 2 1993
		DIVISION OF OIL, GAS & MINING
14. I hereby certify that the foregoing is true and correct Signed Dobles Scharmer	Coordinator of Environmental a Regulatory Affairs	nd Date <u>11–8–93</u>
(This space for Federal or State office use). Approved by	Title	Date
Title 18 U.S.C. Section 1001, makes it a crime for any pers or representations as to any matter within its jurisdiction.	on knowingly and willfully to make to any department or agency of the Un	ited States any false, fictitious or fraudulent statements

						-		·		i	
1.	Well name	e and num er: <u>43-01</u> 3	ber: 3-31369	Balcron M	onument Federa	1 #23–11			• .		
2.	Well loca	ation: QQ	<u>NESW</u> s	ection <u>11</u>	_ township :	98_ range	<u>16E</u> county <u>Duche</u>	esne			٠
3.	Hell open		Equitable Re	esources Ener	ngy Company, B	alcron Oil I			· ·		
, =	Address:		Billings, M		• .		phone: (406) 25	9–7860			
4.	Drilling Address:			on Drilling ver 40			phone: (304) 47	· 2-4610			
				thannon, W	26201		-				
·····	······································										
5.	Water end	countered	(continue	on reverse	side if neces	sary)					
	De	epth		Volume			Quality		Comment of the second	madel white the	-
	from	to	(f	low rate o	r head)	(fr	esh or salty)	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		MILE	13
			No wate	r encountere	d.				NOV 1	2 1993	.
			<u> </u>						DIVIS	ON _O	•
								OIL	, GAS	& MIN	r VING
•		· · · · · · · · · · · · · · · · · · ·	· · ·			1					
										•	
_			~ ~							•	
6.	Formation	n tops:	See Ge	ologic Repor	t	•			•		
			•					······			
If re	an analy: port to th	sis has b his form.	een made	of the wa	iter encoun	tered, pla	ease attach a co	opy oi	f the		
I	certify th	hat this	report i	s true and	complete	to <i>f</i> he be:	st of my knowle	dge.		1	
Nai	me <u>Bobbie</u> tle Coordin	Schuman . ator of Env	ironmental a		Signature Date <u>11-</u> 8	Doblin	2 Schuma	<u>~</u>			
Cor	Reg	ulatory Affa	ars	~~~~]	



1601 Lewis Avenue P.O. Box 21017 Billings, MT 59104

Office: (406) 259-7860

FAX: (406) 245-1365 🔲

FAX: (406) 245-1361 🔯

November 9, 1993

NOV 1 2 1993

Bureau of Land Management 170 South 500 East Vernal, UT 84078

DIVISION OF OIL, GAS & MINING

Gentlemen:

RE: Balcron Monument Federal #23-11

NE SW Section 11, T9S, R16E

Duchesne County, Utah

Enclosed are the following items for the referenced well:

Well Completion Report

Site Security Diagram (Sundry Notice)

NTL2B Disposition of Produced Water (Sundry Notice)

Sincerely,

Molly Conrad

Operations Secretary

/mc

Enclosures

Utah Division of Oil, Gas and Mining: enclosed is the Report of Water Encountered (Utah

Form 7)

UI ED STATES

SUBMIT IN DUPL



ronn approved. Budget Bureau No. 1004-01 Expires August 31, 1985

		August			137
		HOITAND			
T-1798	75-	11.00	A IF	「「)

DEDARTMENT OF THE INCOME.	(Section 1)	· -	
DEPARTMENT OF THE INTERIOR	structions on	5. LEASE DESIG	NATION AND
BUREAU OF LAND MANAGEMENT	reverse side)	LT 1700E	

		~								1 - 0 17 707	_ <u>U</u>	0-10-20
WELL CO	MPLETION	OR I	RECON	APLETI	ON	REPOR	RT AN	ND LO	G *	1 ,	I, ALLO	TTEE OR TRIBE NAME
1a. TYPE OF WE	LL: 011.	X	GAS WELL	1						n/a	T	
b. TYPE OF COM		ا،ا شکا	WELL L	J bi	, v 🗀	Other	MM		F1 58 1 8			TNAME
NEW NT	WORK [] DEI	er-	ring	DIFF	. [1116	Jonah Un		N 1 17 18
WELL,		·	BACK L	J REST	'R. L	Other		.y_ I Dol be	-1-8-88-	I the		ment Federal
Fouitable	Resources Ene	rgy Con	pany. E	Balcron	Oil D	ivision		. : *		9. WELL NO.		HIL TENELAL
3. ADDRESS OF OPE			1 37					• • • • • • • • • • • • • • • • • • • •		- #23 - 11		
P.O. Box 2	21017, Billing	s, M	59104	((406) 2	2597860).				ND POC	L, OR WILDCAT
4. LOCATION OF WE				ccordance	with ar	y State re	equireme	nts) *		-		te/Green River
	.787' FSL, 214										R., M.,	OR BLOCK AND BURYEY
At total depth	terval reported be									NE SW S€	etia	n 11, T9S, R16E
At total depth				1 14 pri	MIT NO		DAME	E ISSUED		12. COUNTY	O.P.	13. STATE
				1 -	····· ·013–31			21-92		PARISH		1
5. DATE SPUDDED	16. DATE T.D. R	EACHED	17. DATE	2						Duchesne		UIAH ELEV. CASINGHEAD
8-30-93	9-23-93		10	-21 -9 3			56	22' GL	1	RT, GR, ETC.) *		
O. TOTAL DEPTH, MD	ı		D., MD A T	VD 22.	160 M. 71		,		LLED BY	ROTARY TOO	LS	CYRPE TOOFS
5750'		671'		<u>l.:</u>			ı/a	<u> </u>	→	Sfc - TD	,- ,-	
. PRODUCING INTE					NAME (MD AND T	VD) *				2	5. WAS DIRECTIONAL SURVEY MADE
5155'-5162			4962 '- 4	<i>9</i> 98'	(Freen Ri	ver			•		No
5171'-5181											07	
DLL - FDC	- CNL - CR	RUN		_						1		AS WELL CORED
BLIGHTCLE		106		28-93				· · · · · · · · · · · · · · · · · · ·		1		···
CABINO BIZE	WEIGHT, LB./	****	CASIN			ort all str	ings set		MENTING			,
8–5/8"	24#		277	(MD)						RECORD		AMOUNT PULLED
5-1/2"	15.5#					2-1/4"		0 sxs '(72 1		
7-1/2	17.3#		5730'		/	7–7/8''		0 sxs 50		z and		
		_					_9	0 sxs Hi	TILL .			<u>n/a</u>
	<u> </u>	LINER R	PCOPD.	<u></u> !			t	1 20	<u> </u>	TURING PRO	\D.F.	
SIZE	TOP (MD)	BOTTOM		SACKS CE	MENTE	SCREEN	(MD)	30.		TUBING RECO		PACKER SET (MD)
n/a			····-/ -			300020	(5.57	$\frac{3.22}{2-7/}$	' <u>Q</u> ''-	52961	<u>ν,</u>	
				·				- 2 //		J230		n/a
. PERFORATION RE	CORD (Interval, si	re and nu	mber)			32.	Α.	CID SHOT	FRACT	URE, CEMENT	r som	PPAP PTC
5155'-5162	' (2 SPF) ·	4710'	-47 17'	(2 SPF)			INTERVA		-, -	OUNT AND KIN		
5171'-5181				(= 221)		1	-5181'	(2,0)	_1			29,180# sand
	441, 48481, 4	350', 48	3581,48	364'. 4º	9621	71.75	JIOI		77/2	52 bbls 2% 1	CT T	ntor
	41, 49921, 499					4840	- 4998	श				29,500#16/30 sa
	hole per stat		,			-10-10		<i></i>				% KCL water.
.•			·		PROI	DUCTION			1 W/ 2	oz Dons gen	164 2	10 ILLI WALEL.
TB FIRST PRODUCT	TON PRODU	CTION ME	THOD (FI	owing, ga			ize and	type of pu	mp)			s (Producing or
10-21-93		Pump -	1-1/2"	Insert	Pump						t-in) _	roducing
TE OF TEST	HOURS TESTED		E SIZE	PROD'N	FOR	OIL-BE	L.	GASN	CF.	WATER-BBL		UAS-OIL RATIO
10 - 25 - 93	2/4	n,	/a	TEST P	EK10D	110		16	5	20		1500
OW, TUBING PRESS.	CABINO PRESSUR		ULATED	011,B	Bt	G A	s-MCF.	<u> </u>	WATER-	-HBL.	OIL G	RAVITY-API (CORR.)
n/a	n/a		OUR RATE	110)	1	165	İ	20			34
. DISPOSITION OF G		fuel, vent	ed, etc.)			<u>'</u>				TEST WITNES	SED B	Y
Used for fi	æl.									Dale Gr	iffin	
LIST OF ATTACH	MENTS				i					·		
. I hereby certify	that the foregoin	g and att	ached info	ormation	is comn	lete and c	orrect s	s determin	ed from	all available re	ecords	
\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	11: 1	_/			Č	oordina	tor of	EUATION	mental.	and		
SIGNED	vue xc	uun	ian	TIT	LE	Regula	tory A	ffairs		DATE	<u> 11</u>	-6-93
Bobt	oie Schuman			~ .								

FORMATION	TOP						· · · · · · · · · · · · · · · · · · ·
		воттом	DESCRIPTION, CONTENTS, ETC.		NAME	TC	
·			•			MEAS, DEPTH	TRUE VERT. DEPT
			·- •				
,	·						
			y nomi		Con Conlocia	Homoretr	
			No DST's run.		See Geologic	report.	
,	-						
•			·				
				Anna Carrier C			
			₽ /				
			DIVISION OF GAS & MINING	NOV 1 2 1993			
			AS AS			1	
			<u>∞</u>	2 19			
			N S C	35.			1
			ING				
						•	
• .							•
• •				. •			
				•			



1601 Lewis Avenue P.O. Box 21017 Billings, MT 59104 Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361

November 30, 1993

Bureau of Land Management 170 South 500 East Vernal, UT 84078

Gentlemen:

As requested, enclosed are sundry notices which are being resubmitted to comply with Onshore Order #7 which covers disposition of produced waters. These are being resubmitted for the following wells:

Balcron Monument Federal #32-11
Balcron Monument Federal #22-5
Balcron Monument Federal #13-5
Balcron Federal #41-21Y
Balcron Federal #21-13Y
Balcron Federal #21-9Y
Balcron Monument Federal #23-5
Balcron Monument Federal #23-11
Balcron Federal #22-10Y
Balcron Federal #44-14Y
Balcron Federal #24-3Y

These are to replace the sundry notices which were filed as NTL2B.

Also enclosed for your information is a copy of the State approval of the primary facility at which we dispose of our produced water.

Sincerely,

Bobbie Schuman

Coordinator of Operations,

Environmental and Regulatory Affairs

/rs

Enclosures

cc: Utah Division of Oil, Gas and Mining

Form 3160-5 (June 1990)

UNITED STATES DEPARTMENT OF THE INTERIOR **BUREAU OF LAND MANAGEMENT** DEC 0 1 1993

DIVISION OF

FORM APPROVED Budget Bureau No. 1004-0135

(Note: Report results of multiple completion on Well

Expires:		
 Decises	 	

				•				
11-	'n	a	SI	:50	1			

JOHL GAS & MINING

Do not use this form for proposals to di	ill or to deepen or reentry to a different reservoir. R PERMIT—" for such proposals	n/a
SUBMIT	IN TRIPLICATE	7. If Unit or CA, Agreement Designation
1. Type of Well Oil Well Gas Well Other 2. Name of Operator		Jonah Unit 8. Well Name and No. Balcron Monument Fed. #23-11
Equitable Resources Energy Co 3. Address and Telephone No. P.O. Box 21017; Billings, MT	· · · · · · · · · · · · · · · · · · ·	9. API Well No. 43-013-31369 10. Field and Pool, or Exploratory Area
4. Location of Well (Footage, Sec., T., R., M., or Survey E NE SW Section 11, TS 1787' FSL, 2147' FWL	9S, R16E	Monument Butte/Grn.River 11. County or Parish, State Duchesne County, UTAH
12. CHECK APPROPRIATE BOX	s) TO INDICATE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION	TYPE OF ACTION	
Notice of Intent Subsequent Report	Abandonment Recompletion Plugging Back Casing Repair	Change of Plans New Construction Non-Routine Fracturing Water Shut-Off
Final Abandonment Notice	Altering Casing Other Onshore Order #7	Conversion to Injection Dispose Water

Completion or Recompletion Report and Log form.) 13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

> Any water produced by this well will be held in a produced water tank and trucked to a commercial disposal facility. The primary facility to be used is the R.N. Industries produced water disposal facility located in Section 9, T2S, R2W in Duchesne County, Utah. A copy of the State-issued permit for that facility is on file at the Vernal Bureau of Land Management. If for some reason the operator is unable to use this primary disposal facility, the produced water will be trucked to another State-approved disposal facility. If applicable, Operator has received approved Right-of-Way access to this well location from the Vernal Bureau of Land Management.

Λ		•	
14. I hereby certify that the foregoing is fade and correct		or of Environmental Latory Affairs	Date November 30, 1993
Robbie Schuman (This space for Federal or State office use)			
Approved by	Title	Accepted of Utah Di	b y ∘the State ivision of
Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly	and willfully to make to any		
or representations as to any matter within its jurisdiction.	See Instruction on R	Date: / Z	_3_73

FEB 1 7 1991

DAILY OPERATING REPORT

43-013-31369

BALCRON MONUMENT FEDERAL #23-11 Location: NE SW Section 11, T9S, R16E

Duchesne Councy, _ 2100' FWL, 1980' FSL 5.750' Formation: Green River

Monument Butte Prospect Elevations: 5,622' GL

Contractor: Union Drilling Rig #17

Operator: Balcron/EREC

Spud: 8/30/93 - Leon Ross 8-5/8" @ 877' Union KB Casing: 5-1/2" @ 5730.67'

Tubing: 2-7/8" @ 5296.20' KB

8-25-93 Start location.

8-26-93 Work on location.

8-27-93 Finish location.

Move on Ross air rig. Spud 12:30 8-30-93. Drill 12-1/4" hole to 8-30-93 268'.

Pull drill collars out of hole & run 6 jts 8-5/8" csg. Dowel cmt 8-31-93 well. Plug down & 2 pm.m 8-31-93. Csq detail as follows: Guide shoe - .70; 1 jt 8-5/8" 24# shoe jt - 44'; insert float; 5 jts 8-5/8" 24# csg - 225.31'; 3 centralizers; Csg landed @ Union KB Dowell cmt w/150 sxs Class "G" w/2% CCL + 1/4#/sx Celloflakes. Good circ approximately 6 bbls cmt return. CC: \$11,239 DC: \$11,239

9-13-93 TD: 451' (174') Day 1 Formation: Uintah MW 8.3 VIS 27 pH 10.5 Present Operation: Drilling

Test BOP & manifold to 2000# - OK. Test surface pipe to 1500# - OK. PU collars & drill cmt, drill & survey.

CC: \$23,776 DC: \$12,527

TD: 476' (0') Day 3 9-15-93 Formation: Uintah

Present Operation: WO repairs. CC: \$25,414 DC: \$972

9-16-93 TD: 476' (0') Day 4 Formation: Uintah

Present Operation: Repair rig.

DC: \$400 CC: \$25,814

TD: 1,825' (1,349') Day 5 9-17-93 Formation: Green River MW 8.3 VIS 27 pH 11 Present Operation: Drilling Repair rig, drill, survey, & clean on rig. CC: \$42,800 DC: \$19,986

BALCRON MONUMENT FEDERAL #23-11

Location: NE SW Section 11, T9S, R16E

Duchesne County, Utah

---TIGHT HOLE---

- 9-18-93 TD: 3,118' (1,293') Day 6
 Formation: Green River
 MW 8.4 VIS 27 pH 10.5
 Present Operation: Drilling
 Drill, survey, & clean on rig.
 DC: \$16,322 CC: \$59,122
- 9-19-93 TD: 3,956' (838') Day 7
 Formation: Green River
 MW 8.4 VIS 27 pH 10.5
 Present Operation: Drilling
 Drill, survey, change airhead rubber.
 DC: \$10,931 CC: \$70,053
- 9-20-93 TD: 4,940' (984') Day 8
 Formation: Green River
 MW 8.4 VIS 27 Ph 10.5
 Present Operation: Drilling
 Drill, survey & clean on rig.
 DC: \$15,461 CC: \$85,514
- 9-21-93 TD: 5,507' (567') Day 9
 Formation: Green River
 MW 8.4 VIS 27 pH 10.5
 Present Operation: Trip Out.
 Drill, survey, blow hole, circ w/fluid. Start trip out for bit.
 DC: \$8,005 CC: \$93,519
- 9-22-93 TD: 5,750' (243') Day 10
 Formation: Green River
 MW 8.4 VIS 27 pH 10.5
 Present Operation: RU loggers.
 Trip for bit, drill, circ for logs, survey & TOH.
 DC: \$5,175 CC: \$98,694

2:30 a.m. 9-23-93.

BALCRON MONUMENT FEDERAL #23-11 Location: NE SW Section 11, T9S, R16E Duchesne County, Utah

---TIGHT HOLE---

9-27-93 Completion

MIRU, TIH w/4-3/4" drag bit, 5-1/2" scraper & 182 jts 2-7/8" EUE, J-55 tbg. Tag PBTD @ 5671' KB. Circ hole clean w/2% KCL wtr, TOOH w/tbg & tools. RU Schlumberger to perf 5155'-5162', 5171'-5181' KB 2 SPF. RD Schlumberger. TIH w/5-1/2" BP, 5-1/2" packer & 165 jts 2-7/8" tbg, set BP @ 5204' KB, set packer @ 5167' KB. RU Western to break down pressure test surface equipment to 5000 psig - OK. Start break down, initial 1600 psi, back to 800 psi, 2 BPM. Communicated between perfs, reset packer @ 5122' KB. Start break down initial break 1000 psi, back to 800 psi, 2.5 BPM. No ball off, ISIP - 800 psi. Pump for rate 6.6 BPM @ 2200 psi, ISIP 800. SDFN. Load to recover 124 BW. See treatment report attached. DC: \$18,068

9-28-93 Completion

Csg vac, tbg vac. TOOH w/tbg & packer. RU Western to frac. Pressure tets surface equipment to 4000 psi - OK. Load hole 66 bbls, fluid level. Frac well using 28,200# 20-40 sand & 29,180# 16-30 sand. Average treating rate 25.1 BPM, average treating pressure - 1800 psi. See treatment report attached. DC: \$22,368

9-29-93 Completion

Csg - vac psig. TIH w/BP retrieving head, 1 jt 2-7/8" tbg, packer, SN & 162 jts 2-7/8" tbg. Tag sand fill @ 5095' KB. Circ sand out ot BP, set packer @ 5095' KB. Made 22 swab runs, recovered 79 BF, 1 all, 78 water. Last 3 runs stable @ 5050, oil trace. SWIFN. Load to recover 542 BW. DC: \$19,679

9-30-93 Completion

CP - 0, Tbg vac psig. Tag fluid @ 2300'. Made 9 swab runs, 40 BF, recovered 2% oil average. TIH, tag sand fill @ 5158' KB, clean to Release BP, TOOH w/tbg, SN, packer & BP. BP @ 5204'. Schlumberger to perf 4840, 44, 48, 50, 58, 64, 4962, 68, 4984, 88, 92, 94, 96, 98 1 hole @ station. RD Schlumberger, TIH w/RBP, set BP @ 5025' KB, set packer @ 4976' KB. RU Western to do break down. Pressure test surface equipment to 5400 psi - OK. Start break down initial break to 2500 psi, back to 1700' @ 2.5 BPM. Start 2 balls per bbl, ball off, pump for rate 5.5 BPM @ 2000 psi. ISIP 700 psi, release packer, wash balls off BP, release BP, reset BP @ 4976', set packer @ 4900. Start break down, initial break @ 2.0 BPM, 3000 psi, back to 2000 psi, pump 4 balls, no ball off. Pump for rate 4.0 BPM 2000 psi. ISIP 600 psi, reset BP @ 4900', set packer @ 4820'. Start break down, initial break @ 4.0 BPM @ 3000 psi. Back to 1600 psi, pump for rate 6.2 BPM @ 2000, RD Western. Load to recover 640 BW. DC: \$22,900

BALCRON MONUMENT FEDERAL #23-11

Location: NE SW Section 11, T98, R16E

Duchesne County, Utah

---TIGHT HOLE---

10-1-93 Completion

> TIH to BP, circ balls off BP. Release BP, reset BP, set packer & pressure test to 3000 psi 10 min - ok. TOOh w/tbg, SN, 5-1/2" packer, 1 jt tbg, & BP retrieving head. RU Western to frac stage #2. See Treatment Report attached. Pressure test surface equipment to 4200 psig - ok. RU Cutter to set RBP @ 4750' KB, & perf 4710-17' 2 SPF. RD Cutter Wireline. TIH w/5-1/2" packer, SN, & 150 jts 2-7/8" tbg, set packer @ 4687' KB. RU Western to do breakdown on 4710-4717'. Pressure test surface equipment to 4800 psi - ok. Refer to Treatment Report. Initial Break @ 1800 psi at 2.5 BPM, back o 1800 psi @ 4.5 BPM. TOOH w/tbq & packer. Western to frac 4710-17'. Pressure test surface equipment to 4000 psi - ok. Refer to Treatment Report. SWIFN. Load to recover 1418 BW.

DC: \$10,020

10-2/3-93 Well SI.

10-4-93 Completion

> Csg vac. TIH w/BP retrieving tool & tbg. Tag sand fill @ 4630' KB. Circ sand out to 4750' (BP), release BP & TOOH w/tbg & BP. w/BP retrieving tool, 1 jt 2-7/8" tbg, 5-1/2" packer, SN & 2-7/8" tbg, tag sand fill at 4900' KB, circ sand out to 503=26', set packer @ 4656'. Made 6 swab runs, recovered 30 BW, trace of oil. SWIFN.

DC: \$7,435

10-5-93 Completion

CP - 0, TP - 0. Fluid level @ 1200' F.S. Made 25 swab runs, 1st five runs 50% oil. Last 4 runs 10% oil, no sand, fluid level stable @ 2300'. Fluid recovered 120 bbls, wtr recovered 100 bbls. TIH, tag sand fill @ 4995', could not circ down. TOOH w/tbg & packer, LD packer, TIH w/BP retrieving tool & tbg to 4687'. SWIFN. DC: \$3,300

10-6-93 Completion

> Csg - vac. TIH, tag sand @ 4995' KB, circ clean to BP @ 5045' KB, retrieve BP, TOH w/tbq & BP. TIH w/the following:

Length <u>Landed</u> at KB 1 jt 2-7/8" tbg EUE, J-55, 8RD, 6.5# 31.85' 5296.20' KB one 2-7/8" x 3' perf sub 3.05 5264.35' KB one seat nipple 5261.30' KB 1.15' 168 jts 2-7/8" tbg EUE, J-55, 8RD 6.5# 5250.15' 5260.15' KB. ND BOP, NU wellhead. TIH w/the following: BHP, 2-1/2" x 1-1/2" x 16' RHAC w/RA plunger 209 3/4" x 25' rods plain one 3/4" x 8' pony one $3/4" \times 6'$ pony one 3/4" x 2' pony one 1-1/4" x 16' polish rods SM

Pressure test tbg to 500 psi - OK.

DC: \$7,118

BALCRON MONUMENT FEDERAL #23-11 Location: NE SW Section 11, T98, R16E Duchesne County, Utah


---TIGHT HOLE---

- 10-21-93 Completion Started pumping @ 11:30 a.m. 5 SPM, 64" stroke. Date of first production 10-21-93.
- 10-22-93 Completion Change vent system on production tanks. DC: \$595
- 10-25-93 Completion
 Hook up frac tank for temp production tank.
 DC: \$1,255

WELL NAME	FIELD	QTR/QTR	SEC.	TWP.	RANGE	COUNTY	ZONE	LEASE NO.	API NUMBER	FOOTAGES	UNIT
	医克尼耳基氏性毒素 建克莱克	E3028E53	M392 3			K38K3783	======================================				
Balcron Monument Fed. #32-15 Balcron Monument Fed. #23-15 Balcron Monument Fed. #41-15 Balcron Monument Fed. #34-10J	Monument Butte Monument Butte Monument Butte Monument Butte	SW NE NE SW NE NE SW SE	15 15 15	9S 9S 9S 9S	16E 16E 16E 16E	Duchesne Duchesne Duchesne Duchesne	Green River Green River Green River Green River	U-017985 U-017985 U-017985 U-017985	43-013-31368 43-013-31373 43-013-31367 43-013-31416	1868' FNL, 1993' FEL 1724' FSL, 2078' FWL 460' FNL, 500' FEL 592' FSL, 1979.2' FEL	Jonah Jonah Jonah Jonah
Balcron Monument Fed. #32-12J	Monument Butte	SWINE	12	98	16E	Duchesne	Green River	U-035521	43-013-31419	1804.8' FNL, 2138.6'FEL	Jonah
C&O Gov't #4 Balcron Monument Fed. #14-12J	Monument Butte Monument Butte	NE SW SW SW	12 12	9S 9S	16E 16E	Duchesne Duchesne	Green River Green River	U-035521-A U-035521-A	43-013-30742 43-013-31411	2140' FSL, 1820' FWL 660' FSL, 660' FWL	Jonah Jonah
Balcron Monument Fed. #14-11 Balcron Monument Fed. #21-14J	Monument Butte Monument Butte	SW SW NE NW	11 14	9S 9S	16E 16E		Green River Green River	U-096547 U-096547	43-013-31374 43-013-31421	1048' FSL, 446' FWL 517.8'FNL, 1850.2'FWL	Jonah Jonah
Balcron Monument Fed. #12-11J Balcron Monument Fed. #43-11J Walton Federal #34-11 Balcron Monument Fed. #23-11 Balcron Monument Fed. #32-11 Balcron Monument Fed. #41-14J Balcron Monument Fed. #12-12J	Monument Butte Monument Butte Monument Butte Monument Butte Monument Butte Monument Butte	SW NW NE SE SW SE NE SW SW NE NE NE SW NW	11 11 11 11 11 14 12	9S 9S 9S 9S 9S 9S	16E 16E 16E 16E 16E 16E	Duchesne Duchesne Duchesne Duchesne Duchesne	Green River Green River Green River Green River Green River Green River	U-096550 U-096550 U-096550 U-096550 U-096550 U-096550	43-013-31417 43-013-31002 43-013-31003 43-013-31369 43-013-31408 43-013-31410	2128' FNL, 689' FWL 2126.9'FSL, 692.8'FEL 537' FSL, 2092' FEL 1787' FSL, 2147' FWL 2059' FNL, 1763' FEL 363.3'FNL, 600' FEL 738.6'FNL, 648.2'FWL	Jonah Jonah Jonah Jonah Jonah Jonah
Balcron Monument Fed. #44-1J	Monument Butte	SE SE	1	98	16E	Duchesne	Green River	U-44426	43-013-31415	859' FSL, 338' FEL	Jonah

APPLICATION FOR INJECTION WELL - UIC FORM 1

OPERATOR _	Equitable Resources Energy Company, Balcron Oil Division
ADDRESS _	P.O. Box 21017
	Billings, MT 59104



Well name and number:Balcron Monument Federal #23-11J
Field or Unit name: Monument Butte Field/Jonah Unit Lease no. U-096550
Well location: QQ NE SW section 11 township 9S range 16E county Duchesne
Is this application for expansion of an existing project? Yes 🕅 No []
Will the proposed well be used for: Enhanced Recovery? Yes [x] No [] Disposal? Yes [] No [x] Storage? Yes [] No [x]
Is this application for a new well to be drilled? Yes [] No [x]
If this application is for an existing well, has a casing test been performed on the well? Yes [] No [X] Date of test: API number: 43-013-31369
Proposed injection interval: from 4,710' to 5,181' Proposed maximum injection: rate 600 BWPD pressure 2000 psig
Proposed injection zone contains [3] oil, [] gas, and/or [] fresh water within % mile of the well.
IMPORTANT: Additional information as required by R615-5-2 should accompany this form.
List of Attachments: <u>UIC Permit Application</u>
I certify that this report is true and complete to the best of my knowledge. Name Bobbie Schuman Signature Bobbie Schuman Title Regulatory and Environmental Specialist Date Cugual 2, 1994 Phone No. (406) 259-7860
(State use only) Application approved by Title Approval Date

Comments:

INJECTION PERMIT TRACKING RECORD

Company: <u>Equipolities</u>	4	Well:	23.	// J	
Location: Sec	Twn: 95				
County: <u>Julyma</u>	Field:	· B	Unit: _	John	9L
API No.: <u>43-0/3 -</u>	31369				
Date Received: 8/3	/94			·	
Cause Number:					
Notice Date:					
Conversion Approval:	·				
Permit Issued:					
Commencement:					
Drilled: /					
Code:					
Hearing Date:					
Wells In AOD.					



Michael O. Leavitt
Governor
Ted Stewart
Executive Director
James W. Carter
Division Director

355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax) 801-538-5319 (TDD)

September 1, 1994

Uintah Basin Standard 268 South 200 East Roosevelt, Utah 84066

Gentlemen:

Re: Notice of Agency Action - Cause No. UIC-152

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please send proof of publication and billing to the Division of Oil, Gas and Mining, 355 West North Temple, 3 Triad Center, Suite 350, Salt Lake City, Utah 84180-1203.

Sincerely,

Lisa D. Clement Administrative Secretary

Lisa D. Clement

Enclosure WOI168





Michael O. Leavitt Governor Ted Stewart Executive Director James W. Carter Division Director 355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax) 801-538-5319 (TDD)

September 1, 1994

Newspaper Agency Corporation Legal Advertising 157 Regent Street Salt Lake City, Utah 84110

Gentlemen:

Re: Notice of Agency Action - Cause No. UIC-152

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please send proof of publication and billing to the Division of Oil, Gas and Mining, 355 West North Temple, 3 Triad Center, Suite 350, Salt Lake City, Utah 84180-1203.

Sincerely,

Lisa D. Clement Administrative Secretary

Gusa D. Clement

Enclosure WOI168



Equitable Resources Energy Company 44-1J, 34-10J, 34-11, 12-11J, 14-11J, 23-11J, 32-11J, 43-11J, 12-12J, 14-12J, 32-12J, C & O Government #4, 21-14J, 41-14J, 23-15J, 32-15J, and 41-15J Wells Cause No. UIC-152

Publication Notices were sent to the following:

Newspaper Agency Corporation Legal Advertising 157 Regent Street Salt Lake City, Utah 84110

Uintah Basin Standard 268 South 200 East Roosevelt, Utah 84066

Bureau of Land Management Vernal District Office 170 South 500 East Vernal, Utah 84078

Equitable Resources Energy Company P.O. Box 21017 Billings, Montana 59104

Dan Jackson
U.S. Environmental Protection Agency
Region VIII
999 18th Street
Denver, Colorado 80202-2466

Ed Bonner State Lands and Forestry 3 Triad Center, Suite 400 Salt Lake City, Utah 84180-1204

Lisá D. Clement

Administrative Secretary

September 1, 1994

BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RESOURCES STATE OF UTAH

---ooOoo---

IN THE MATTER OF THE APPLICATION

NOTICE OF AGENCY ACTION

OF EOUITABLE RESOURCES ENERGY

CAUSE NO. UIC-152

COMPANY FOR ADMINISTRATIVE APPROVAL TO CONVERT THE 44-1J, 34-10J,

34-11, 12-11J, 14-11J, 23-11J, 32-11J, 43-11J, 12-12J,

14-12J, 32-12J, C & O GOVERNMENT #4,

21-14J, 41-14J, 23-15J, 32-15J, AND 41-15J WELLS, LOCATED IN SECTIONS 1, 10, 11, 12, 14, & 15, TOWNSHIP 9 SOUTH, RANGE 16 EAST, S.L.M..

DUCHESNE COUNTY, UTAH, TO CLASS II

INJECTION WELLS

---00000---

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division is commencing an informal adjudicative proceeding to consider the application of Equitable Resources Energy Company ("Equitable") for administrative approval to convert the 44-1J, 34-10J, 34-11, 12-11J, 14-11J, 23-11J, 32-11J, 43-11J, 12-12J, 14-12J, 32-12J, C & O Government #4, 21-14J, 41-14J, 23-15J, 32-15J, and 41-15J Wells, located in Sections 1, 10, 11, 12, 14 & 15, Township 9 South, Range 16 East, Duchesne County, Utah, to Class II injection wells. The proceeding will be conducted in accordance with Utah Admin. R.649-10, Administrative Procedures.

Equitable proposes to inject water into the captioned wells in the Green River Formation interval at approximately 4590 - 5614 feet, for the purpose of secondary recovery operations. Equitable is requesting a maximum injection pressure of 2000 psig and estimates the injection volume to be approximately 600 barrels of water per day for each well.

Any person desiring to object to the application or otherwise intervene in the proceeding, must file a written protest or notice of intervention with the Division within fifteen days of the date of publication of this notice. If such a protest or notice of intervention is received, a hearing may be scheduled before the Board of Oil, Gas and Mining. Protestants and/or intervenors should be prepared to demonstrate at the hearing how this matter affects their interests.

DATED this 1st day of September, 1994.

STATE OF UTAH DIVISION OF OIL, GAS AND MINING

Associate Director, Oil and Gas

Form 3160-5 (June 1990)

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM APPROVED Budget Bureau No. 1004-0135 Expires: March 31, 1993

5. Lease Designation and Serial No.

See attached listing 6. If Indian, Allottee or Tribe Name

SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN T	7. If Unit or CA, Agreement Designation Jonah Unit	
1. Type of Well X Well	any Ralcron Oil Division	8. Well Name and No. See attached listing 9. API Well No.
3. Address and Telephone No. P.O. Box 21017; Billings, MT 59:	•	See attached listing 10. Field and Pool, or Exploratory Area
4. Location of Well (Footage, Sec., T., R., M., or Survey Description	on) .	Monument Butte/Green Rive
See attached listing		Duchesne County, UTAH
12. CHECK APPROPRIATE BOX(s) TO	O INDICATE NATURE OF NOTICE, RE	PORT, OR OTHER DATA
TYPE OF SUBMISSION	· TYPE OF ACT	пои
Notice of Intent Subsequent Report	Abandonment Recompletion Plugging Back	Change of Plans New Construction Non-Routine Fracturing
Final Abandonment Notice	Casing Repair Altering Casing Other	Water Shut-Off X Conversion to Injection Dispose Water (Note: Report results of multiple completion on Well Completion on Recompletion Report and Log form.)
Describe Proposed or Completed Operations (Clearly state all perting the subsurface locations and measured and true vertical department.)	nent details, and give pertinent dates, including estimated date of	Completion or Recompletion Report and Log form.)

Operator intends to convert the wells on the attached listing to water injection in accordance with the attached injection well completion diagrams. Water will be injected at a rate of 5-6 STBWPD per foot of pay (average 180-200 STBWPD). The proposed conversion and water injection will commence as soon as Utah State UIC permits are approved.

14. I hereby certify that the foregoing in true and correct Signed Abbut Schunum	Regulatory and Tide Environmental Specialist	Date 9-12-94
(This space for Federal or State office use) Approved by Conditions of approval, if any:	Tide	Date

Tide 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

BALCRON MONUMENT FEDERAL #23-11J

Jonah Unit/Monument Butte Field Lease No. U096550

NE SW Section 11, T9S, R16E

Duchesne County, Utah

BALCRON OIL 8-1-94/ks

Proposed Injection Well Completion Diagram

Elev. Gr @ 5621'

Elev. KB @ 5631' (10' KB)

SURFACE CASING

8-5/8", 24#, J-55 Length @ 270.01' Hole size @ 12-1/4" Depth landed @ 277' KB Cemented w/150 sxs Class "G" w/2% CCL & 1/4#/sx Celoflake. Good returns

PRODUCTION CASING

5-1/2", 15.5#, K-55 Length @ 5740.67' Hole size @ 7-7/8" Depth landed @ 5730.67' KB Cemented w/90 sxs Hifill & tail w/350 sxs 50-50 POZ. TOC @ 2510' from CBL

TUBING

2-7/8", 6.5#, J-55 SN @ 2-7/8" x 1.15' (2.25" ID) SN landed @ 4641' KB

Retrievable Csg Tension Packer Model: Arrow Set-1 Landed @ 4645' KB

Proposed Injection Horizons

4710'-4717' (7')	(2 SPF)	RED 1
4836'-4844' (8')	(2 SPF)	RED 5
4848'-4850' (2')	(2 SPF)	RED 5
4858'-4864' (6')	(2 SPF)	RED 5
4962'-4968' (6')	(2 SPF)	GREEN 1
4984'-4989' (5')	(2 SPF)	GREEN 1
4992'-4998' (6')	(2 SPF)	GREEN 1
5155'-5162' (7')	(2 SPF)	GREEN 4
5171'-5181' (10')	(2 SPF)	GREEN 4

<-- 277' KB

-- Uintah Formation @ Surface to 1400' ---

<---Top of Cement @ 2510' from CBL

-- Green River Formation @ 1400' to 4100' ---

PERFORATION RECORD .

4710'-4717' (7')	(2 SPF)	RED 1
4840', 4844', 4848', 4850'	(1 SPF)	RED 5
4858', 4864'	(1 SPF)	RED 5
4962', 4968', 4984', 4988'	(1 SPF)	GREEN 1
4992', 4994', 4996', 4998'	(1 SPF)	GREEN 1
5155'-5162' (7')	(2 SPF)	GREEN 4
5171'-5181' (10')	(2 SPF)	GREEN 4

-- Retrievable Csg Tension Packer @ 4645' KB

PROPOSED REPERFORATING

4836'-4844' (8')	(2 SPF)	RED 5
4848'-4850' (2')	(2 SPF)	RED 5
4858'-4864' (6')	(2 SPF)	RED 5
4962'-4968' (6')	(2 SPF)	GREEN 1
4986'-4989' (3')	(2 SPF)	GREEN 1
4992'-4998' (6')	(2 SPF)	GREEN 1

--- Douglas Creek Member @ 4100' to 5350' ---

PBTD @ 5671' KB TD @ 5750' KB

- -- Wasatch Formation Transition @ 5350' to 6000' --
- Wasatch Formation @ 6000' --



1601 Lewis Avenue P.O. Box 21017 Billings, MT 59104 Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361 FAX: (406) 245-1361

SEP | 3 | 994

September 12, 1994

Bureau of Land Management 170 South 500 East Vernal, UT 84078 BALCRON MONUMENT Federal 23-11 SEL 11 T95 & 16E 43-017-31369

Gentlemen:

Enclosed are Notices of Intent to convert the seventeen wells on the enclosed list to water injection.

If you have any questions or need additional information, please let me know.

Sincerely,

Bobbie Schuman

Sophie Schuman

Regulatory and Environmental Specialist

/hs

Enclosures

cc: Dan Jarvis, Utah Division of Oil, Gas and Mining

143 SOUTH MAIN ST P.O. BOX 45838 SALT LAKE CITY, UTAH 8 FED. TAX I.D. # 87-0217663

Newspaper Agency Corporation The Salt Lake Tribune (P) DESER

CUSTOMER'S COPY

LEGAL ADVERTISING INVOICE

CUSTOMER NAME AND ADDRESS	ACCOUNT NUMBER	BILLING DATE
DIV OF OIL, GAS & MINING	LE-5385340	09/13/94
355 WEST NORTH TEMPLE 3 TRIAD CENTER #350 SLC, UT 84180		S INFORMATION .) 237-2822

	AF:	FIDAVIT OF PUBL	ICATION	
DIV OF CORPORATION, PRINTED IN T NOTICE OF AGENCY ACTION 34 BEFORE THE DIVISION OF OF CAUSE NO. UIC-152 BEFORE THE DIVISION OF OF CAUSE OF UITAH IN THE MATTER OF THE APPLICATION OF FOUNTABLE RESOURCES ENERGY COMPANY FOR ADMINISTRATIVE APPROVAL TO CONVERT THE 44-11, 34-10, 34-11, 12-11, 14-41, 22-11, 33-211, 43-11, 12-12, 14-12, 32-12, 12-12, 14-12, 32-12, 12-12, 14-12, 12-14, 12-14, 14-14, 12-14, 14-14, 12-14, 14-14, 12-14, 14-14, 12-14, 14-14, 12-14, 14-14, 12-14, 14-14, 14-14, 12-14, 14-14,	T OF NOTICE OF OIL, GAS & M AGENT FOR THE HE ENGLISH LAN ACITY, SALT LA SEP 12 199	OF AGENCY ACTIONCA INING WAS E SALT LAKE TRIBUN IGUAGE WITH GENERA	EEPER, I CERTIFY THAT JUSE NO. UIC-152BEFOR PUBLISHED BY THE NEW E AND DESERET NEWS, DA L CIRCURATION IN UTAL STATE OF UTAH.	FOR WSPAPER AGENCY ALLY NEWSPAPERS
THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER. Notice is hereby given that the Division is commending an informal adjudicative proceeding to consider the application of Equitable Resources Energy ompany ("Equitable") for administrative approval to convent the 44-11, 34-10, 34-11, 12-11, 14-11, 12-12, 14-12, 32-12, 16-15, 100 and 11-15. Wells, located in Sections 1, 10, 11, 21, 14, 15, 10 mships) South, Range 16 East, Duchesne County, Utah, to Class II Injection wells. The proceeding will be conducted in accordance with Utah Admin, R649-10, Administrative Procedures. Equitable proposes to Inject water into the captioned wells in the Green River Promotine.	ACC	OUNT NAME		TELEPHONE
located in Sections 1, 10, 11, 12, 14, 8, 15, Lownship 9 South, Range 16 East, Duchesne County, Utah, to Class II Injection wells. The proceeding will be conducted in accordance with Utah Admin, R.649-10, Administrative Proceedings.	& MINING S	CHEDULE		801-538-5340 AD NUMBER
Equitable proposes to inject water into the capitioned wells in the Green River Formation Interval at approximately 4590 - 5044 feet, for the purpose of secondary recovery operations Equitable is requesting a maximum injection pressure of 2000 paire of secondary in the proposition of the position of the properties of	5. [CAPTIO	ЭЙ	98710280 MISC CHARGES
Any person destring to object to the application or other was intervene in the proceeding, must file a written protest or other notice of intervention with the Division within fifteen days of the date of publication of this notice. If such a protest or notice of metryenion is received, a hearing may be scheduled before the Board of Oil, Gas and Mining. Protestants and/or intervenors should be prepared to demonstrate at the hearing how this notifier affects their interests. DATED this 1st day of September, 1904	NOTICE (OF AGENCY ACTIONCA	USE NO. UIC-152BEFOR RATE	.00 AD CHARGE
ne Bodrd of Oil, Gas and Mining, Protestants and/or independent should be prepared to demonstrate at the hearing how this matter affects their interests. DATED this, 1st day of September, 1994.	2 COLUMN	1	1.64	160.72
STATE OF UTAH STATE OF UTAH DIVISION OF OIL GAS AND MINING	ON RECEIPT OF	THIS INVOICE T	OTAL AMOUNT DUE	160.72

THANK YOU FOR USING LEGAL ADVERTISING.

PLEASE RETURN THIS PORTION **LEGAL**

WITH YOUR PAYMENT IN THE ENCLOSED ENVELOPE ADVERTISING

15041 4505551000			
LE-5385340	98710280	09/13/94	160.72
			141 stato enlocate
ACCOUNT NUMBER	AD NUMBER	ETTLEWE BAND	PAY THIS AMOUNT

LEGAL ADVERTISING

PLEASE REMIT TO:

NEWSPAPER AGENCY CORPORATION P.O. BOX 45838 SALT LAKE CITY, UTAH 84145-0838

MAKE CHECKS PAYABLE TO: NEWSPAPER AGENCY CORPORATION

ADV06-NT

DIV OF OIL, GAS & MINING 355 WEST NORTH TEMPLE 3 TRIAD CENTER #350

SLC,

DIVISION OF OIL, GAS AND MINING UNDERGROUND INJECTION CONTROL PROGRAM

PERMIT DECISION DOCUMENT

Applicant: Balcron Oil Location: Jonah Unit

Wells: Federal 34-10,12-11,14-11,23-11,32-11,34-11,43-11,

C&O Govt. #4,12-12,14-12,32-12,21-14,41-14,23-15,32-15,

41-15 and 44-1

Ownership Issues: The proposed wells are located in sections 1,10,11,12,14 and 15 township 9 south, range 16 east, Duchesne County, Utah. Surface ownership within the 1/2 mile area is held by the BLM and the State of Utah. All of the wells are located on Federal land. Mineral interests are held by private individuals, the State of Utah, and the federal government. Balcron Oil has submitted an affidavit stating that a copy of UIC form 1 was sent as notice to all surface owners and operators within a 1/2 mile radius of each of the proposed injection wells.

Well Integrity: The seventeen wells proposed for conversion to injection all have surface casing set at approximately 300 feet ± 30 feet, and were all cemented to surface. Production casing was set at a depth of approximately 5600 feet - 5800 feet, and were all cemented above the injection zone. Cement bond logs are on file with the Division and verify reported cement tops. The interval from 4590-5614 feet (Green River Formation) has been perforated for water injection. A 2 7/8 inch tubing with a packer will be set above the perforations for injection of water. There are 27 producing wells, 17 injection wells and 5 plugged and abandonded wells in the 1/2 mile area of review. All wells in the AOR have sufficient cement behind the production string and have adequate surface casing to prevent migration of fluid up the hole. At the time of conversion the casing will be pressure tested. Casing/tubing annulus pressure will be monitored on a daily basis and reported on a monthly basis thereafter. Additional casing pressure tests shall be run every five years or whenever the tubing and packer assemblies are pulled for workover purposes.

Ground Water Protection: The base of moderately saline water in the area of the project is at a depth of approximately 300-500 feet. Each of the injection wells and offset producing wells have adequate surface casing and sufficient cement on the production casing to protect fresh water. The submitted fracture pressure for the field is .861 psi/ft resulting in a maximum allowed surface pressure of 2000 psi. Injection pressures for each of the injectors will be maintained below the fracture pressure so as not to initiate fractures in the overlying strata. The confining intervals above and below the injection zone consists of tight shales, siltstones and limestones of the Green River Formation. Water analysis indicate that the TDS of injection zone is greater than 10,000 TDS.

Oil/Gas & Other Mineral Resources Protection: Balcron is the operator of the Jonah Unit. A unit agreement was previously formed, correlative rights issues were addressed before the Board of Oil, Gas and Mining when the matter was heard.

Bonding: Balcron is the operator of all wells within the project and is bonded by the Federal Government.

Actions Taken and Further Approvals Needed: These applications are for wells in an existing waterflood unit, previously supplied data and information along with newly submitted data supports a decision to approve the wells for conversion to injection. A public notice has been published in both the Salt Lake Tribune and the Uinta Basin Standard. The applications for the injection wells are technically complete. A casing pressure test needs to be conducted when the well is converted and a casing\tubing pressure test run prior to injection. The casing tubing annulas needs to be pressured to 1000 psi and not 500 psi as stated in the permit. Following the 15 day comment period if no objections are received it is recommended to issue both an approval to convert the wells and an injection permit. There are no special conditions or stipulations and the permit should be granted in accordance with the conditions set forth in the application.

	09-30-94
Reviewers	Date



Michael O. Leavitt
Governor
Ted Stewart
Executive Director
James W. Carter
Division Director

355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax) 801-538-5319 (TDD)

October 4, 1994

Equitable Resources Energy Company Balcron Oil Division 1601 Lewis Avenue Billings, Montana 59104

Re: Monument Butte Federal 34-10, 12-11, 14-11, 23-11, 32-11, 34-11, 43-11, 12-12, 14-12, 32-12, 21-14, 41-14, 23-15, 32-15, 41-15, 44-1 and C&O Govt.#4 Wells Located in Sections 1, 10, 11, 12, 14 and 15, Township 9 South, Range 16 East, Duchesne County, Utah

Gentlemen:

In accordance with Utah Admin. Code R.649-5-3-3, the Division of Oil, Gas and Mining (the "Division") issues its administrative approval for conversion of the referenced wells to Class II injection wells.

The following stipulations shall apply for compliance with this approval:

- 1. Full compliance with all applicable requirements regarding operation, maintenance and reporting for Underground Injection Control ("UIC") Class II injection wells pursuant to Utah Admin. Code R.649-1 et seq.
- 2. Conformance with all conditions and requirements of the enclosed Underground Injection Control Permit and the application submitted by Equitable Resources Energy Company.

If you have any questions regarding this approval or the necessary requirements, please contact Dan Jarvis at this office.

Sincerely,

Associate Director

cc: Dan Jackson, EPA
Bureau of Land Management, Vernal





Michael O. Leavitt
Governor

Ted Stewart
Executive Director

James W. Carter
Division Director

355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax) 801-538-5319 (TDD)

UNDERGROUND INJECTION CONTROL PERMIT

Cause No. UIC-152

Operator:

Equitable Resources Energy Company

Wells:

Monument Butte Federal 34-10, 12-11, 14-11, 23-11, 32-11, 34-11, 43-11, 12-12, 14-12, 32-12, 21-14, 41-14, 23-15, 32-15, 41-15, 44-1 and C&O Govt.#4

Location:

Sections 1, 10, 11, 12, 14 and 15, Township 9 S,

Range 16 E,

Duchesne County

Well Type:

Enhanced Recovery (waterflood)

Stipulations of Permit Approval

- 1. Approval for conversion to Injection Wells issued on October 4, 1994.
- 2. Maximum Allowable Injection Pressure: 2000 psig

3. Maximum Allowable Injection Rate: 600 bbls per day/well

Approved by:

R.J. Firth
Associate Director, Oil and Gas

Date



***		1
Form 3160-5 UNITED STATES		FORM APPROVED
(June 1990) DEPARTMENT OF THE INTERIOR		Budget Bureau No. 1004-0135
BUREAU OF LAND MANAGEMENT	The second secon	Expires: March 31, 1993
	4	5. Lease Designation and Serial No.
	Entry to provide a comprehensive statement of the control of the c	U-17985
SUNDRY NOTICES AND REPORTS ON W	vells ONV OF OIL, GAS & MIRRED	6. If Indian, Allottee or Tribe Name
	The state of the s	
Do not use this form for proposals to drill or to deepen or		n/a
Use "APPLICATION FOR PERMIT " for such p	roposais	7. If Unit or CA, Agreement Designation
SUBMIT IN TRIPLICATE		
	·	
1. Type of Well		Jonah Unit
X OII Gas		
Well Well Other		8. Well Name and No.
2. Name of Operator		Balcron Monument Federal #23-11J
EQUITABLE RESOURCES ENERGY COMPANY, BALCRO	N OIL DIVISION	9. API Well No.
Address and Telephone No.		43-013-31369
P.O. Box 21017; Billings, MT 59104 (406) 259-7860		Field and Pool, or Exploratory Area Monument Butte/Green River
4. Location of Well (Footage, Sec., T., R., M., or Survey Description)		WOLDING BUILD GLOSIT FIVE
SURFACE: NE SW Section 11, T9S, R16E		11. County or Parish, State
TD: 1787' FSL & 2147' FWL		
		Duchesne County, Utah
12. CHECK APPROPRIATE BOX(s) TO INDIC	CATE NATURE OF NOTICE, REPORT, OR OT	THER DATA
TYPE OF SUBMISSION	TYPE OF ACTION	
☐ N. #	Abandonment	Change of Plans
Notice of Intent	Additionillent	
	Recompletion	New Construction
X Subsequent Report	Plugging Back	Non-Routine Fracturing
Cabbeddent roport		<u> </u>
	Casing Repair	Water Shut-Off
Final Abandonment Notice	Altering Casing	Conversion to Injection
		□
	X Other	Dispose Water
	Amendment to Completion Report	(Note: Report results of multiple completion on Well
		Completion or Recompletion Report and Log form.)
13. Describe Proposed or Completed Operations (Clearly state all pertine)	nt details, and give pertinent dates, including estimated date of starting at	ny proposed work. If well is
directionally drilled, give subsurface locations and measured and tr	ue vertical depths for all markers and zones pertinent to this work.)*	
Attached are the Geologcial Markers	and their Measured Depths to be amended on	
the original completion report submitt	ted on 11-29-93.	
and on great our product of our contract	••••	
14. I hereby certify that the foregoing is true and correct		
A A		· •
D11. (1		
Signed Tybble Schuman Title	Regulatory and Environmental Specialist	Date 12-8-94
Olymon Control Control		
(This space for Federal or State office use)		
Approved by Title		Date
Approved by Title Conditions of approval, if any:		
•• •		
Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly a	ad will fully to make to any department as assess of the United Civics and	u falsa ficitious or fraudulant

*See Instruction on Reverse Side

EQUITABLE RESOURCES ENERGY COMPANY Balcron Oil Division

Balcron Monument Federal #23-11J NE SW Section 11, T9S, R16E Duchesne County Utah

Amendment to Completion Report Submitted on 11-9-93

GEOLOGICAL MARKERS

NAME	MEASURED DEPTH
Green River	1577 <i>'</i>
Horse Bench Sandstone	2213′
Second Garden Gulch	3878 <i>'</i>
"Y" Marker	4506 ′
Douglas Creek Marker	4661'
Second Douglas Creek	4896
Green Marker	5046'
Carbonate Marker	5527 ′
Red-1 Sandstone	4709 ′
Red-5 Sandstone	4835'
Green-1 Sandstone	4961'
Green-4 Sandstone	5155 ′

STATE OF UTAH Division of Oil, Gas and Mining 355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203

INJECTION WELL - PRESSURE TEST

1			
Test Date:	Well Owner/Operator:	Baleran	
Disposal Well:	Enhanced Recovery Wells	10	ther:
API No.: 43- <u>013 = 31369</u>	Well Name/Number:	23-11.J.	
Section://	Township: 95	Range:	16 E
Initial Conditions:			
Tubing - Rate:	I Pressure:	_ <i>300</i> psi	
Casing/Tubing Annulus	- Pressure:	psi	
Conditions During Test:			
Time (Minutes) 0 5 10 15 20 25 30 Results: Pass/Fail Conditions After Test: Tubing Pressure:	Annulus Pressure /075 /075 /075 /075 /075 psi	<i>"</i>	b
-	Pressure:	psi	
REMARKS:	MIT - W	ell is read	f h
	(
Operator Representative	D	OGM Witness	7

Form 3160-5 (June 1990)

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

V.	1	£-	
2. 2. 2. 2. A. A.			

FORM APPROVED

 afer par		1001-0133	
Expires:	March	31, 1993	
 Designat	ion and	Secial No.	_

SUNDRY NOTICES AND REPORTS ON WELLS	
o not use this form for proposals to drill or to deepen or reentry to a different reservoir	۲.
Use "APPLICATION FOR PERMIT—" for such proposals	

Do not use this form for proposals to drill or Use "APPLICATION FOR PE	to deepen or reentry to a different reservoir.	6. If Indian, Allonee or Tribe Name
SUBMIT IN	TRIPLICATE .	7. If Unit or CA, Agreement Designation Jonah Unit
I. Type of Well Oil Gas X Other WIW		8. Well Name and No.
2. Name of Operator Equitable Resources Energy Compa 3. Address and Telephone No.	any, Balcron Oil Division	Balcron Monument Federal #23-1. 9. API Well No. 43-013-31369
P.O. Box 21017; Billings, MT 59. 4. Location of Well (Footage, Sec., T., R., M., or Survey Description)		10. Field and Pool, or Exploratory Area
NE SW Section 11, T9S, R16E 1787' FSL, 2147' FWL	•	Monument Butte/Green River 11. County or Parish, State Duchesne County, UTAH
12. CHECK APPROPRIATE BOX(s) TO	D INDICATE NATURE OF NOTICE, REPO	RT, OR OTHER DATA
TYPE OF SUBMISSION	• TYPE OF ACTION	•
Notice of Intent Subsequent Report Final Abandonment Notice	Abandonment Recompletion Plugging Back Casing Repair Altering Casing	Change of Plans New Construction Non-Routine Fracturing Water Shut-Off Conversion to Injection
13. Describe Proposed or Completed Operations (Clearly state all perting give subsurface locations and measured and true vertical dept	ent details, and give pertinent dates, including estimated date of startin	Dispose Water (Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

This well has been converted to water injection in accordance with permit approval. Refer to the attached workover procedure, well report, and injection well completion diagram for details of the conversion.

4. I hereby certify that the foregoing is true and correct Signed Dobbie Schuman	Regulatory and	Date January 13, 1995
(This space for Federal or State office use) Approved by Conditions of approval, if any:	Tide	Date

Tide 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

BALCRON MONUMENT FEDERAL #23-11J Jonah Unit/Monument Butte Field Lease No. U-096550 NE SW Section 11, T9S, R16E Duchesne County, Utah

WELL HISTORY REPORT

Date

Work Description

-0.000			
LONGO	ion or woll	. fra Yazzaki	r injection.
CONTRACTOR		TO HERE	9.HUCUMIL

10-1-94

- MIRU Basin Well Service, TOOH w/rods,pump, & tbg, RDMO.

10-9-94

- MIRU Cannon Well Service, RIH w/bit & scrapper to TD.
- RU Cutters Wireline, reperforate as follows:

4836'-4844' (8')	(2 SPF)	RED 5
4848'-4850' (2')	(2 SPF)	RED 5
4858'-4864' (6')	(2 SPF)	RED 5
4962'-4968' (6')	(2 SPF)	GREEN 1
4986'-4989' (3')	(2 SPF)	GREEN 1
4992'-4998' (6')	(2 SPF)	GREEN 1

- RIH w/ 2 7/8" injection tbg & Arrow Set-1 packer.
- Pump 55 gals Champion Cortron #23-83 corrosion inhibitor mixed w/ 60 STBW down csg.
- Set packer @ 4639' KB, NU wellhead, pressure test csg annulus to 1000 psig. no loss, RDMO.

10-18-94

Perform MIT, pressure csg annulus to 1075 psig for 15 min., no loss, tbg @ 300 psig, Utah OG&M wittness Dan Jarvis.

8-18-94

RU Alnigther Hot Oil Service, mix 5 gals Wsetern Claymaster & 10 gals 940 surfactant w/ 130 STB 2% KCl water, pump down tbg @ 180 deg.F., 1.5 STBPM @ 100 psig, start water injection @ 375 STBPD.

Balcron Monument Federal #23-11J NE SW Section 11, T9S, R16E 1787' FSL & 2147' FWL Lease No. U096550 Jonah Unit/Monument Butte Field Duchesne County, Utah

Injection Well Completion Diagram

14%

2% 2% 2% 14% 14% 15%

15% 22% BALCRON OIL 1-11-94 JZ

Elev. Gr @ 5621'

Elev. KB @ 5631' (10' KB)

SURFACE CASING

8-5/8", 24#, J-55 Length @ 270.01' Hole size @ 12-1/4" Depth landed @ 277' KB Cemented w/150 sxs Class "G" w/2% CCL & 1/4#/sx Celoflake. Good returns

PRODUCTION CASING

5-1/2", 15.5#, K-55 Length @ 5740.67' Hole size @ 7-7/8" Depth landed @ 5730.67' KB Cemented w/90 sxs Hifill & tail w/350 sxs 50-50 POZ. TOC @ 2510' from CBL

TUBING/INJECTION STRING

Injection Equipment & Size	Length FT.	Setting Deptl FT.(w/10' KB		
KB	10.00			
1) 148 jnts 2 7/8" tbg	4621.11	4631.11		
2) 2 7/8" SN (2.25" ID)	1.10	4632.21		
3) 2 7/8"x 2 3/8" X-Over	0.60	4632.81		
4) 5.5" Arrow Set-1 Pkr	6.20	4639.01		
End of Tubing	0.20	4639.01		

Injection Packers Set 10-9-94 By Mtn States.

2 7/8" SN ID @ 2.25". Arrow Set-1 Pkr set w/ 16" Tension. Packer fluid - 55 gals Champion Cortron #23-83 w/60 STBW.

Injection Horizons

Tracer Survey ran 12-28-94.

UTAH CAUSE NO.: UIC-152

<-- 277' KB

- Uintah Formation @ Surface to 1400'

<-- Top of Cement @ 2510' from CBL

- Green River Formation @ 1400' to 4100'

PERFORATION RECORD

		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
4710'- 4717' (7')	(2 SPF)	RED 1
4840', 4844', 4848', 4850'	(1 SPF)	RED 5
4858', 4864'	(1 SPF)	RED 5
4962', 4968', 4984', 4988'	(1 SPF)	GREEN 1
4992', 4994', 4996', 4998'	(1 SPF)	GREEN 1
5155'- 5162' (7')	(2 SPF)	GREEN 4
5171'- 5181' (10')	(2 SPF)	GREEN 4

<-- Arrow Set-1 Packer @ 4639' KB

Reperforated on 10-9-94:

(2 SPF)	RED 5
(2 SPF)	RED 5
(2 SPF)	RED 5
(2 SPF)	GREEN 1
(2 SPF)	GREEN 1
(2 SPF)	GREEN 1
	(2 SPF) (2 SPF) (2 SPF) (2 SPF)

- Douglas Creek Member @ 4100' to 5350'

PBTD @ 5671' KB TD @ 5750' KB

- Wasatch Formation Transition @ 5350' to 6000'
- Wasatch Formation @ 6000'

BALCRON OIL

WELL REPORT

WELL NAME: Bakron Monument Federal #23-11J

FIELD: Jonah Unit/Monument Butte Field

FEDERAL LEASE NO.: U-096550

LOCATION: NE SW Section 11, T9S, R16E

1787' FSL & 2147' FWL COUNTY/STATE: Duchesne County, Utah

WORKING INTEREST: 0.805079506

PRODUCING FORMATION: Green River COMPLETION DATE: 10-21-93

INITIAL PRODUCTION: 110 STBOPD, 165 MSCFPD, 20 STBWPD LAST PRODUCTION: 16 STBOPD, 100 MCFPD, 0 STBWPD

PRESENT PROD STATUS: Water Injection Well

Started Water injection 10-28-94.

CONVERSION TO INJ.: 10-9-94 INJECTION RATE: 375 STBWPD ELEVATIONS - GROUND: 5621'

TOTAL DEPTH: 5750' KB

NIDE 40E 040B10

SURFACE CASING

STRING: 1 SIZE: 85/8"

GRADE: J-55 WEIGHT: 24#

LENGTH: 6 jts @ 270.01' HOLE SIZE: 12 1/4"

DEPTH LANDED: 277' KB

CEMENT DATA: 150 sxs Class-G w/2% CCI

& 1/4 # per sx Flocele. Good returns to surface.

TUBING/INJECTION STRING

Injection Equipment & Size	Length FT.	Setting Depth FT.(w/10' KB)
KB	10.00	
1) 148 ints 2 7/8" tbg	4621.11	4631.11
2) 2 7/8" SN (2.25" ID)	1.10	4632.21
3) 2 7/8"x 2 3/8" X-Over	0.60	4632.81
4) 5.5" Arrow Set-1 Pkr	6.20	4639.01
End of Tubing		4639.01

Injection Packers Set 10-9-94 By Mtn States.

27/8" SN ID @ 2.25".

Arrow Set-1 Pkr set w/ 16" Tension.

Packer fluid - 55 gals Champion Cortron #23-83 w/60 STBW.

Injection Horizons

4710'-4717' (7')	RED 1
4836'-4844' (8')	RED 5
4848'-4850' (2')	RED 5
4858'-4864' (6')	RED 5
4962'-4968' (6')	GREEN 1
4984'-4989' (5')	GREEN 1
4992'-4998' (6')	GREEN 1
5155'-5162' (7')	GREEN 4
5171'-5181' (10')	GREEN 4

DATE: 1-11-94 JZ

API NO.: 43-013-31369

UTAH CAUSE NO.: UIC-152

NET REVENUE INT.: 0.73831617 Oil

0.66359285 Gas

SPUD DATE: 8-30-93 OILGRAVITY: 34 API

BHT: 138 Deg.F

LAST MIT DATE: 10-18-94

1075 psig for 15 min., no loss.

KB: 5631' (10' KB)

PLUG BACK TD: 5671'KB

PRODUCTION CASING

CEMENT DATA: 90 sxs Hifill & tail

w/350 sxs 50-50 POZ

CEMENT TOP AT: 2510' from CBL

PERFORATION RECORD

4710'-4717' (7') 4840', 4844', 4848', 4850' 4858', 4864' 4962', 4968', 4984', 4988' 4992', 4994', 4996', 4998' 5155'-5162' (7') 5171'-5181' (10') Reperforated on 10-9-94:	(2 SPF) (1 SPF) (1 SPF) (1 SPF) (1 SPF) (2 SPF) (2 SPF)	RED 1 RED 5 RED 5 GREEN 1 GREEN 1 GREEN 4
4836'-4844' (8') 4848'-4850' (2') 4858'-4864' (6') 4962'-4968' (6') 4986'-4989' (3') 4992'-4998' (6')	(2 SPF) (2 SPF) (2 SPF) (2 SPF) (2 SPF) (2 SPF)	RED 5 RED 5 RED 5 GREEN 1 GREEN 1 GREEN 1

BREAKDOWN/ACID JOB

** See Attached Sheet **

FRAC JOB

** See Attached Sheet **

LOGS: Compensated Neutron/Litho-Density Log; Dual Laterolog Micro-SFL; Mud Log; Cement Bond/Gamma-Ray & CCL Log Balcron Monument Federal #23-11J Jonah Unit/Monument Butte Field Lease No. U-096550 NE SW Section 11, T9S, R16E Duchesne County, Utah

BREAKDOWN INFORMATION

5155'-5181' KB -

9-27-93: By Western w/4,263 gals 2% KCI wtr. ATP 1800 psi,

max 2200 psi. ATR 5 BPM.

4984'-4998' KB &

4962'-4968' KB &

4840'-4864' KB -

9-30-93: By Western w/5,800 gals 2% KCL wtr.

4710'-4717' KB -

10-1-93: By Western w/1974 gals 2% KCL wtr. ATP 2600 psi, max

4000 psi. ATR 5 BPM, max 5.2 BPM. ISIP 1500 psi.

FRAC INFORMATION

5155'-5181' KB -

9-28-93: By Western w/28,200# 20/40 mesh sand & 29,180# 16/30 mesh sand w/18,732 gals 2% KCL gelled wtr. ATP 1800 psi.

ATR 25.1 BPM. ISIP 1900 psi, 5 min 1570 psi, 10 min 1460 psi,

15 min 1430 psi.

4984'-4998' KB &

4962'-4968' KB &

4840'-4864' KB -

10-1-93: By Western w/30,700# 20/40 mesh sand & 29,500# 16/30

mesh sand w/23,604 gals 2% KCL gelled wtr. ATP 2200 psi, max

3000 psi. ATR 25 BPM, max 35 BPM. ISIP 1600 psi.


4710'-4717' KB -

10-1-93: By Western w/20,000# 16/30 mesh sand w/11,634 gals 2% KCL gelled wtr. ATR 19.5 BPM, max 21.1 BPM, ISIP 2000 psi.

5 min 1690 psi, 10 min 1590 psi, 15 min 1530 psi.



1601 Lewis Avenue Billings, MT 59102 Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361



March 16, 1995

Mr. Dan Jarvis State of Utah Division of Oil, Gas & Mining 355 West North Temple Salt Lake City, UT 84180

Dear Mr. Jarvis:

Attached are copies of the injection profile reports for our enhanced recovery wells in the Jonah Unit.

If you have any questions, please call John Zellitti at (406) 259-7860.

Sincerely,

Bobbie Schuman


Regulatory and Environmental Specialist

/hs

Attachments

EQUITABLE RESOURCES ENERGY COMPANY-BALCRON OIL DIVISION INJECTION PROFILE

MONUMENT FEDERAL 23-11J Date: 12/28/94 Surface Temp: 47 F BHT: 150 F PBTD: 5671 TD: 5575 Desired Rate: 375 B/D Metered Rate: 375 B/D Measured Rate: 333 B/D Tbg Pressure: 0 PSI Csg Pressure: 0 PSI



43-013- 3136-

Remarks: R/A Tracer survey indicates exits as shown. Packer checks okay.

Service Company: Well Information Services, Inc.

Operator: Bart Williams



APR 4 1996

1601 Lewis Avenue Billings, MT 59102

April 1, 1996

Mr. Dan Jarvis
Utak Division of Oil, Gas and Mining
UIC Program
355 West North Temple
Salt Lake City, UT 84180

Dear Dan:

Effective April 1, 1996, our name will change from Equitable Resources Energy Company, Balcron Oil Division to Equitable Resources Energy Company. Attached is a listing of permits which we have with your Agency. This change will apply to those. If you note that I have missed some or if you have any questions, please do not hesitate to give me a call at (406) 259-7860, extension 240 to discuss this.

This change affects $\underline{\text{only}}$ our company name. The physical locations of our offices and the personnel remain the same.

If you have any questions, please do not hesitate to give me a call.

Sincerely,

Bobbie Schuman

Regulatory and

Environmental Specialist

/hs

Enclosures

UTAH UIC PERMITS


Balcron Monument Fed: #23-11	
	State #UIC-152
Balcron Monument Fed. #14-11	State #UIC-152
Balcron Monument Fed. #12-11	State #UIC-152
Walton Federal #34-11	State #UIC-152
Balcron Monument Fed. #34-10J	State #UIC-152
Balcron Monument Fed. #44-1J	State #UIC-152
Coyote Basin Area Waterflood	
Area Permit No. UT2653-00000 (Approved 2/18/94)	
Coyote Basin Fed. #42-6X	UT2653-03751 (AREA PERMIT UT2653-00000)
East Red Wash Federal #2-5	UT2653-03752 (AREA PERMIT UT2653-00000)
East Red Wash Federal #4-6	UT2653-04224 (AREA PERMIT UT2653-00000)
Amerada Guinand Federal #1	UT2653-04225 (AREA PERMIT UT2653-00000)
Section 2 Waterflood	
Area Permit No. UT2776-00000 (Approved 11/95)	
Balcron Monument State #14-4	UT2776-04275 (State UIC-163)
Balcron Monument State #22-2	UT2776-04276 (State UIC-163)
Pariette Field SWD	
Pariette Bench #4 SWD (UT)	UT2676-02569



1601 Lewis Avenue Billings, MT 59102 Office: (406) 259-7860 FAX: (406) 245-1365 ☐ FAX: (406) 245-1361 🗔

March 22, 1996

Utah Division of Oil, Gas and Mining 355 West North Temple Salt Lake City, UT 84180



Gentlemen:

Effective April 1, 1996, our name will change from Equitable Resources Energy Company, Balcron Oil Division to Equitable Resources Energy Company. Attached is a sundry notice reflecting that change. To simplify paperwork, I have done one sundry notice with copies for each of the wells. To this letter I have attached a list of our wells for your ease in filing the sundry notices in the well files. This should be sufficient for your purposes.

I have the listings on a spreadsheet so if it would be easier for you to have them sorted differently (for example, the Montana Board of Oil and Gas prefers them sorted by API number), please give me a call at (406) 259-7860, extension 240 and I would be glad to provide a list to your specifications.

This change affects only our company name. The physical locations of our offices and the personnel remain the same. We will be changing our well signs and ask for your patience and cooperation as this will be done as soon as possible but may take some time since we do have so many properties at which to make the change.

If you have any questions, please do not hesitate to give me a call.

Sincerely,

Bobbie Schuman Regulatory and

Environmental Specialist

/hs

Enclosures

Balcron Monument Fed. #14-12J	Monument Butte	SW SW	12	98	16E	Düchesne	Uτ	ww	Green River	U-035521-A	43-013-31411	COO! FO!	-T	
Balcron Monument Fed. #14-15	Monument Butte	sw sw	15	98	16E		UT		Green River	U-035321-A		660' FSL, 660' FWL	Vernal	Jonah
Baicron Monument Fed. #14-26	Monument Butte	sw sw	26	88	16E	Duchesne	UT		Green River	U-34346	43-013-31381	772' FSL, 543' FWL	Vernal	ļ
Balcron Monument Fed. #14-3-9-17Y	Monument Butte	SW SW	3	98	17E		UT		Green River	U-64381	43-013-31512		Vernai	
Balcron Monument Fed. #14-4	Monument Butte	SW SW	4	98	16E	Duchesne	UT		Green River		43-013-31535		Vernai	<u> </u>
Balcron Monument Fed. #14-5	Monument Butte	SW SW	5	 	17E	Duchesne	UT		Green River	U-73086	43-013-31430		Vernal	<u> </u>
Balcron Monument Fed. #14-8	Monument Butte	sw sw	8	+	17E	Duchesne	UT		Green River	U-020250 UTU-74108	43-013-31385	1	Vernai	Jonah
Balcron Monument Fed. #21-10-9-17Y	Monument Butte	NE NW	10	+	17E	Duchesne	UT		Green River	U-65210	43-013-31398	660' FSL, 660' FWL	Vernal	Beluga
Balcron Monument Fed. #21-14J	Monument Butte	NE NW	14	+	16E	Duchesne	UT	wiw	Green River		43-013-31537	807' FNL, 2120' FWL	Vernal	
Balcron Monument Fed. #21-17	Monument Butte	NE NW	17	95	17E	Duchesne	UT	Oil	Green River	U-096547	43-013-31421	518' FNL, 1850' FWL	Vernal	Jonah
Baicron Monument Fed. #21-25	Undesignated	NE NW	25	85	17E	Uintah	UT	Oil	Green River	U-3563-A	43-013-31387	500' FNL, 1980' FWL	Vernai	Beluga
Balcron Monument Fed. #22-12J	Monument Butte	SE NW	12	98	16E	Duchesne	UT	Oil	Green River	U-67845	43-047-32528	748' FNL, 1964' FWL	Vernal	
Balcron Monument Fed. #22-14J	Monument Butte	SE NW	14	98	16E	Duchesne	UT	PND		U-096550	43-013-15796	2018' FNL, 2099' FWL	Vernal	Jonah
Balcron Monument Fed. #22-17	Monument Butte	SE NW	17	98	17E	Duchesne	UT	Oil	Green River	U-096547	43-013-31489	2134' FNL, 2198' FWL	Vernal	Jonah
Balcron Monument Fed, #22-20-9-18Y	Monument Butte	SE NW	20	95	18E	Uintah	UT	Oil	Green River	UTU-72106	43-013-31429	1800' FNL, 1980' FWL	Vernai	Beluga
Balcron Monument Fed. #22-22-8-17Y	Monument Butte	SE NW	22	85	17E	Duchesne	UT	Oil	Green River	U-64917	43-047-32711	1980' FNL, 1980' FWL	Vernal	
Balcron Monument Fed. #22-5	Monument Butte	SE NW	5	98	17E	Duchesne	UT	WIW	Green River	U-67845	43-013-31538	1945' FNL, 2030' FWL	Vernal	
Balcron Monument Fed #23-11	Monument Butte	NE SW	11	95	16E				Green River	U-020252	43-013-31384	1853' FNL, 1980' FWL	Vemai	Jonah
Balcron Monument Fed. #23-15	Monument Butte	NE SW	15	98	16E	Duchesne Duchesne	UT	WIW	Green River	U-096550	43-013-31369	1787' FSL, 2147' FWL	Vernal	Jonah
Balcron Monument Fed. #23-24-8-17		NE SW	24	85	17E	Uintah	UT	WIW	Green River	U-017985	43-013-31373	1724' FSL, 2078' FWL	Vernal	Jonah
Balcron Monument Fed. #23-25	Undesignated	NE SW	25	88	17E	Uintah		PND	Green River				Vernal	
Balcron Monument Fed. #23-5	Monument Butte	NE SW	5	98	17E		UT	Oil	Green River	U-67845	43-047-32529	1927' FSL, 2139' FWL	Vernal	
Balcron Monument Fed. #24-12J	Monument Butte	SE SW	12	98	16E	Duchesne	UT	Oil	Green River	U-020252	43-013-31383	1816 'FSL, 2057'FWL	Vemal	Jonah
Balcron Monument Fed. #24-25	Undesignated	SE SW	25	8S		Duchesne	UT	Oil	Green River	U-035521-A		539' FSL, 1777' FWL	Vernal	Jonah
Balcron Monument Fed. #24-5	Monument Butte	SE SW	5	98		Uintah	UT	Oil	Green River	U-67845	43-047-32669	653' FSL, 2028' FWL	Vernal	
Balcron Monument Fed. #24-6	Monument Butte	SE SW	6	95		Duchesne	UT	WIW	Green River	U-020252	43-013-31375	765' FSL, 2243' FWL	Vernal	Jonah
Balcron Monument Fed. #31-17	Monument Butte	NE NW	17	98	17E	Duchesne	UT	WW	Green River	U-020252-A	43-013-31363	504' FSL, 1613' FWL	Vernai	Jonah
Balcron Monument Fed. #31-1J	Monument Butte	NW NE	1/		17E	Duchesne	UT	Oil	Green River	UTU-72106	43-013-31428	660' FNL, 1980' FEL	Vernal	Beluga
Balcron Monument Fed. #31-25	Undesignated	NW NE	25	98	16E	Duchesne	UT	Oil	Green River	U-33992	43-013-31413	660' FNL, 1980' FEL	Vernal	Jonah
Balcron Monument Fed. #31-7J	Monument Butte	NW NE	7	88		Uintah	UT	Oil	Green River	U-67845	43-047-32530	660' FNL, 1980' FEL	Vernal	···
Balcron Monument Fed, #32-11	Monument Butte	SW NE		98		Duchesne	UT	WIW	Green River	U-44426		831' FNL, 1782' FEL	Vernal	Jonah
Balcron Monument Fed. #32-12J	Monument Butte	SW NE	11	98		Duchesne		WIW	Green River	U-096550	43-013-31386	2059' FNL, 1763' FEL	Vernal	Jonah
	Monument Butte	SW NE	12	98		Duchesne	UT	WIW	Green River	U-035521	43-013-31419	1805' FNL, 2139' FEL	Vernal .	Jonah
Balcron Monument Fed. #32-15	Monument Butte		14	98		Duchesne	UT	PND	Green River	U-096547	43-013-31490	1980' FNL, 1980' FEL	Vernal .	Jonah
Salcron Monument Fed. #32-17		SW NE	15	98		Duchesne		WIW	Green River	U-017985	43-013-31368	1868' FNL, 1993' FEL	Vernal .	Jonah
	Monument Butte	SW NE	17	98	17E	Duchesne	UT	Oil	Green River	UTU-72106	43-013-31465	1880' FNL, 1980' FEL	Vernal I	Beluga

		•
FORM	8	

E OF UTAH DIVISION OF OIL, GAS AND MINING

			5. Lease Designation and Serial Number:
			See attached listing
OHLES	NOTICES AND REPORTS	011 11 0	6. If Indian, Allottee or Tribe Name:
SUNDRY	n/a		
Do not use this form for prop Use APPI	7. Unit Agreement Name: See attached listing		
1. Type of Well: OIL GAS	☐ OTHER: See attached lis	sting	B. Well Name and Number: See attached listing
2. Name of Operator:	ourses Francis Comment D. J.	0.1 0.	9. API Well Number: See attached listing
3. Address and Telephone Number:	ources Energy Company, Balo	cron UII Division	
•	enue Avenue; Billings, MT 5	59102 (406) 259-7860	10. Field and Pool, or Wildcat: See attached listing
4. Location of Well		(100, 200 7000	Tocc accached 113c11ig
Footages: Sec	e attached listing		county: See attached list
QQ, Sec.,T.,R.,M.:			State: UTAH
11. CHECK APPRO	PRIATE BOXES TO INDICATE N	IATURE OF NOTICE PEROI	OT OD OTHER DATA
	•		
	CE OF INTENT mit in Duplicate)	ì	UENT REPORT riginal Form Only)
☐ Abandon	☐ New Construction	☐ Abandon *	☐ New Construction
— □ Repair Casing	☐ Pull or Alter Casing	Repair Casing	☐ Pull or Alter Casing
Change of Plans	☐ Recomplete	☐ Change of Plans	☐ Reperforate
☐ Convert to Injection	☐ Reperforate	☐ Convert to Injection	☐ Vent or Flare
☐ Fracture Treat or Acidize	☐ Vent or Flare	☐ Fracture Treat or Acidize	☐ Water Shut-Off
☐ Multiple Completion	☐ Water Shut-Off	Other Operator name	
Other	_ ···a.o. oo. o	to other	
		Date of work completion	
Approximate date work will start			Recompletions to different reservoirs on WELL
		COMPLETION OR RECOMPLETION REPORT	
		Must be accompanied by a cement verifical	lon report.
		A	· · · · · · · · · · · · · · · · · · ·
Effective Apri Energy Company	1.1, 1996, operator will c , Balcron Oil Division TO:	hange its name from Eq Equitable Resources En	uitable Resources
Effective Apri Energy Company Physical locat	7.1, 1996, operator will c 7. Balcron Oil Division TO: Tion of the operator remain	hange its name from Eq Equitable Resources En	uitable Resources ergy Company.
Effective Apri Energy Company Physical locat (406) 259-7860	7. 1, 1996, operator will c 7, Balcron Oil Division TO: 7, Sion of the operator remain 1, FAX: (406) 145-1361. Th	hange its name from Eq Equitable Resources En s as: 1601 Lewis Avenue is is to report the ope	uitable Resources ergy Company.
Effective Apri Energy Company Physical locat (406) 259-7860	7.1, 1996, operator will c 7. Balcron Oil Division TO: Tion of the operator remain	hange its name from Eq Equitable Resources En s as: 1601 Lewis Avenue is is to report the ope	uitable Resources ergy Company.
Effective Apri Energy Company Physical locat (406) 259-7860	7. 1, 1996, operator will c 7, Balcron Oil Division TO: 7, Sion of the operator remain 1, FAX: (406) 145-1361. Th	hange its name from Eq Equitable Resources En s as: 1601 Lewis Avenue is is to report the ope	uitable Resources ergy Company.
Effective Apri Energy Company Physical locat (406) 259-7860	7. 1, 1996, operator will c 7, Balcron Oil Division TO: 7, Sion of the operator remain 1, FAX: (406) 145-1361. Th	hange its name from Eq Equitable Resources En s as: 1601 Lewis Avenue is is to report the ope	uitable Resources ergy Company.
Effective Apri Energy Company Physical locat (406) 259-7860	7. 1, 1996, operator will c 7, Balcron Oil Division TO: 7, Sion of the operator remain 1, FAX: (406) 145-1361. Th	hange its name from Eq Equitable Resources En s as: 1601 Lewis Avenue is is to report the ope	uitable Resources ergy Company. ; Billings, MT 59102 rator name change
Effective Apri Energy Company Physical locat (406) 259-7860	7. 1, 1996, operator will c 7, Balcron Oil Division TO: 7, Sion of the operator remain 1, FAX: (406) 145-1361. Th	hange its name from Eq Equitable Resources En s as: 1601 Lewis Avenue is is to report the ope	uitable Resources ergy Company. ; Billings, MT 59102 rator name change
Effective Apri Energy Company Physical locat (406) 259-7860 only. It affe	7. 1, 1996, operator will c 7, Balcron Oil Division TO: 7, Sion of the operator remain 1, FAX: (406) 145-1361. Th	hange its name from Eq Equitable Resources En s as: 1601 Lewis Avenue is is to report the ope hed listing.	uitable Resources ergy Company. ; Billings, MT 59102 rator name change

Page No. 4		STAT INVENTORY	E OF OF IN		ON W	ELLS	
OPERATOR	API NO.	WELL	TNS	RGE	SE	WELLTYPE	INDIAN COUNT
******	******	*****	***	***	**	*****	*****
CROSS CREEK	43-037-20117	NAVAJO A #1	41S	26E	5	INJD	Y
CROSS CREEK	43-037-20164	NAVAJO A #3	41S	26E	5	INJI	Y
ENSERCH EXPL	43-013-31240	FEDERAL 43-3	08S	16E	33	INJW	N
ENSERCH EXPL	43-013-31269	FEDERAL 34-3	088	16E	33	WLNI	N
ENSERCH EXPL	43-013-31229	FEDERAL 14-3	08S	16E	33	INJW	N
ENSERCH EXPL	43-613-31225	FEDERAL 14-3	088	16E 16E	34 4	INJW INJW	N N
ENSERCH EXPL	43-013-31272 43-013-30670	FEDERAL 21-4 FEDERAL 32-5	09S 09S	16E	5	INJW	N
ENSERCH EXPL ENSERCH EXPL	43-013-30070	FEDERAL 41-5	09S	16E	5	INJW	N
ENSERCH EXPL	43-013-31203	1-26B	09S	19E	26	INJG	N
ENSERCH EXPL	43-013-30913	44-5H	09S	17E	5	INJW	N
ENSERCH EXPL	43-013-30678	42-8H	09S	17E	8	INJW	N
ENSERCH EXPL	43-013-31457	22-8H	09S	17E	.8	INJW	N
ENSERCH EXPL	43-013-30679	31-8H	09S	17E	8	INJW	N
ENSERCH EXPL	43-013-31049	22-9H	09S	17E	9	INJW	N
ENSERCH EXPL	43-013-30682	24-9H	09S	17E	9	INJW	. N
ENSERCH EXPL	43-013-30887	11-9H	09S	17E	9	INJW	N
ENSERCH EXPL	43-013-31108	33-9H	09S	17E	9	INJW	N
ENSERCH EXPL	43-013-30656	13-9H	09S	17E	9	INJW	N
EQUITABLE RE	43-013-31362	FEDERAL 11-6	09S	17E	6	INJW	Y
EQUITABLE RE	43-013-31361	FEDERAL 33-6	09S	17E	6	INJW	Y
EQUITABLE RE	43-013-31363	FEDERAL 24-6	09S	17E	6	INJW	Y
EQUITABLE RE	43-013-31364	FEDERAL 42-6	09S	17E	6	INJW	Y
EQUITABLE RE	43-013-30919	FEDERAL 22-6	09S	17E	6	INJW	Y
EQUITABLE RE	43-013-15779	FEDERAL 1-6	09S	17E	6	INJW	<u>Y</u>
EQUITABLE RE	43-013-30918	FEDERAL 13-6	098	17E	6	INJW	<u>Y</u>
EQUITABLE RE	43-047-15681	PARIETTE BEN	09S	19E	7	INJD	Y
EQUITABLE RE	43-013-31404	42-1J	09S	16E	1	WUNI	Y Y
EQUITABLE RE	43-013-31415	44-1J	09S	16E	1	INJW	N
EQUITABLE RE	43-013-30702	FEDERAL 1-13	09S 09S	16E 16E	1 1	INJW INJW	N
EQUITABLE RE	43-013-30735	FEDERAL 1-33 1-24	09S	16E	1	INJW	N
EQUITABLE RE EQUITABLE RE	43-013-30701 43-013-31384	22-5		-16E		INJW 17E	v
EQUITABLE RE	43-013-31364	34-10J	09S	16E	10	INJW	N N
EQUITABLE RE	43-013-31410	43-11J	09S	16E	11	INJW	N
EQUITABLE RE	43-013-31369	23-11J	09S	16E	11	INJW	N
EQUITABLE RE	43-013-31417	12-11J	095	16E	11	INJW	N
EQUITABLE RE	43-013-31386	32-11J	098	16E	11	INJW	N
EQUITABLE RE	43-013-31003	FEDERAL 34-1	098	16E	11	WLNI	N
EQUITABLE RE	43-013-31374	14-11J	09S	16E	11	INJW	N
EQUITABLE RE	43-013-31410	12-12J	09S	16E	12	INJW	N
EQUITABLE RE	43-013-31411	14-12J	09S	16E	12	INJW	N
EQUITABLE RE	43-013-30742	GOVT C&O #4	09S	16E	12	INJW	N
EQUITABLE RE	43-013-31419	32-12J	09S	16E	12	INJW	N .
EQUITABLE RE	43-013-31408	41-14J	09S	16E	14	INJW	N
EQUITABLE RE	43-013-31421	21-14J	09S	16E	14	WLMI	N
EQUITABLE RE	43-013-31367	41-15J	09S	16E	15	INJW	N
EQUITABLE RE	43-013-31373	23-15J	09S	16E	15	WLNI	N
EQUITABLE RE	43-013-31368	32-15J	09S	16E	15	INJW	· N
EQUITABLE RE	43-013-31375	24-5	09S	17E	5	INJW	Y
EQUITABLE RE	43-013-31370	FEDERAL 13-5	09S	17E	5	INJW	Y
EQUITABLE RE	43-013-31195	ALLEN FEDERA	098	17E	6	INJW	N Y
EQUITABLE RE	43-013-31405	31-7J	09S	17E	7	INJW	
EQUITABLE	43-013-31492	11-79	95	17E	7	INGW	N

Division of Oil, Gas OPERATOR CHANGE H				Routing:
	ion received by the division tem when completed. Write N		able.	2-DEF/88-FILE 3-VLD GIL
☐ Change of Opera ☐ Designation of		☐ Designation of KEX Operator Name 4	Agent Shange Only	5-IEQU/ 6-FILM
The operator of t	he well(s) listed below	w has changed (EFFEC	TIVE DATE: 4-1-96)
TO (new operator) (address)	EQUITABLE RESOURCES EI 1601 LEWIS AVE BILLINGS MT 59102-412		(address) BALCRON 1601 LE	OIL DIVISION WIS AVE
- · · <u></u>	phone <u>(406)259-7860</u> account no. <u>N9890</u>		phone (S MT 59102-4126 406) 259-7860 no. <u>N</u> 9890
Hell(s) (attach addi	tional page if needed):			
Name: Name:	API:013-3 API: API: API: API: API: API: API: API:	Entity: Entity: Entity:	_ SecTwpRng _ SecTwpRng SecTwnRng	Lease Type: Lease Type: Lease Type:
/ Operator (A	-8–10) Sundry or othe ttach to this form). C_ℓ	ectol 9-9-96 & 9-8-76/		4.5 4.5
operating a	ent of Commerce has be ny wells in Utah. Is ompany file number:	company registered	new operator abov with the state?	e is not currently (yes/no) If
comments se	and Federal Hells Of ephone Documentation ction of this form. uld take place prior to	Hanagement review of	ort). Make note of <mark>Federal and Inc</mark>	of BLM status in fian well operator
LC 5. Changes have	e been entered in the e	Oil and Gas Informa	tion System (Wang/	IBM) for each well
Lee 6. Cardex file	has been updated for e	each well listed abo	ve. (4-11-967	
Lec 7. Well file la	abels have been updated	l for each well list	ed above. (4-11-96)	
· ror digtribi	e been included on the Ition to State Lands an	d the Try Commission	n /// ///	
9. A folder has placed there	s been set up for the for reference during	Operator Change fil routing and process	e, and a copy of i	this page has been 1 documents.

OPERATOR	CHANGE WORKSHEET (CONTINUED) Initial each item when completed. Write N/A if item is not applicable.
ENTITY	REVIEW
Lic1.	(Rule R615-8-7) Entity assignments have been reviewed for all wells listed above. Were entity changes made? (yes/no) (If entity assignments were changed, attach copies of Form 6, Entity Action Form).
NA 2.	State Lands and the Tax Commission have been notified through normal procedures of entity changes.
BOND VE	RIFICATION (Fee wells only) # 5578314 (\$80,000) Sition Ins. C. (Bond Rider In Progress)
	(Rule_R615-3-1) The new operator of any fee lease well listed above has furnished a proper bond.
2.	A copy of this form has been placed in the new and former operators' bond files.
N/A 3.	The former operator has requested a release of liability from their bond (yes/no) Today's date 19 19 If yes, division response was made by letter dated 19
LEASE I	NTEREST OHNER NOTIFICATION RESPONSIBILITY
' .	(Rule R615-2-10) The former operator/lessee of any fee lease well listed above has been notified by letter dated 19, of their responsibility to notify any person with an interest in such lease of the change of operator. Documentation of such notification has been requested.
<u>15</u> 2.	Copies of documents have been sent to State Lands for changes involving State leases.
FILMING	All attachments to this form have been microfilmed. Date: My 20 19 W.
FILING	
1.	Copies of all attachments to this form have been filed in each well file.
	The <u>original</u> of this form and the <u>original</u> attachments have been filed in the Operator Change file.
COMMENT	S
9/04/10	Blm/BIA Formal approved not necessary".

WE71/34-35

STATE OF UTAH DIVISION OF OIL, GAS AND MINING

	5. Lease Designation and Serial Number:							
	See Attached							
SUNDRY NOTICES AND REPORTS								
CONDIN NO HOLO AND HELOING	n/a							
Do not use this form for proposals to drill new wells, deepen sxisting wells, or to reent	or plugged and abandoned wells.							
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for s	uch proposals. See Attached							
1. Type of Well: OIL XX GAS OTHER:	8. Well Name and Number:							
	See Attached							
2. Name of Operator: Inland Production Company	OCT 1 3 1997 OCT 1 3 1997 OCT 1 3 1997							
3. Address and Telephone Number:	10. Field and Pool, or Wildcat:							
475 - 17th Street, Suite 1500, Den	ver, CO 80202 See Attached							
Footages: See Attached Exhibit	_							
QQ, Sec., T., R.M.:	County:							
CC COC. I. I. I. I.	State:							
11. CHECK APPROPRIATE BOXES TO INDICATE N	ATURE OF NOTICE, REPORT, OR OTHER DATA							
NOTICE OF INTENT	SUBSEQUENT REPORT							
(Submit in Duplicate)	(Submit Original Form Only)							
☐ Abandon ☐ New Construction	☐ Abandon * ☐ New Construction							
Repair Casing Pull or Alter Casing	☐ Repair Casing ☐ Pull or Alter Casing							
☐ Change of Plans ☐ Recomplete	☐ Change of Plans ☐ Reperforate							
Convert to Injection Reperforate	☐ Convert to Injection ☐ Vent or Flare							
☐ Fracture Treat or Acidize ☐ Vent or Flare	☐ Fracture Treat or Acidize ☐ Water Shut-Off							
☐ Multiple Completion ☐ Water Shut-Off	CYOther Change of Operator							
OtherChange of Operator								
•	Date of work completion 9-30-97'							
Approximate date work will start	Report results of Multiple Completions and Recompletions to different reservoirs on WELL							
	COMPLETION OR RECOMPLETION REPORT AND LOG form.							
	Must be accompanied by a cement verification report.							
DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and givertical depths for all markers and zones pertinent to this work.)	e pertinent dates. If well is directionally drilled, give subsurface locations and measured and true							
Effective September 30, 1997, Inland Production Company will take over operations of the wells on the attached list. The previous operator was: Equitable Resources Energy Company								
1601 Lewis Avenue Billings, MT 59102								
Effective September 30, 1997, Inland Production Company is responsible under the terms and conditions of the leases for operations conducted on the leased lands or a portion thereof under State of Utah Statewide Bond No. 4471291.								
. OCT 1 1997								
13.								
Name & Signature: CHRIS	A. POTTER, ATTORNEY-IN-FACT Date: 9/30/97							

(4\04)

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

00T 1 0 1997

DECEINED

TRANSFER OF AUTHORITY TO INJECT - UIC FORM 5

OCT 1 3 1997

Well name and number: See Attached	**JONAH (GREEN RIVER) UNIT
Field or Unit name:See Attached	API no. See Attached
Well location: QQ section towns	thip range county
See Attached Effective Date of Transfer:September	
CURRENT OPERATOR	
Transfer approved by:	
Name David M. McCoskery	Company Equitable Resources Energy Co.
Signature M. Mahy	Address <u>1601 Lewis Avenue</u>
Title Director of Operations & Engineerin	g <u>Billings, MT</u> 59102
Date <u>9-30-97</u>	Phone (406) 259-7860 ·
Comments:	•
· · · · · · · · · · · · · · · · · · ·	
NEW OPERATOR	
Transfer approved by:	
Name Chris A Potter	Company Inland Production Company
Signature ()	Address 475 - 17th Street, Suite 1500
Title CHRISA. POTTER, ATTORNEY-IN-FACT	Denver, CO 80202
Date 9-30-97	Phone (303) 292-0900
Comments:	
(State use only) Transfer approved by	Title Envison Maugen
Approval Date 1-20-98	CANTESALLA
	CAUSE # 728-2
(3/89)	

1 .

Injection Wells for Inland Change of O		1				\ <u></u>	
WELL NAME	LOCATION	COUNTY	ST	FIELD NAME	API NUMBER	LEASE NO.	AGREEMENT NO.
AMERADA GUINAND #1	SWNW 7 8S 25E	UINTAH	UT	COYOTE BASIN	43-047-20245-00	UTU016271V	UTU72085A
COYOTE BASIN #42-6X	SENE 6 8S 25E	UINTA		COYOTE BASIN	43-047-32346-00	UTU017439B	UTU72085A
EAST RED WASH FED. #4-6	SWSE 6 8S 25E	UINTAH		COYOTE BASIN	43-047-20261-00	UTU020309D	UTU72085A
EAST RED WASH #2-5	NWNW 58S 25E	UINTA		COYOTE BASIN	43-047-20252-00	UTU063597A	UTU72085A
ÁLLEN FEDERAL #1	SESE 6 9S 17E	DUGUEONE		MONUNCHE DUTTE (I)	10.040.45770.00	NET 10000E0 A	117170000
ALLEN FEDERAL #13-6		DUCHESNE		MONUMENT BUTTE (J)	43-013-15779-00	UTU020252A	UTU72086A
ALLEN FEDERAL #13-6	NWSW 6 9S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-30918-00	UTU020252A	UTU72086A
ALLEN FEDERAL #22-6	SENW 6 9S 17E	DUCHESNE	UI	MONUMENT BUTTE (J)	43-013-30919-00	UTU020252A	UTU72086A
	LOT2 6 9S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31195-00	UTU020252A	UTU72086A
MONUMENT BUTTE FED. #11-6	NWNW 69S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31362-00	UTU020252A	UTU72086A
MONUMENT FEDERAL #11-7J	NW NW 7 9S 17E	DUCHESNE	UI	MONUMENT BUTTE (J)	43-013-31492-00	UTU44426	UTU72086A
MONUMENT BUTTE #13-5	NWSW 59S 17E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-31370-00		UTU72086A
MONUMENT BUTTE #22-5	SENW 5 9S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31384-00	UTU020252	UTU72086A
MONUMENT BUTTE #24-5	SESW 5 9S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31375-00	UTU020252	UTU72086A
MONUMENT BUTTE FED. #24-6	SESW 69S 17E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-31363-00	UTU020252A	UTU72086A
MONUMENT BUTTE #31-7	NWNE 7 9S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31405-00	UTU72106	UTU72086A
MONUMENT BUTTE FED. #33-6	NWSE 6 9S 17E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-31361-00	UTU020252A	UTU72086A
MONUMENT BUTTE FED. #42-6	SENE 6 9S 17E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-31364-00	UTU020252A	UTU72086A
MONUMENT BUTTE FED. #12-11	SWNW 119S 16E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-31417-00	UTU096550	UTU72086A
MONUMENT BUTTE FED. #14-11	SWSW 119S 16E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-31374-00	UTU096547	UTU72086A
MONUMENT BUTTE #12-12	SWNW 129S 16E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-31410-00	UTU096550	UTU72086A
MONUMENT BUTTE #14-12	SWSW 129S 16E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-31411-00		UTU72086A
MONUMENT BUTTE #21-14	NENW 149S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31421-00	1	UTU72086A
MONUMENT BUTTE #23-11	NESW 119S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31369-00	UTU096550	UTU72086A
MONUMENT BUTTE FED. #23-15	NESW 159S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31373-00	UTU017985	UTU72086A
MONUMENT BUTTE #32-11	SWNE 119S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31386-00	010017000	UTU72086A
MONUMENT BUTTE #32-12	SWNE 129S 16E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-31419-00		UTU72086A
MONUMENT BUTTE #41-14	NENE 149S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31408-00	UTU096550	UTU72086A
MONUMENT BUTTE #43-11	NESE 119S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31002-00	UTU096550	UTU72086A
MONUMENT BUTTE FED. #32-15	SWNE 159S 16E	DUCHESNE	IIT	MONUMENT BUTTE (J)	43-013-31368-00	UTU017985	UTU72086A
MONUMENT BUTTE FED. #34-10	SWSE 109S 16E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-31416-00	UTU017985	UTU72086A
MONUMENT BUTTE FED. #41-15	NENE 159S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31367-00		
MONUMENT BUTTE FED. #42-1	SENE 1 9S 16E	DUCHESNE	UT	MONUMENT BUTTE (J)		UTU017985	UTU72086A
MONUMENT BUTTE FED. #44-1J	SESE 1 9S 16E	DUCHESNE			43-013-31404-00	UTU40652	UTU72086A
0&O GOV'T #4	NESW 129S 16E			MONUMENT BUTTE (J)	43-013-31415-00	UTU44426	UTU72086A
MONUMENT BUTTE FED. #1-13	NWSW 1 9S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-30742-00	UTU035521A	UTU72086A
MONUMENT BUTTE FED. #1-13	NWSE 1 9S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-30702-00	UTU18399	UTU72086A
MONUMENT BUTTE #1-24		DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-30735-00	UTU52013	UTU72086A
	SESW 1 9S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-30701-00	UTU18399	UTU72086A
WALTON FEDERAL #34-11	SWSE 119S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31003-00	UTU096550	UTU72086A
MONUMENT STATE #11-2-9-17CD	NW NW 2 9S 17E	DUCHESNE	UT	MONUMENT BUTTE (CD)	43-013-42685	ML 45555	

11422

11426 11438 Page No. 06/16/97

STATE OF UTAH INVENTORY OF INJECTION WELLS

OPERATOR *******	API NO.	WELL ******	TNS	RGE ***	SE **	WELLTYPE *****	INDIAN COUNT
COASTAL OIL	43-013-30337	G. HANSON #2	02S	03W	4	INJD	*****
COASTAL OIL	43-013-30038	2-23B4 LAKE	02S	04W	23	INJD	Y
COASTAL OIL	43-013-30371	L RUSSELL 2-	02S	04W	32	INJD	Y
COASTAL OIL	43-013-30391	EHRICH 2-11B	02S	05W	11	INJD	Y
COASTAL OIL	43-013-30340	LDS CHURCH #	02S	05W	27	INJD	Ϋ́
COASTAL OIL	43-047-31996	NBU 159	025 09S	21E	35	INJD	Y
COCHRANE RES		3-23	38S	25E	23	INJW	Y
COCHRANE RES		1-25	38S	25E	25	INJW	N
COCHRANE RES		4-25	38S	25E	25	INJW	N
COCHRANE RES		WDW 1	38S	25E	25	INJD	N
COCHRANE RES		3-26	38S	25E	26		N
CROSS CREEK	43-037-16269	SOUTH ISMAY	41S	26E		INJW	N
CROSS CREEK	43-037-20117	NAVAJO A #1	41S	26E	5	INJD	Y
CROSS CREEK	43-037-20164	NAVAJO A #1			5	INJD	Y
ENSERCH EXPL		FEDERAL 14-3	41S	26E	5	INJI	Y
ENSERCH EXPL		FEDERAL 14-3 FEDERAL 43-3	08S	16E	33	INJW	N
ENSERCH EXPL			08S	16E	33	INJW	N
ENSERCH EXPL		FEDERAL 34-3	08S	16E	33	INJW	N
ENSERCH EXPL		FEDERAL 14-3	08S	16E	34	INJW	N
ENSERCH EXPL	43-013-31272	FEDERAL 21-4	09S	16E	4	INJW	N
ENSERCH EXPL	43-013-31205	FEDERAL 41-5	09S	16E	5	INJW	N
ENSERCH EXPL		FEDERAL 32-5	09S	16E	5	WLMI	N
ENSERCH EXPL	43-013-30913	44-5H	09S	17E	5	INJW	N
ENSERCH EXPL	43-013-30678	42-8H	09S	17E	8	INJW	N
ENSERCH EXPL	43-013-31457	22-8H	09S	17E	8	INJW	N
ENSERCH EXPL	43-013-30679	31-8H	09S	17E	8	INJW	N
ENSERCH EXPL	43-013-31049	22-9H	09S	17E	9	INJW	N
ENSERCH EXPL	43-013-30887	11-9H	09S	17E	9	WLMI	N
ENSERCH EXPL	43-013-31108	33-9H	09S	17E	9	INJW	N
ENSERCH EXPL	43-013-30682	24-9H	09S	17E	9	WLMI	N
	43-013-30656 43-013-31364	13-9H	09S	17E	9	WLMI	N
		FEDERAL 42-6	09S	17E	6	INJW	Y
	43-013-31361 43-013-15779	FEDERAL 33-6	09S	17E	6	WLMI	Y
		FEDERAL 1-6	09S	17E	6	WLMI	Y
	43-013-31362	FEDERAL 11-6	09S	17E	6	WLMI	Y
	V43-013-30919	FEDERAL 22-6	09S	17E	6	WUNI	Y
	43-013-31363	FEDERAL 24-6	09S	17E	6	INJW	Y
	43-013-30918	FEDERAL 13-6	09S	17E	6	INJW	Y
	43-047-15681	PARIETTE BEN	09S	19E	7	INJD	Y
	43-013-30735	FEDERAL 1-33	09S	16E	1	INJW	N
	43-013-30702	FEDERAL 1-13	09S	16E	1	INJW	N
	43-013-30701	1-24	09S	16E	1	INJW	N
	43-013-31404	42-1J	09S	16E	1	INJW	Y
	43-013-31415	44-1J	09S	16E	1	WLMI	Y
	43-013-31416	34-10J	09S	16E	10	INJW	N
	43-013-31002	43-11J	09S	16E	11	INJW	N
	43-013-31369	23-11J	09S	16E	11	WLMI	N
EQUITABLE RE	√43-013-31417	12-11J	09S	16E	11	INJW	N
EQUITABLE RE	43-013-31386	32-11J	09S	16E	11	INJW	N
EQUITABLE RE	43-013-31374	14-11J	09S	16E	11	INJW	N
	43-013-31003	FEDERAL 34-1	09S	16E	11	INJW	N
	√43-013-31419	32-12J	09S	16E	12	INJW	N
EQUITABLE RE	43-013-31411	14-12J	09S	16E	12	WLMI	N
EQUITABLE RE	43-013-30742	GOVT C&O #4	09S	16E	12	INJW	N



(406) 259-7860 Telephone (406) 245-1361 Fax

December 10, 1997

Lisha
State of Utah
Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, UT 84114-5801

Dear Lisha:

RE: Equitable Sale of Utah Properties

Effective September 30, 1997, Equitable Resources Energy Company sold all of its Utah properties to Inland Production Company.

Please feel free to contact me if you require additional information.

Sincerely,

Molly Conrad

Agent for Equitable Resources

Energy Company

/mc



Crazy Mountain Oil & Gas Services P.O. Box 577 Laurel, MT 59044 (406) 628-4164 (406) 628-4165

TO: Lishar St of Wan.

FROM.

Molly Conrad

Crazy Mountain Oil & Gas Services

(406) 628-4164

Pages Attached - Including Cover Sheet 2.

NOTE:

Here is the letter you requested. Callieb you need anything further.



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office P.O. Box 45155 Salt Lake City, UT 84145-0155

IN REPLY REFER TO UT-931

January 13, 1998

Inland Production Company 475 17th Street, Suite 1500 Denver, Colorado 80202

Re:

Jonah (Green River) Unit

Duchesne County, Utah

Gentlemen:

On January 13, 1998, we received an indenture dated November 17, 1997, whereby Equitable Resources Energy Company resigned as Unit Operator and Inland Production Company was designated as Successor Unit Operator for the Jonah (Green River) Unit, Duchesne County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective January 13, 1998. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under Jonah (Green River) Unit Agreement.

Your statewide (Utah) oil and gas bond No. 0056 will be used to cover all operations within the Jonah (Green River) Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Robert A. Henricks

Robert A. Henricks Chief, Branch of Fluid Minerals

Enclosure

bcc: District Manager - Vernal (w/enclosure)

Division of Oil Gas & Mining / Minerals Adjudication Group U-932

File - Jonah (Green River) Unit (w/enclosure)

MMS - Data Management Division

Agr. Sec. Chron

Fluid Chron

U-931:TAThompson:tt:1/13/98

Page No. 01/13/98

UTU72086A

UTU72086A

UTU72086A

430133136300s1 24-6

430133061300s1 31-15

430131579100s1 3

SESW

6 9s

NWNW 14 9s

NWNE 15 98

17E

16E

16E

WIW

POW

POW

UTU020252A

UTU096547

UTU017985

EQUITABLE RESOURCES ENERG

EQUITABLE RESOURCES ENERG

EQUITABLE RESOURCES ENERG

WELL STATUS REPORTS
UTAH STATE OFFICE

INSPECTION ITEM

1

API NO.

WELL

QTQT SEC TWN RNG WELL

LEASE NAME

OPERATOR

INSPECTION I	TEM API NO.	NUMBER	WIWI	SEC	I WN	KNG	STATUS	LEASE NAME	OPERATOR	
** INSPECTION IT	EM UTU72086A	JONAH ((GR) SECO	ONDAF	REI	COVERY	UNIT			
UTU72086A	430131511100s1		NWSW			16E	POW	UTU035521A	EQUITABLE RESOURCES ENERG	
UTU72086A	430131578000\$1	1	NWNW	5	9s	17E	POW	UTU020252	EQUITABLE RESOURCES ENERG	
UTU72086A	430131577900s1	1	SESE	6	9s	17E	WIW	UTU020252A	EQUITABLE RESOURCES ENERG	
UTU72086A	430131578900s1	1	SESW	11	9 S	16E	POW	UTU096547	EQUITABLE RESOURCES ENERG	
UTU72086A	43013157920081	1	SESE	11	9 S	16E	POW	UTU096550	EQUITABLE RESOURCES ENERG	
UTU72086A	430133070200s1	1-13	NWSW	1	9s	16E	WIW	UTU18399	EQUITABLE RESOURCES ENERG	
UTU72086A	430133070300s1	1-14	SWSW	1	9s	16E	POW	UTU18399	EQUITABLE RESOURCES ENERG	
UTU72086A	430133064600s1	1-23	NESW	1	9s	16E	POW	UTU18399	EQUITABLE RESOURCES ENERG	
UTU72086A	430133070100s1	1-24	SESW	1	9s	16E	WIW	UTU18399	EQUITABLE RESOURCES ENERG	
UTU72086A	430133073500s1	1-33	NWSE	1	9s	16E	WIW	UTU52013	EQUITABLE RESOURCES ENERG	
UTU72086A	430133073600s1	1-34	SWSE	1	9s	16E	POW	UTU52013	EQUITABLE RESOURCES ENERG	
UTU72086A	430133073400s1	1-43	NESE	1	9s	16E	POW	UTU52013	EQUITABLE RESOURCES ENERG	
UTU72086A	430133136200s1	11-6	L4	6	98	17E	WIW	UTU020252A	EQUITABLE RESOURCES ENERG	
UTU72086A	430133149200s1	11-7J	NUNU	7	9 S	17E	WIW	UTU44426	EQUITABLE RESOURCES ENERG	
UTU72086A	430133088900\$1	12-1	NWNE	12	9s	16E	POW	UTU44426	EQUITABLE RESOURCES ENERG	
UTU72086A	430133141700\$1	12-11J	SWNW	11	98	16E	WIW	UTU096550	EQUITABLE RESOURCES ENERG	
UTU72086A	430133141000\$1	12-12J	SWNW	12	9 s	16E	WIW	UTU096550	EQUITABLE RESOURCES ENERG	
UTU72086A	430133061100s1	12-5	SWNW	5	9s	17E	POW	UTU020252	EQUITABLE RESOURCES ENERG	
UTU72086A	430133058200\$1	12-6	SWNW	6	9 \$	17E	POW	UTU020252A	EQUITABLE RESOURCES ENERG	
UTU72086A	430133149300\$1	12-7J	SWNW	7	9s	17E	POW	UTU44426	EQUITABLE RESOURCES ENERG	
UTU72086A	430131579000\$1	13-11J	NWSW	11	9s	16E	POW	UTU096547	EQUITABLE RESOURCES ENERG	
UTU72086A	430133137000s1	13-5	NWSW	5	9s	17E	WIW	UTU020252	EQUITABLE RESOURCES ENERG	
UTU72086A	430133091800s1	13-6	NWSW	6	9s	17E	WIW	UTU020252A	EQUITABLE RESOURCES ENERG	
UTU72086A	430133137400s1	14-11	SWSW	11	9s	16E	WIW	UTU096547	EQUITABLE RESOURCES ENERG	
UTU72086A	430133141100s1	14-12J	SWSW	12	9s	16E	WIW	UTU035521A	EQUITABLE RESOURCES ENERG	
UTU72086A	430133138500s1	14-5	SWSW	. 5	9s	17E	POW	UTU020252	EQUITABLE RESOURCES ENERG	
UTU72086A	430131511200s1	2	NWSE	12	9s	16E	POW	UTU0 3 5521	EQUITABLE RESOURCES ENERG	
UTU72086A	430131579300s1	2	NWNE	14	9\$	16E	POW	UTU096550	EQUITABLE RESOURCES ENERG	
UTU72086A	430133060300s1	2-1	L1	1	9s	16E	POW	UTU 33 992	EQUITABLE RESOURCES ENERG	
UTU72086A	430133140600X1	21-12J	NENW	12-	9s	16E	ABD	UTU096550	EQUITABLE RESOURCES ENERG-	
UTU72086A	430133142100s1	21-14J	NENW	14	9s	16E	WIW	UTU096547	EQUITABLE RESOURCES ENERG	
UTU72086A	430133142200 x1	21-15J	NENW	-15-	93	16E	ABD	UTU017985	EQUITABLE RESOURCES ENERG	
UTU72086A	43013306120081	21-5	NENW	5	9 8	17E	POW	UTU020252	EQUITABLE RESOURCES ENERG	
UTU72086A	430133058400\$1	21-6	L3	6	9 s	17E	POW	UTU020252A	EQUITABLE RESOURCES ENERG	
UTU72086A	430131579600s2	22-12J	SENW	12	9s	16E	POW	UTU096550	EQUITABLE RESOURCES ENERG	
UTU72086A	430133063400s1	22-15	SENW	15 9	9S	16E	POW	UTU017985	EQUITABLE RESOURCES ENERG	
UTU72086A	430133138400s1	22-5	SENW	5	9s	17E	WIW	UTU020252	EQUITABLE RESOURCES ENERG	
UTU72086A	430133091900s1	22-6	SENW	6 '	9S	17E	WIW	UTU020252A	EQUITABLE RESOURCES ENERG	
UTU72086A	430133136900s1	23-11	NESW	11 9	9S	16E	WIW	UTU096550	EQUITABLE RESOURCES ENERG	
UTU72086A	430133137300s1	23-15	NESW	15	9S	16E	WIW	UTU017985	EQUITABLE RESOURCES ENERG	
UTU72086A	430133138300s1	23-5	NESW	5 9	9 S	17E	POW	UTU020252	EQUITABLE RESOURCES ENERG	
UTU72086A	430133055800s1	23-6	NESW	6	98	17E	POW	UTU020252A	EQUITABLE RESOURCES ENERG	
UTU72086A	430133140900s1	24-12J	SESW	12 9	9S	16E	POW	UTU035521A	EQUITABLE RESOURCES ENERG	
UTU72086A	430133063100s1	24-15	SESW	15 9	9 S	16E	POW	UTU017985	EQUITABLE RESOURCES ENERG	
UTU72086A	430133137500s1	24-5	SESW	5 9	9S	17E	WIW	UTU020252	EQUITABLE RESOURCES ENERG	
11711700074	1704774717000				^-	47-				

Page No. 01/13/98


WELL STATUS REPORTS UTAH STATE OFFICE

INSPECTION ITEM	API NO.	WELL NUMBER	QTQT	SEC	TWN	RNG	WELL Status	LEASE NAME	t	OPERATOR .	
UTU72086A	430133141300s1	31-1J	L2	1	9s	16E	POW	UTU 33 992	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133119500s1	31-6	L2	6	9s	17E	WIW	UTU020252A	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133140500s1	31-7J	NWNE	7	9\$	17E	WIW	UTU44426	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133138600s1	32-11	SWNE	11	9s	16E	WIW	UTU096550	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133141900s1	32-12J	SWNE	12	9s	16E	WIW	UTU035521	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133136800s1	32-15	SWNE	15	9s	16E	WIW	UTU017985	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133141400s1	32-1J	SWNE	1	9\$	16E	POW	UTU33992	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133055900s1	32-6	SWNE	6	9s	17E	POW	UTU020252A	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133145100s1	33-11j	NWSE	11	9 S	16E	OSI	UTU096550	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133063200s1	33-15	NWSE	15	98	16E	POW	UTU017985	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133136100s1	33-6	NWSE	6	9s	17E	WIW	UTU020252A	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133141600s1	34-10J	SWSE	10	9s	16E	WIW	UTU017985	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133100300s1	34-11	SWSE	11	9s	16E	WIW	UTU096550	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133058600s1	34-6	SWSE	6	9s	17E	POW	UTU020252A	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133074200s1	4	NESW	12	9s	16E	WIW	UTU035521A	EQUITABLE	RESOURCES	ENERG
UTU72086A	430131579500s1	4	SENW	11	9s	16E	POW	UTU096550	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133148700s1	41-12J	NENE	12	9s	16E	POW	UTU44426	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133140800s1	41-14J	NENE	14	9s	16E	WIW	UTU096550	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133136700s1	41-15	NENE	15	9s	16E	WIW	UTU017985	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133058100s1	41-6	NENE	6	9s	17E	POW	UTU020252A	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133006600s1	42-11J	SENE	11	98	16E	POW	UTU096550	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133148600s1	42-12J	SENE	12	9s	16E	POW	UTU035521	EQUITABLE	RESOURCES	ENERG
UTU72086A	43013306330081	42-15	SENE	15	9s	16E	POW	UTU017985	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133140400s1	42-1J	SENE	1	9s	16E	WIW	UTU40652	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133136400\$1	42-6	SENE	6	9s	17E	WIW	UTU020252A	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133100200s1	43-11J	NESE	11	9s	16E	WIW	UTU096550	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133058300s1	43-6	NESE	6	9S	17E	POW	UTU020252A	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133063000s1	44-10	SESE	10	9s	16E	POW	UTU017985	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133141500s1	44-1j	SESE	1	9s	16E	WIW	UTU44426	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133092600s1	7-A	NENE	7	9s	17E	POW	UTU44426	EQUITABLE	RESOURCES	ENERG
UTU72086A	430133096100s1	7-c	NENW	7	9s	17E		UTU44426	EQUITABLE	RESOURCES	ENERG

JONAH (GREEN RIVER) UNIT

DUCHESNE COUNTY, UTAH

EFFECTIVE: JULY 1, 1993



16E

UNIT OUTLINE (UTU72086A)

4,221.61 ACRES

SECONDARY ALLOCATION FEDERAL 100.00% Division of Oil, Gas and Mining

OPERATOR CHANGE WORKSHEET

Attach all documentation received by the division regarding this change. Initial each listed item when completed. Write N/A if item is not applicable.

Routing:	
1-1100	64 Acr
2-04-11	7-KAS
3-DT82713	8-SI /
4-VLD	9-FILE
5-JPAY	

			_		•	•			Ls	-IPB	
		ange of Opera signation of O	•	old)		ignation of rator Name	•	Only			
The	ope	erator of the w	vell(s) listed	l below has cl	hanged, e	ffective: _	9-30-97	, ———			
то	: (ne	ew operator) (address)	PO BOX ROOSEVE		6	FROM:	` -	rator) address)	PO BOX 5 LAUREL M C/O CRAZ Phone:	577	
WE	LL((S) attach addition	onal page if no	eeded:		*JONAH	(GREEN	river)	UNIT	-	
Name Name Name Name Name Name	e: _ e: _ e: _ e: _	**SEE ATTAC		API: API: API:	3-3131	Entity: _ Entity: _		S T S T S T S T S T S T	R	Lease:	
OPI	1. 2.	form). (L	Sundry or or $c'c'$ / 2-10 Sundry or	ther legal doc	umentatio						
NA	3.	The Depart wells in Utal	ment of C h. Is the co	ommerce has ompany regis	s been con tered wit	ntacted if the state	he new o ? (yes/n	perator a	bove is not If yes, shov	currently ow company	perating any file number:
Jec Jec	4.	FOR INDIA note of BLM changes sho through 9 be	A status in ould ordina	EDERAL WE comments se rily take plac	ction of t	his form.	BLM app	oroval of	Federal ar	id Indian v	vell operator
fic he	5.6.	Changes hav (1-14-98) Cardex file l	e been ente ** uc/o has been u	ered in the Oi allow fro 1-14-9 and ated for each	l and Gas	s Informat C/DB+5.e /- ted above.	tion Syst -14-98.	em (3270) for each v	well listed a	bove.
Lec	7.	Well file lab									
Lec	8.	Changes have to Trust Land	been inclu ls, Soverei	ded on the mogn Lands, UG	onthly "O S, Tax Co	perator, Acommission	ddress, ar , etc. //-	nd Accou -14-98)	nt Changes	" memo for	distribution
Jec.	9.	A folder has reference dur	been set using routing	p for the Op	erator C	hange file original do	e, and a concents.	copy of th	nis page ha	s been plac	ed there for

ENTITY REVIEW 1. (r649-8-7) Entity assignments have been reviewed for all wells listed above. Were entity changes made? (yes(no)) If entity assignments were changed, attach copies of Form 6, Entity Action Form. Entity
(yes/no) If entity assignments were changed, attach copies of Form 6, Entity Action Form. End: Ly 1492 " Jornah (GP) Un; f". 2. Trust Lands, Sovereign Lands, Tax Commission, etc., have been notified through normal procedures of entity changes. BOND VERIFICATION - (FEE WELLS ONLY) 1. (r649-3-1) The NEW operator of any fee lease well listed above has furnished a proper bond. 2. A copy of this form has been placed in the new and former operator's bond files. 3. The FORMER operator has requested a release of liability from their bond (yes/no), as of today's date
1. (r649-3-1) The NEW operator of any fee lease well listed above has furnished a proper bond. 2. A copy of this form has been placed in the new and former operator's bond files. 3. The FORMER operator has requested a release of liability from their bond (yes/no), as of today's date
 2. A copy of this form has been placed in the new and former operator's bond files. 3. The FORMER operator has requested a release of liability from their bond (yes/no), as of today's date
 2. A copy of this form has been placed in the new and former operator's bond files. 3. The FORMER operator has requested a release of liability from their bond (yes/no), as of today's date
LEASE INTEREST OWNER NOTIFICATION OF RESPONSIBILITY
1. Copies of documents have been sent on to at Trust Lands for changes involving State leases, in order to remind that agency of their responsibility to review for proper bonding.
2. (r649-2-10) The former operator of any fee lease wells listed above has been contacted and informed by letter dated19, of their responsibility to notify all interest owners of this change.
FILMING
1. All attachments to this form have been microfilmed. Today's date: 2,3,98
FILING
1. Copies of all attachments to this form have been filed in each well file.
2. The original of this form , and the original attachments are now being filed in the Operator Change file.
COMMENTS
980114 B/m /54 aprv. eft. 1-13-98.

STATE OF UTAH DIVISION OF OIL GAS AND MINING



			1.0
Well Name: MON FRORM 33-11J	API Number: _4	<u> 13.013-5136</u>	39
Qtr/Qtr: NE/SW Section: //	Township: 9	∑ Range: _	16E
Company Name: TNI AND PROPE	ACTION CO.	nPavy	
Lease: State Fee			
Inspector: Linnis Longa	D. ()	17.00	
Inspector: Pinns - Onça-	Date: <u>06-7</u>	7-00	
Initial Conditions:			
Tubing - Rate:	Pressure:_	1800	_ psi
Casing/Tubing Annulus - Pressure: 1310	psi	j.	
Conditions During Test:			
Time (Minutes) Annulus Pres	ssure_	Tubing Pressure	
0 /2(0	PSI	1800 PSI	
5 <u>(210</u>		1800	_
10		1800	_
15 <u>/∂/0</u>		1800	-
20 <u>[] [] [] [</u>		1800	_
25 / <i>ð/0</i>		1800	_
30 <u>1910</u>		1.800	_
Results: Pass/Fail			
Conditions After Test:			
Tubing Pressure: / ბ O psi			
Casing/Tubing Annulus Pressure: COMMENTS: Destul for Sigur Nu) psi	•	
COMMENTS: Testal for 5 year ru	le In	ut. Ob	256 BP1
COMMENTS. 12014 An Syun 74	us. In	us un Co.	
			
	testal	2) 12:15 A	n
ο			
Kar Leskooll			
Operator Representative			

May 5, 1987

STATE OF UTAH			
DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		5. LEASE DESIGNATION AND SERIAL NO. U-096550	
SUNDRY NOTICES AND REPORTS ON WELLS		6. IF INDIAN, ALLOTTEE OR TRIBAL NAME	
(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT" for such proposals.)		N/A	
		7. UNIT AGREEMENT NAME	
OIL GAS WELL OTHER		JONAH	
2. NAME OF OPERATOR INLAND PRODUCTION COMPANY		8. FARM OR LEASE NAME MONUMENT FEDERAL 23-11J	
3. ADDRESS OF OPERATOR Route 3, Box 3630, Myton Utah 84052		9. WELL NO. MONUMENT FEDERAL 23-11J	
(435-646-3721) 6+			
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface		10 FIELD AND POOL, OR WILDCAT MONUMENT BUTTE	
NE/SW 1787 FSL 2147 FWL		11 SEC., T., R., M., OR BLK. AND SURVEY OR AREA NE/SW Section 11, T09S R16E	
14 API NUMBER 43-013-31369 15. ELEVATIONS (Show whether DF, RT, GR, etc.) 5622 GR		12 COUNTY OR PARISH DUCHESNE	13 STATE UT
16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data NOTICE OF INTENTION TO: SUBSECTION		UENT REPORT OF:	
NOTICE OF INTENTION TO			 1
TEST WATER SHUT-OFF PULL OR ALTER CASING	WATER SHUT-OFF	REPAIRING WELL	
FRACTURE TREAT MULTIPLE COMPLETE	FRACTURE TREATMENT	ALTERING CASING	
SHOOT OR ACIDIZE ABANDON*	SHOOTING OR ACIDIZING ABANDONMENT*		
REPAIR WELL	(OTHER) Perform 5 year MIT		
(OTHER)	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)		
17 DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all per proposed work. If well is directionally drilled, give subsurface locations and mea			
The MIT was conducted on the subject well to satisfy the f charted for thirty minutes with no leak off. Mr. Dennis Ing	five year MIT. On 6-7-00 t gram with the DOGM was i	he casing was pressured up n attendance and approved	to 1210 psi and the test.
	Accepte Utah Di	ed by the vision of and Mining	
18 I hereby certify that the foregoing is true and correct SIGNED Rod Bird TITLE	Production Foreman CONTRECT	ORD ONLY	6/7/00
(This space for Federal or State office use) APPROVED BY		DATE	

* See Instructions On Reverse Side

RECEIVED


JUN 0 9 2000 DIVISION OF OIL, GAS AND MINING

Machanical Integrity Test Casing or Annulus Pressure Test

Inland Production Company Rt. 3 Box 3630 Myton, UT 84052

435-646-3721

Witness: DSMMS Tugken Test Conducted by: Koy Li Others Present:	Date le 17 100	Time 12:15
Well: Monument Fed 23-47-6 Well Location: NE/SW SEC, 11, To Duchesne Co, UT	35. R V. S	ument Buttz -013-31369
<u>Time</u>	Casing Pressure	
0 min 5 10 15 20 25 30 min 35 40 45 50 55	1210 1210 1210 1210 1210 1210	psig psig psig psig psig psig psig psig
Tubing pressur Result:	Pass	psig OIL, GAS AND MINING psig psig injecting @ 63.56 BPJ Fail
Signature of Person Co	nducting Test: Ray	dedell





United States Department of the Interior



BUREAU OF LAND MANAGEMENT Utah State Office P.O. Box 45155 Salt Lake City, UT 84145-0155 http://www.blm.gov

IN REPLY REFER TO: 3106 (UT-924)

September 16, 2004

Memorandum

To:

Vernal Field Office

From:

Acting Chief, Branch of Fluid Minerals

Subject:

Merger Approval

Attached is an approved copy of the name change recognized by the Utah State Office. We have updated our records to reflect the merger from Inland Production Company into Newfield Production Company on September 2, 2004.

Milas Loutas

Michael Coulthard Acting Chief, Branch of Fluid Minerals

Enclosure

1. State of Texas Certificate of Registration

cc:

MMS, Reference Data Branch, James Sykes, PO Box 25165, Denver CO 80225 State of Utah, DOGM, Attn. Earlene Russell, PO Box 145801, SLC UT 84114

Teresa Thompson Joe Incardine

Connie Seare

Corporations Section P.O.Box 13697 Austin, Texas 78711-3697





Office of the Secretary of State

The undersigned, as Secretary of State of Texas, does hereby certify that the attached is a true and correct copy of each document on file in this office as described below:

Newfield Production Company Filing Number: 41530400

Articles of Amendment

September 02, 2004

In testimony whereof, I have hereunto signed my name officially and caused to be impressed hereon the Seal of State at my office in Austin, Texas on September 10, 2004.





Secretary of State

ARTICLES OF AMENDMENT TO THE ARTICLES OF INCORPORATION OF INLAND PRODUCTION COMPANY

In the Office of the Secretary of State of Texas

SEP 02 2004

Corporations Section

Pursuant to the provisions of Article 4.04 of the Texas Business Corporation Act (the "TBCA"), the undersigned corporation adopts the following articles of amendment to the articles of incorporation:

ARTICLE 1 - Name

The name of the corporation is Inland Production Company.

ARTICLE 2 - Amended Name

The following amendment to the Articles of Incorporation was approved by the Board of Directors and adopted by the shareholders of the corporation on August 27, 2004.

The amendment alters or changes Article One of the Articles of Incorporation to change the name of the corporation so that, as amended, Article One shall read in its entirety as follows:

"ARTICLE ONE - The name of the corporation is Newfield Production Company."

ARTICLE 3 - Effective Date of Filing

This document will become effective upon filing.

The holder of all of the shares outstanding and entitled to vote on said amendment has signed a consent in writing pursuant to Article 9.10 of the TBCA, adopting said amendment, and any written notice required has been given.

IN WITNESS WHEREOF, the undersigned corporation has executed these Articles of Amendment as of the 1st day of September, 2004.

INLAND RESOURCES INC.

By: Susan G. Riggs, Treasurer

			• •		•
UTSL-	15855	61052	73088	76561	
071572A	16535	62848	73089	76787	-
065914	16539	63073B	73520A	76808	
	16544	63073D	74108	76813	
	17036	63073E	74805	76954	63073X
	17424	63073O	74806	76956	63098A
	18048	64917	74807	77233	68528A
UTU-	18399	64379	74808	77234	72086A
	19267	64380	74389	77235	72613A
02458	26026A	64381	74390	77337	7201371 73520X
03563	30096	64805	74391	77338	74477X
03563A	30103	64806	74392	77339	75023X
04493	31260	64917	74393	77357	76189X
05843	33992	65207	74398	77359·	76331X
07978	34173	65210	74399	77365	76788X
09803	34346	65635	74400	77369	77098X
017439B	36442	65967	74404	77370	77107X
017985	36846	65969	74405	77546	77236X
017991	38411	65970	74406	77553·	77376X
017992	38428	66184	74411	77554	78560X
018073	38429	66185	74805	78022	79485X
019222	38431	66191	74806	79013	79641X
020252	39713	67168	74826	79014	80207X
020252A	39714	67170	74827	79015	81307X
020254	40026	67208	74835	79016	, 0100111
020255	40652	67549	74868	79017	
020309D	40894	67586	74869	79831	,
022684A	41377	67845	74870	79832	•
027345	44210	68105	74872	79833 [,]	
034217A	44426	68548	74970	79831	
035521	44430	68618	75036	79834	•
035521A	45431	69060	75037	80450	
038797	47171	69061	75038	80915	
058149	49092	69744	75039	81000	
063597A	49430	70821	75075		
075174	49950	72103	75078		•
096547	50376	72104	75089		
096550	50385	72105	75090		
	50376	72106	75234		
	50750	72107	75238		
10760	51081	72108	76239		
11385	52013	73086	76240		
13905	52018	73087	76241		
15392	58546	73807	76560		
•					

3033824454

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING

UIC FORM 5

ell Name and See Attach			API Number
ocation of We			
Footage :		County ;	Field or Unit Name See Attached List
_	n, Township, Range:	• •	Lease Designation and Number
	у типус	State: UTAH	
FFECTIVE	DATE OF TRANSFER: 9/1/2004		
JRRENT O	PERATOR		
Company:	inland Production Company	Name: Brid	an Harris
Address:	1401 17th Street Suite 1000		
	city Denver state Co zip 80202	- 	ineering Tech.
Phone:	(303) 893-0102		5/2004
_		Date: 9/1	// CVV*
Comments			
Comments:	TOR		
	OR Newfield Production Company	Name: Bria	n Harris ⊿∕/
W OPERAT	TOR	· · · · · · · · · · · · · · · · · · ·	n Harris
W OPERAT Company: Address:	OR Newfield Production Company	Signature:	
W OPERAT Company: Address:	Newfield Production Company 1401 17th Street Suite 1000	Signature: 7	ng Harris May Thomas The control of the control
W OPERAT Company: Address:	Newfield Production Company 1401 17th Street Suite 1000	Signature: 7	g Harris Man
W OPERAT Company: Address; Phone:	Newfield Production Company 1401 17th Street Suite 1000	Signature: 7	ng Harris May Thomas The control of the control
W OPERAT Company: Address; Phone:	Newfield Production Company 1401 17th Street Suite 1000	Signature: 7	ng Harris May Thomas The control of the control
W OPERAT Company: Address: Phone: Comments:	Newfield Production Company 1401 17th Street Suite 1000 city Denver state Co zip 80202	Signature: 7	ng Harris May Thomas The control of the control
W OPERATOR OF THE PROPERTY OF	Newfield Production Company 1401 17th Street Suite 1000 city Denver state Co zip 80202	Signature: 7 Title: Engi	neering Tech.
W OPERATOR OF THE PROPERTY OF	Newfield Production Company 1401 17th Street Suite 1000 city Denver state Co zip 80202	Signature: 7 Title: Engi	neering Tebh.
W OPERATOR OF THE PROPERTY OF	Newfield Production Company 1401 17th Street Suite 1000 city Denver state Co zip 80202	Signature: 7 Title: Engi	neering Tebh.
W OPERATOR OF THE PROPERTY OF	Newfield Production Company 1401 17th Street Suite 1000 city Denver state Co zip 80202	Signature: 7 Title: Engi	neering Tebh.

(5/2000)

RECEIVED SEP 2 0 2004

OPERATOR CHANGE WORKSHEET

ROUTING
1. GLH
2. CDW
3. FILE

Change of Operator (Well Sold)

Designation of Agent/Operator

X Operator Name Change

Merger

	9/1/2004
TO: (New Oper	ator):
N2695-Newfield	Production Company
Route 3 B	ox 3630
Myton, U	Γ 84052
Phone: 1-(435) 64	16-3721
Unit:	JONAH (GREEN RIVER)
	N2695-Newfield Route 3 B Myton, U' Phone: 1-(435) 64

WELL(S) NAME	01 11			API NO	ENTITY		WELL	WELL
	01 11			API NO			WELL	WELL
MONTED 40 11	11	090S	140E		INO	TYPE	TYPE	STATUS
MON FED 42-1J			LOOF	4301331404		Federal	WI	A
MON FED 43-11J		090S	160E	4301331002	11492	Federal	WI	A
WALTON FED 34-11	11	090S	160E	4301331003	11492	Federal	WI	A
MON FED 23-11J	11	090S	160E	4301331369	11492	Federal	WI	A
MON FED 14-11J	11	090S	160E	4301331374	11492	Federal	WI	A
MON FED 32-11J	11	090S	160E	4301331386	11492	Federal	WI	A
MON FED 41-15	15	090S	160E	4301331367	11492	Federal	WI	Α
MON FED 32-15J	15	090S	160E	4301331368	11492	Federal	WI	A
MON FED 23-15	15	090S	160E	4301331373	11492	Federal	WI	Α
MON FED 13-5	05	090S	170E	4301331370	11492	Federal	WI	A
MON FED 24-5	05	090S	170E	4301331375	11492	Federal	WI	Α
MONUMENT FED 23-5J	05	090S	170E	4301331383	11492	Federal	OW	P
MON FED 22-5	05	090S	170E	4301331384	11492	Federal	WI	A
MONUMENT FED 14-5	05	090S	170E	4301331385	11492	Federal	OW	P
ALLEN FED 31-6	06	090S	170E	4301331195	11492	Federal	WI	A
MONUMENT 33-6	06	090S	170E	4301331361	11492	Federal	WI	Α
MON FED 11-6	06	090S	170E	4301331362	11492	Federal	WI	A
MON FED 24-6	06	090S	170E	4301331363	11492	Federal	WI	A
MON FED 42-6	06	090S	170E	4301331364	11492	Federal	WI	Α
GETTY 7C	07	090S	170E	4301330961	11492	Federal	ow	P
							-	

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the FORMER operator on: 9/15/2004

2. (R649-8-10) Sundry or legal documentation was received from the NEW operator on: 9/15/2004

3. The new company was checked on the Department of Commerce, Division of Corporations Database on:

on: 2/23/2005

4. Is the new operator registered in the State of Utah:5. If NO, the operator was contacted contacted on:

YES Business Number:

755627-0143

Newfield_Jonah GR 3_FORM_4B.xls 3/7/2005

6a. (R649-9-2)Waste Management Plan has been received on:	IN PLACE
6b. Inspections of LA PA state/fee well sites complete on:	waived
 Federal and Indian Lease Wells: The BLM and of operator change for all wells listed on Federal or Indian. 	or the BIA has approved the merger, name change, leases on: BLM BIA
8. Federal and Indian Units:	
The BLM or BIA has approved the successor of unit oper	rator for wells listed on: n/a
 Federal and Indian Communization Agreeme The BLM or BIA has approved the operator for all wells 	
10. Underground Injection Control ("UIC") T Inject, for the enhanced/secondary recovery unit/project for	The Division has approved UIC Form 5, Transfer of Authority to r the water disposal well(s) listed on: 2/23/2005
DATA ENTRY:	
1. Changes entered in the Oil and Gas Database on:	2/28/2005
2. Changes have been entered on the Monthly Operator Cha	ange Spread Sheet on: 2/28/2005
3. Bond information entered in RBDMS on:	2/28/2005
4. Fee/State wells attached to bond in RBDMS on:	2/28/2005
5. Injection Projects to new operator in RBDMS on:	2/28/2005
6. Receipt of Acceptance of Drilling Procedures for APD/New	v on: waived
FEDERAL WELL(S) BOND VERIFICATION:	
1. Federal well(s) covered by Bond Number:	<u>UT 0056</u>
INDIAN WELL(S) BOND VERIFICATION: 1. Indian well(s) covered by Bond Number:	61BSBDH2912
FEE & STATE WELL(S) BOND VERIFICATIO 1. (R649-3-1) The NEW operator of any fee well(s) listed cov	
2. The FORMER operator has requested a release of liability to The Division sent response by letter on:	from their bond on:n/a* n/a
LEASE INTEREST OWNER NOTIFICATION:	
3. (R649-2-10) The FORMER operator of the fee wells has be of their responsibility to notify all interest owners of this characteristics.	
COMMENTS:	
*Bond rider changed operator name from Inland Production Co	mpany to Newfield Production Company - received 2/23/05

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES 5. LEASE DESIGNATION AND SERIAL NUMBER: DIVISION OF OIL, GAS AND MINING UTU096550 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: SUNDRY NOTICES AND REPORTS ON WELLS 7. UNIT or CA AGREEMENT NAME: not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, JONAH UNIT to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. 8. WELL NAME and NUMBER: 1. TYPE OF WELL: GAS WELL Injection well OIL WELL OTHER **BALCRON MONUMENT FED 23-11** 9. API NUMBER 2. NAME OF OPERATOR: 4301331369 Newfield Production Company 10. FIELD AND POOL, OR WILDCAT: PHONE NUMBER 3. ADDRESS OF OPERATOR: Monument Butte ZIP 84052 435.646.3721 STATE UT CITY Myton Route 3 Box 3630 4. LOCATION OF WELL: COUNTY: Duchesne FOOTAGES AT SURFACE: 1787 FSL 2147 FWL Utah STATE: OTR/OTR. SECTION. TOWNSHIP, RANGE, MERIDIAN: NE/SW, 11, T9S, R16E CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA TYPE OF ACTION **SubDate** TYPE OF ACTION TYPE OF SUBMISSION REPERFORATE CURRENT FORMATION DEEPEN ACIDIZE ■ NOTICE OF INTENT SIDETRACK TO REPAIR WELL FRACTURE TREAT ALTER CASING (Submit in Duplicate) TEMPORARITLY ABANDON NEW CONSTRUCTION CASING REPAIR Approximate date work will TUBING REPAIR OPERATOR CHANGE CHANGE TO PREVIOUS PLANS VENT OR FLAIR PLUG AND ABANDON CHANGE TUBING WATER DISPOSAL PLUG BACK CHANGE WELL NAME X SUBSEQUENT REPORT (Submit Original Form Only) WATER SHUT-OFF PRODUCTION (START/STOP) CHANGE WELL STATUS Date of Work Completion: X OTHER: - 5 Year MIT RECLAMATION OF WELL SITE COMMINGLE PRODUCING FORMATIONS 06/06/2005 RECOMPLETE - DIFFERENT FORMATION CONVERT WELL TYPE 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. On 6-6-05 Dennis Ingram with the State of Utah DOGM was contacted concerning the MIT on the above listed well. Permission was given at that time to perform the test on 6-6-05. On 6-6-05the csg was pressured up to 1590 psig and charted for 30 minutes with 0 psi pressure loss. The well was injecting during the test. The tbg pressure was 1980 psig during the test. There was not a State representative available to witness the test. API# 43-013-31369. Accepted by the Utah Division of Oil, Gas and Mining

COPY SENT TO OPERATOR

initials

NAME (PLEASE PRINT) Kathy Chapman

SIGNATURE

Kathy Chapman

TITLE Office Manager

DATE 06/09/2005

(This space for State use only)

RECEIVED
JUN 1 0 2005

Mechanical Integrity Test Casing or Annulus Pressure Test


Inland Production Company

Rt. 3 Box 3630 Myton, UT 84052 435-646-3721

am om

Test Conducted by:	Ti) Harm		Time <u>/.'30</u>
Well: Bakron monument	Fed. 25-11J.	9-/6 Field: Jo	nah unit
Well Location: we/sw)	1795 RIGE	API No:	
	Time	Casing Pressure	
	0 min	1590	psig
	5	1590	psig
	10	1590	psig
	15	1590	psig
	20	1590	psig
	25	1590	psig
	30 min	1590	psig
	35		psig
	40		psig
	45		psig
	50		psig
	55		psig
	60 min		psig
Tubing	pressure: _	1980	psig
Re	sult:	gass F	ail

Signature of Person Conducting Test: 40 Shuak



	SIAIE OF UI			
	DIVISION OF OIL, GA			5. LEASE DESIGNATION AND SERIAL NUMBER: UTU096550
SUNDRY	WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME;		
not use this form for proposals to drill ne to drill horizontal lat	7. UNIT OF CA AGREEMENT NAME: JONAH UNIT			
1. TYPE OF WELL:				8. WELL NAME and NUMBER:
OIL WELL	GAS WELL OTH	ER Injection well		BALCRON MONUMENT FED 23-11
2. NAME OF OPERATOR:				9. API NUMBER:
Newfield Production Company	<u> </u>			4301331369
3. ADDRESS OF OPERATOR:			PHONE NUMBER	10. FIELD AND POOL, OR WILDCAT:
Route 3 Box 3630 cm	ry Myton STATE	UT ZIP 84052	435.646.3721	Monument Butte
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 1787 FSL 2 OTR/OTR, SECTION, TOWNSHIP, RANGE.		E		COUNTY: Duchesne STATE: Utah
11. CHECK APPROL	PRIATE BOXES TO IND	DICATE NATURE	OF NOTICE, REPO	RT, OR OTHER DATA
	•	TYPE OF ACTIO	N SubDate	
TYPE OF SUBMISSION		T	YPE OF ACTION	
	ACIDIZE	DEEPEN		REPERFORATE CURRENT FORMATION
■ NOTICE OF INTENT		=		
(Submit in Duplicate)	ALTER CASING	FRACTURE	TREAT	SIDETRACK TO REPAIR WELL
Approximate date work will	L CASING REPAIR	NEW CONS	TRUCTION	TEMPORARITLY ABANDON
	CHANGE TO PREVIOUS PLANS	OPERATOR OPERATOR	CHANGE	TUBING REPAIR
-	CHANGE TUBING	PLUG AND	ABANDON	VENT OR FLAIR
X SUBSEQUENT REPORT	CHANGE WELL NAME	PLUG BAC		WATER DISPOSAL
(Submit Original Form Only)		=		
Date of Work Completion:	CHANGE WELL STATUS	=	ON (START/STOP)	WATER SHUT-OFF
•	COMMINGLE PRODUCING FORM	ATIONS RECLAMA	TION OF WELL SITE	OTHER: -
08/24/2005	CONVERT WELL TYPE	X RECOMPLE	ETE - DIFFERENT FORMATION	
12. DESCRIBE PROPOSED OR CO	MPLETED OPERATIONS. Clear	rly show all pertinent detai	ils including dates, depths, vo	lumes, etc.
The subject well was recomple CP2 sds @ 5628-5637; PB11 shots. On 9-19-05 Dennis Ingr Permission was given at that ti 30 minutes with no pressure lower was not a State representative	sds @ 4444-4452', GB6 sds am with the State of Utah D0 ime to perform the test on 9- oss. The well was not injectir	6 @ 4212-4234, GB2 OGM was contacted of 23-05. On 9-23-05 thing during the test. Th	sds @ 4062-4068' all wi concerning the MIT on the ne csg was pressured up	ith 4 JSPF for a total of 232 he above listed well. o to 1320 psig and charted for
COPY SENT TO OPERATE Date: 10-12-02 Indicas: Compo		Utah	oted by the Division of s and Mining	
NAME (PLEASE PRINT) Kathy Chapma	n		TITLE Office Manager	

(This space for State use only)

RECEIVED OCT 0 / 2005

DATE__10/03/2005


Mechanical Integrity Test Casing or Annulus Pressure Test

Inland Production Company Rt. 3 Box 3630 Myton, UT 84052 435-646-3721

Test Conducted by: Michael Hullings	Date <u>9</u> / 23 /	<u>05</u> Time <u>/0:00</u>	@ pm
Others Present:			7
Well: Monument Fed. 23-111-9-16	Field:		
Well Location: NE/SW, Sec. 11, T95, R16E	API No:	43-013-31369	3

<u>Time</u>	Casing Pressure	
0 min	1320	psig
5	1320	psig
10	1320	psig
15	1320	psig-
20	1320	psig
25	1320	psig
30 min	1320	psig
35	•	psig
40		psig
45		psig
50		psig
55		psig
60 min		psig
Tubing pressure: _	1000	psig
Result:	Pass F	ail

Signature of Witness:	
Signature of Person Conducting Test:	Michael Auther



STATE OF UTAH DIVISION OF OIL GAS AND MINING

INJECTION WELL - PRESSURE TEST

Well Name: BF 23-11-9-16 Ott/Ott: NE/SW Section: // Township: 95 Range: 16/E Lease: State Fee Federal 4740945 Sindian Date: 5/19/10
Initial Conditions: Tubing - Rate: Pressure: 1370 psi Casing/Tubing Annulus - Pressure: 1070 psi
Conditions During Test: Time (Minutes) Annulus Pressure Tubing Pressure 0 1070 1320 10 1070 1320 15 1070 1320 20 1070 1320 25 1070 1320 30 1070 1320 Results: Pass/Fail 1070 1320
Conditions After Test: Tubing Pressure:

STATE OF UTAH

	5. LEASE DESIGNATION AND SERIAL NUMBER: USA UTU-096550				
SUNDRY	NOTICES A	ND REPO	ORTS ON	WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
Do not use this form for proposals to dr wells, or to drill horizont	ill new wells, significantly de al laterals. Use APPLICATION	epen existing wells b	elow current bottom-	hole depth, reenter plugged	7. UNIT OF CA AGREEMENT NAME: GMBU
I. TYPE OF WELL: OIL WELL		OTHER			8. WELL NAME and NUMBER: BALCRON MONUMENT FED 23-11
2. NAME OF OPERATOR:	·				9. API NUMBER:
NEWFIELD PRODUCTION COM	IPANY				4301331369
3. ADDRESS OF OPERATOR:				PHONE NUMBER	10. FIELD AND POOL, OR WILDCAT:
Route 3 Box 3630	CITY Myton	STATE UT	ZIP 84052	435.646.3721	GREATER MB UNIT
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 1787 FSL 2	2147 FWL				COUNTY: DUCHESNE
OTR/OTR. SECTION. TOWNSHIP. RANGE.	MERIDIAN: NESW, 11,	T9S, R16E			STATE: UT
CHECK APPROL	PRIATE BOXES T	O INDICAT	E NATURE (OF NOTICE, REP	ORT, OR OTHER DATA
TYPE OF SUBMISSION			TY	PE OF ACTION	
	ACIDIZE		DEEPEN		REPERFORATE CURRENT FORMATION
NOTICE OF INTENT (Submit in Duplicate)	ALTER CASING		FRACTURE T	DE AT	=
			=		SIDETRACK TO REPAIR WELL
Approximate date work will	CASING REPAIR		NEW CONST		TEMPORARITLY ABANDON
	CHANGE TO PREVIOU	S PLANS	OPERATOR (X TUBING REPAIR
	CHANGE TUBING		PLUG AND A	ABANDON	VENT OR FLAIR
SUBSEOUENT REPORT (Submit Original Form Only)	CHANGE WELL NAME		PLUG BACK		WATER DISPOSAL
Date of Work Completion:	CHANGE WELL STATE	JS	PRODUCTIO	N (START/STOP)	WATER SHUT-OFF
Date of work completion.	COMMINGLE PRODUC	ING FORMATIONS	RECLAMATI	ON OF WELL SITE	X OTHER: - MIT
05/19/2010	CONVERT WELL TYPE		RECOMPLET	E - DIFFERENT FORMATION	
12. DESCRIBE PROPOSED OR CO	MPLETED OPERATION	NS. Clearly show a	all pertinent details	s including dates, depths,	volumes, etc.
The above subject well had	d workover procedure	es performed (to	ubing leak), att	ached is a daily stati	us report.
at that time to perform the	test on 05-18-10. Or as not injecting during	n 05-19-10 the o	csg was pressi	red up to 1070 psig	ve listed well. Permission was given and charted for 30 minute with no the test. There was a State
API# 43-013-31369					
				······································	
NAME (PLEASE PRINT) Lucy Chavez-N	laupoto —		*	TITLE Administrative As	sistant
MANNE (FLEASE FRINT) Due; Charles		\		TILE TRANSPORTER	
SIGNATURE Sur	by Nog E	4	I	DATE 05/21/2010	


(This space for State use only)

RECEIVED
JUN 0 3 2010

Mechanical Integrity Test Casing or Annulus Pressure Test

Newfield Production Company Rt. 3 Box 3630 Myton, UT 84052 435-646-3721

Witness: Test Conducted by: <u>NEWF;ELD ExPLOR</u> Others Present:	Date_ <u>5_/19_/10</u> Time <u>4:3(,</u> am_p
Well:Balcron Federal 23-11J-9-16	Field: MOUMENT
Well Location: NE/SW, Sec.11, T95, R16	E API No:43-013-31369
<u>Time</u>	Casing Pressure
0 min	10 10 psig
5	1070 psig
10	1010 psig
15	1070 psig
20	1070 psig
25	10 () psig
30 min	1010 psig
35	psig
40	psig
45 <u> </u>	psig
50	psig
55	psig
60 min	psig
Tubing pressure:	13.20 psig
Result:	Pass Fail
Signature of Witness:	De la companya della companya della companya de la companya della
Signature of Person Conductin	a Vest: Lt. /// https/



Daily Activity Report

Format For Sundry BLCRN MON 23-11-9-16 3/1/2010 To 7/30/2010

5/12/2010 Day: 1

Tubing Leak

WWS #5 on 5/12/2010 - MIRU Western rig #5. Rig up to flow well back overnight. - MIRU Western rig #5. SITP @ 1500 psi. Bleed tbg off to tank. Flow rate of 200 BPH. Line up water trucks & flowback hand. Leave well flowing overnight.

Daily Cost: \$0

Cumulative Cost: \$15,393

5/13/2010 Day: 2

Tubing Leak

WWS #5 on 5/13/2010 - Changed packers. LD 1 jt W/ corrosion hole. Tested tbg. Set & test packer. RDMOSU. - Hauled out approx. 2600 BW through night. Still flowing @ 1 BPM. ND wellhead & release pkr @ 4017'. NU BOP. RU HO trk & circulate down tbg W/ 60 BW @ 250°F. Try dropping SV dn tbg--flowing too hard. TOH W/ tbg. Found corrosion hole in jt #41. TOH W/ remainder of tbg string-LD packer. . MU & TIH W/ new Weatherford 5 1/2" Arrowset 1-X packer (W/ wicker slips & W.L. re-entry guide), new 2 7/8 SN and 128 jts 2 7/8 8rd 6.5# J-55 tbg. Tested tbg in hole in 3 segments. Final test held 3000 psi solid for 30 minutes. Retrieve standing valve W/ overshot on sandline. ND BOP & land tbg on flange. Mix 15 gals Multi-Chem C-6031 & 5 gals B-8850 in 70 bbls fresh water. Pump dn annulus @ 90°F. PU on tbg & set pkr W/ SN @ 4013', CE @ 4017' & EOT @ 4022'. Land tbg W/ 15,000# tension. NU wellhead. Pressure test annulus & pkr to 1500 psi. Holds solid for 1 hour. RDMOSU. - Perform MIT.

Daily Cost: \$0

Cumulative Cost: \$26,343

5/20/2010 Day: 3

Tubing Leak

Rigless on 5/20/2010 - Workover MIT - On 5/18/2010 Dennis Ingram with the State of Utah DOGM was contacted concerning the MIT on the above listed well (Balcron Monument 23-11-9-16). Permission was given at that time to perform the test on 5/18/2010. On5/19/2010 the csg was pressured up to 1070 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test . The tbg pressure was 1320 psig during the test. There was a State representative available to witness the test. (Dennis Ingram) API # 43-013-31369

Finalized

Daily Cost: \$0

Cumulative Cost: \$26,643

Pertinent Files: Go to File List

Sundry Number: 62862 API Well Number: 43013313690000

			FORM 9
	STATE OF UTAH		FORM 9
	DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MININ		5.LEASE DESIGNATION AND SERIAL NUMBER: UTU-096550
SUNDF	RY NOTICES AND REPORTS OF	N WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
	oposals to drill new wells, significantly de reenter plugged wells, or to drill horizontan for such proposals.		7.UNIT or CA AGREEMENT NAME: GMBU (GRRV)
1. TYPE OF WELL Water Injection Well			8. WELL NAME and NUMBER: MON FED 23-11J
2. NAME OF OPERATOR: NEWFIELD PRODUCTION CO	OMPANY		9. API NUMBER: 43013313690000
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT		HONE NUMBER: Ext	9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1787 FSL 2147 FWL			COUNTY: DUCHESNE
QTR/QTR, SECTION, TOWNS	HIP, RANGE, MERIDIAN: 11 Township: 09.0S Range: 16.0E Meridiai	n: S	STATE: UTAH
11. CHEC	K APPROPRIATE BOXES TO INDICATE	NATURE OF NOTICE, REPOF	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
Approximate date work will start:	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION
4/23/2015		1	
	OPERATOR CHANGE	PLUG AND ABANDON	LI PLUG BACK
SPUD REPORT Date of Spud:	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	L TEMPORARY ABANDON
_	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL
DRILLING REPORT Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
	☐ WILDCAT WELL DETERMINATION ✓	OTHER	OTHER: 5 YR MIT
On 04/20/2015 F contacted conce 04/23/2015 the cas 30 minutes with no test. The tubing pr State representa	COMPLETED OPERATIONS. Clearly show all Richard Powell with the State of rning the 5 Year MIT on the abing was pressured up to 1109 pressure loss. The well was nessure was 1326 psig during the ative available to witness the te	of Utah DOGM was bove listed well. On psig and charted for ot injecting during the he test. There was a est - Richard Powell.	
NAME (PLEASE PRINT) Lucy Chavez-Naupoto	PHONE NUMBER 435 646-4874	TITLE Water Services Technician	
SIGNATURE N/A		DATE 4/24/2015	

Sundry Number: 62862 API Well Number: 43013313690000

Mechanical Integrity Test Casing or Annulus Pressure Test

Newfield Production Company Rt. 3 Box 3630 Myton, UT 84052 435-646-3721

Witness: Richard Powell	Date 4 / 23/ 15	Time 9:15	(am) pm
Test Conducted by: Hat Richius			
Others Present:			
•			
Well: Bateron Mon. Federal 23-11J.q	-16 Field: Meno	new sotte	
Well Location: NE/SW Sec. 11, T95, RIGE	API No: 43-0	113-31369	

Time	Casing Pressure	
0 min	1107.0	psig
5	1107.2	psig
10	1108.0	psig
15	1107.8	psig
20	1108.0	psig
25	1108.6	psig
30 min	1109.0	psig
35		psig
40		psig
45		psi
50		psi
55		psi
60 min		psi
Tubing pressure:	1326	psię


Result:

Pass

Fail

Signature of Witness:

Signature of Person Conducting Test:




Balcron Monument Fed 23-11

Spud Date: 8/30/93 Put on Production: 10/21/93 Put on Injection: 10/29/94

GL: 5621' KB: 5631'

Injection Wellbore Diagram Initial Production: 110 BOPD, 165 MCFD, 20 BWPD



1787 FSL 2147 FWL NESW Section 11-T9S-R16E Duchesne Co, Utah API #43-013-31369, Lease #U-096550

TW 08 09-10

NEWFIELD


Schematic

43-013-31369

Well Name: Blcrn Mon 23-11-9-16

Surface Legal Location State/Province **GMBU CTB5** 11-9S-16E 43013313690000 500151814 Utah Duchesne original KB Elevation (ft Total Deoth AT (TVD) (flkB) Spud Date Rig Release Date On Production Date PBTD (All) (fKB Original Hole - 5,683.1 10/21/1993 5,631 5.621

Most Recent Job Job Start Dat rmary Job Type Secondary Job Type Job End Date Job Category Testing N/A 4/23/2015 4/23/2015





Newfield Wellbore Diagram Data Blcrn Mon 23-11-9-16

Surface Legal Location			***************************************		API/UWI		Lease	
11-9S-16E County State/Province					43013313690000 Basin		Field Name	
Duchesne		Utah	,				GMBU CTB5	
Vell Start Date 8/30/1993	8/30/1993 Spud Date			Final Rig Release Date		On Production Date 10/21/1993		
riginal KB Elevation (ft) Ground Elevation (ft) Total Depth (ftKB)			Total Depth All (TVD) (ftKB)		PBTD (All) (ftKB)			
5,631	5,621	<u> </u>	N.	5,750.0			Original Hole - 5,68	3.1
Casing Strings Csg Des		Run D	ate	OD (in)	ID (in)	Wt/Len (lb/ft)	Grade	Set Depth (ftKB)
Surface		8/31/1993		8 5/8	8.097	24.00		27
Production		9/23/1993		5 1/2	4.950	15.50	K-55	5,73
Cement								John Harley
String: Surface, 277ftKB 8/	31/1993		11 50		Mark the second	3		
ementing Company Dowell Schlumberger					Top Depth (ffK8) 10.0	Bottom Depth (ftK8) 278.0	Full Return?	Vol Cement Ret (bbl)
uid Description		2 SEED ON THE PER 100 STATE			Fluid Type	Amount (sacks)	Class	Estimated Top (ftKB)
OOWELL CMT W/150 SXS C			+ 1/4#/SX	CELLOFLAKES	Lead	150	[G	10
string: Production, 5,731ftk ementing Company	(B 9/23/19	93			Top Depth (ftKB)	Bottom Depth (ftKB)	Full Return?	Voi Cement Ret (bbl)
lalliburton Energy Services					2,510.0	5,750.0		
u.d Description					Fluid Type Lead	Amount (sacks)	Class HIFILL	Estimated Top (ftKB) 2,510
luid Description					Fluid Type	Amount (sacks)	Class	Estimated Top (ftKB)
ubing Strings			na na an haippeasann an an		Tail	350	50/50 POZ	4,130
ubing Description			THE ACTION IS NOT THE OWNER.	**************************************	Run Date		Set Depth (ftKB)	
ubing Item Des	Jts	OD (in)	10 (in)	Wt (lb/ft)	8/24/ Grade		Top (ftKB)	4,021 Btm (ftKB)
ubing	128	2 7/8	2.441	6.50		Len (ft) 4,002.91	10.0	4,012
ump Seating Nipple	1	2 7/8	2.441			1.10	4,012.9	4,014
acker	1	2 7/8	1.995			7.07	4,014.0	4,021
						0.50	4,021.1	4,021
	1	2 7/8	1.995			0.00	7,021.1	
Vireline Guide Rod Strings	1	2 7/8	1.995					
Vireline Guide	1	2 7/8	1.995		Run Date		Set Depth (ftkB)	
Vireline Guide Rod Strings	Jts	2 7/8		Wt (lb/ft)	Run Date Grade	Len (ft)		Bim (fiKB)
Vireline Guide Rod Strings od Description Item Des	Jts			Wt (lb/ft)			Set Depth (ftKB)	
Vireline Guide Rod Strings od Description	Jts		in)	Wt (lb/ft) Btm (flKB)	Grade	Len (ft)	Set Depth (ftKB) Top (ftKB)	
Vireline Guide Rod Strings od Description Item Des Perforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori		OD (i	in)				Set Depth (ftKB)	Bim (ftKB)
Vireline Guide Rod Strings and Description Item Des Perforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori Hole	iginal	OD (i	KB) 4,062	Btm (ffKB) 4,068	Grade Shot Dens (shots/ft)	Len (ft) Phasing (*)	Set Depth (ftKB) Top (ftKB)	Btm (ftKB) Date 8/22/2005
Vireline Guide Rod Strings and Description Item Des Perforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori	iginal	OD (i	in)	Btm (ffKB)	Grade Shot Dens (shots/ft)	Len (ft) Phasing (°)	Set Depth (ftKB) Top (ftKB)	Bim (ftKB) Date
Vireline Guide Rod Strings and Description Item Des Perforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori	iginal iginal	OD (i	KB) 4,062	Btm (ffKB) 4,068	Grade Shot Dens (shots/ft)	Len (ft) Phasing (*)	Set Depth (ftKB) Top (ftKB)	Btm (ftKB) Date 8/22/2005
Vireline Guide Rod Strings od Description Item Des Perforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori	iginal iginal iginal	OD (i	KB) 4,062 4,152	Btm (ffKB) 4,068 4,158	Grade Shot Dens (shots/ft) 4	Phasing (*) 90	Set Depth (ftKB) Top (ftKB)	Date 8/22/2005
Vireline Guide Od Strings od Description Item Des erforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori	iginal iginal iginal	OD (i	KB) 4,062 4,152 4,212	Btm (ffKB) 4,068 4,158 4,224	Grade Shot Dens (shots/ft) 4	Phasing (*) 90 90	Set Depth (ftKB) Top (ftKB)	Btm (ftKB) Date 8/22/2005 8/22/2005
Vireline Guide Idea Strings Idea Description Item Des iginal iginal iginal	OD (i	KB) 4,062 4,152 4,212 4,228	Btm (ffKB) 4,068 4,158 4,224 4,234	Grade Shot Dens (shots/ft) 4 4 4	Phasing (*) 90 90 90 90	Set Depth (ftKB) Top (ftKB)	Date 8/22/2005 8/22/2005 8/22/2005 8/22/2005	
/ireline Guide od Strings ad Descripton Item Des erforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori Hole 5 PB11, Original Hole 3	iginal iginal iginal	OD (i	4,062 4,152 4,212 4,228 4,444 4,710 4,840	Btm (ffKB) 4,068 4,158 4,224 4,234 4,452	Grade Shot Dens (shots/ft) 4 4 4	Phasing (*) 90 90 90 90 90	Set Depth (ftKB) Top (ftKB)	Date 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005
/ireline Guide od Strings ad Description Item Des erforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 5 PB11, Original Hole 3 2 2	iginal iginal iginal	OD (i	(KB) 4,062 4,152 4,212 4,228 4,444 4,710 4,840 4,844	Btm (ftKB) 4,068 4,158 4,224 4,234 4,452 4,717 4,840 4,844	Grade Shot Dens (shots/ft) 4 4 4 4 2	Phasing (*) 90 90 90 90 90 180	Set Depth (ftKB) Top (ftKB)	Date 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 10/1/1993
/ireline Guide od Strings ad Description Item Des erforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 5 PB11, Original Hole 3 2 2 2 2	iginal iginal iginal	OD (i	(KB) 4,062 4,152 4,212 4,228 4,444 4,710 4,840 4,844 4,848	Btm (ftKB) 4,068 4,158 4,224 4,234 4,452 4,717 4,840 4,844 4,848	Grade Shot Dens (shots/ft) 4 4 4 4 2	Phasing (*) 90 90 90 90 90 180 360	Set Depth (ftKB) Top (ftKB)	Date 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 10/1/1993 9/30/1993
//reline Guide od Strings ad Description Item Des erforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 5 PB11, Original Hole 3 2 2 2 2 2	iginal iginal iginal	OD (i	(KB) 4,062 4,152 4,212 4,228 4,444 4,710 4,840 4,844 4,848 4,850	Btm (ftKB) 4,068 4,158 4,224 4,234 4,452 4,717 4,840 4,844 4,848 4,850	Shot Dens (shots/ft) 4 4 4 4 1 1	Phasing (*) 90 90 90 90 180 360 360 360 360	Set Depth (ftKB) Top (ftKB)	Date 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 10/1/1993 9/30/1993 9/30/1993 9/30/1993
/ireline Guide od Strings ad Description Item Des erforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 5 PB11, Original Hole 3 2 2 2 2 2 2	iginal iginal iginal	OD (i	4,062 4,152 4,212 4,228 4,444 4,710 4,840 4,848 4,850 4,858	Btm (ftKB) 4,068 4,158 4,224 4,234 4,452 4,717 4,840 4,844 4,848 4,850 4,858	Shot Dens (shots/ft) 4 4 4 4 1 1	Phasing (*) 90 90 90 90 180 360 360 360 360 360 360	Set Depth (ftKB) Top (ftKB)	Date 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 10/1/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993
Vireline Guide Jod Strings Jod Description Item Des erforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 5 PB11, Original Hole 7 PB11, Original Hole 8 PB11, Original Hole 9 PB11, Original Hole 10 PB11, Original Hole 11 PB11	iginal iginal iginal	OD (i	4,062 4,152 4,212 4,228 4,444 4,710 4,840 4,848 4,850 4,858 4,864	Btm (ffKB) 4,068 4,158 4,224 4,234 4,452 4,717 4,840 4,844 4,848 4,850 4,858 4,864	Shot Dens (shots/ft) 4 4 4 4 1 1	Phasing (*) 90 90 90 90 180 360 360 360 360 360 360	Set Depth (ftKB) Top (ftKB)	Btm (ftKB) Date 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 10/1/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993
/ireline Guide od Strings ad Description Item Des erforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 5 PB11, Original Hole 3 2 2 2 2 2 2 2 2 2 2 2 2	iginal iginal iginal	OD (i	4,062 4,152 4,212 4,228 4,444 4,710 4,840 4,848 4,850 4,858 4,864 4,965	Btm (flKB) 4,068 4,158 4,224 4,234 4,452 4,717 4,840 4,848 4,850 4,858 4,864 4,965	Shot Dens (shots/ft) 4 4 4 4 1 1	Phasing (*) 90 90 90 90 180 360 360 360 360 360 360 360 3	Set Depth (ftKB) Top (ftKB)	Btm (ftKB) Date 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 10/1/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993
Vireline Guide od Strings od Description Item Des erforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 7 GB2/GB4/GB6, Ori Hole 8 GB2/GB4/GB6, Ori Hole 9 B11, Original Hole 3 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	iginal iginal iginal	OD (i	(KB) 4,062 4,152 4,212 4,228 4,444 4,710 4,840 4,848 4,850 4,858 4,864 4,965 4,968	Btm (flKB) 4,068 4,158 4,224 4,234 4,452 4,717 4,840 4,844 4,850 4,858 4,864 4,965 4,968	Shot Dens (shots/ft) 4 4 4 4 1 1	Phasing (*) 90 90 90 90 180 360 360 360 360 360 360 360 3	Set Depth (ftKB) Top (ftKB)	Date 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 10/1/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993
Vireline Guide od Strings od Description Item Des erforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 7 GB2/GB4/GB6, Ori Hole 8 GB2/GB4/GB6, Ori Hole 9 PB11, Original Hole 2 CCC 2 CCCC 2 CCCCC 2 CCCCCCCCCCCCCCC	iginal iginal iginal	OD (i	(KB) 4,062 4,152 4,212 4,212 4,228 4,444 4,710 4,840 4,848 4,850 4,858 4,864 4,965 4,968 4,984	Btm (ffKB) 4,068 4,158 4,224 4,234 4,452 4,717 4,840 4,844 4,848 4,850 4,858 4,864 4,965 4,968 4,984	Shot Dens (shots/ft) 4 4 4 4 1 1	Phasing (*) 90 90 90 90 180 360 360 360 360 360 360 360 3	Set Depth (ftKB) Top (ftKB)	Date 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 10/1/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993
Vireline Guide Lod Strings od Description Item Des Perforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 7 GB2/GB4/GB6, Ori Hole 8 GB2/GB4/GB6, Ori Hole 9 B11, Original Hole 2 C C C C C C C C C C C C C C C C C C	iginal iginal iginal	OD (i	(KB) 4,062 4,152 4,212 4,212 4,228 4,444 4,710 4,848 4,850 4,858 4,864 4,965 4,968 4,988	Btm (ffKB) 4,068 4,158 4,224 4,234 4,452 4,717 4,840 4,844 4,850 4,858 4,864 4,965 4,968 4,968 4,988	Shot Dens (shots/ft) 4 4 4 4 1 1 1 1 1 1 1	Phasing (*) 90 90 90 90 180 360 360 360 360 360 360 360 3	Set Depth (ftKB) Top (ftKB)	Date 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 10/1/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993
Vireline Guide Rod Strings od Description Item Des Verforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 7 Hole 9 PB11, Original Hole 7 PB11, Original Hole 7 PB11, Original Hole 8 PB11, Original Hole 9 PB11, Original Hole	iginal iginal iginal	OD (i	(KB) 4,062 4,152 4,212 4,212 4,228 4,444 4,710 4,840 4,848 4,850 4,858 4,864 4,965 4,968 4,984	Btm (ffKB) 4,068 4,158 4,224 4,234 4,452 4,717 4,840 4,844 4,848 4,850 4,858 4,864 4,965 4,968 4,984	Shot Dens (shots/ft) 4 4 4 4 1 1 1 1 1 1 1	Phasing (*) 90 90 90 90 180 360 360 360 360 360 360 360 3	Set Depth (ftKB) Top (ftKB)	Date 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 10/1/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993
Vireline Guide Lod Strings od Description Item Des Perforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 7 GB2/GB4/GB6, Ori Hole 8 GB2/GB4/GB6, Ori Hole 9 B11, Original Hole 2 C C C C C C C C C C C C C C C C C C	iginal iginal iginal	OD (i	4,062 4,152 4,212 4,212 4,228 4,444 4,710 4,848 4,850 4,858 4,864 4,965 4,968 4,988 4,988 4,992	Btm (fiKB) 4,068 4,158 4,224 4,234 4,452 4,717 4,840 4,844 4,848 4,850 4,868 4,965 4,968 4,984 4,988 4,992	Shot Dens (shots/ft) 4 4 4 4 1 1 1 1 1 1 1	Phasing (*) 90 90 90 90 180 360 360 360 360 360 360 360 3	Set Depth (ftKB) Top (ftKB)	Date 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 10/1/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993
Vireline Guide Rod Strings and Description Item Des Verforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 7 Hole 8 GB2/GB4/GB6, Ori Hole 9 PB11, Original Hole 9 PB11, Original Hole 1 CPB11, Original	iginal iginal iginal	OD (i	4,062 4,152 4,212 4,212 4,228 4,444 4,710 4,840 4,848 4,850 4,858 4,864 4,965 4,968 4,988 4,992 4,994	Btm (fiKB) 4,068 4,158 4,224 4,234 4,452 4,717 4,840 4,844 4,848 4,850 4,858 4,864 4,965 4,968 4,968 4,988 4,992 4,994	Shot Dens (shots/ft) 4 4 4 4 1 1 1 1 1 1 1 1 1	Phasing (*) 90 90 90 90 180 360 360 360 360 360 360 360 3	Set Depth (ftKB) Top (ftKB)	Btm (ftKB) Date 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 10/1/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993
Vireline Guide Rod Strings od Description Item Des Perforation Intervals Stage# Zone 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 6 GB2/GB4/GB6, Ori Hole 5 PB11, Original Hole 3 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	iginal iginal iginal	OD (i	4,062 4,152 4,212 4,228 4,444 4,710 4,840 4,848 4,850 4,858 4,965 4,968 4,988 4,988 4,992 4,994 4,996	Btm (fiKB) 4,068 4,158 4,224 4,234 4,452 4,717 4,840 4,844 4,848 4,850 4,858 4,965 4,968 4,968 4,984 4,988 4,992 4,994 4,996	Grade Shot Dens (shots/ft) 4 4 4 1 1 1 1 1 1 1 1 1 1	Phasing (*) 90 90 90 90 180 360 360 360 360 360 360 360 3	Set Depth (ftKB) Top (ftKB)	Btm (fiKB) Date 8/22/2005 8/22/2005 8/22/2005 8/22/2005 8/22/2005 10/1/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993 9/30/1993

NEWFIELD

Newfield Wellbore Diagram Data Blcrn Mon 23-11-9-16

Stage#	Zone	Top (fiKB)	Btm (ftKB)	Shot Dens (shots/ft)	Phasing (*)	Nom Hole Dia (in)	Date
4 CP1/CP2 Original Hole CP1/CP2, Original Hole		5.579	5,590	4	90		8/22/2005
		5,628	5,637	Company A	90		8/22/2005
Stimulations & T	reatments	and the state of	THE CAMPBELL SELVE		A COLUMN TO A PROPERTY OF THE	1 工工工艺 水湖	的解发,他也是一种成本。"
Stage#	ISIP (psi)	Frac Gradient (psi/ft)	Max Rate (bbi/min)	Max PSI (psi)	Total Clean Vol (bbl)	Total Slurry Vol (bbl)	Vol Recov (bbl)
	1,900		25.2	2,250			
	1,600		35.0	3,000			
I	1.800		21.1	2,510			
	1,600	0.72	14.1	4,344			1.
5	2,200	0.93	14.0	3.589			
3	1,900	0.89	14.1	2,769			
Proppant		A LEDAME	C4 = 1 = 52500			5 14 9 5	STATE OF THE STATE OF
Stage#	Total Prop Vol Pumped (lb)		建 加工	Total Add	Amount		
\ \		Proppant Bulk Sand	57380 lb				
		Proppant Bulk Sand	60200 lb				
		Proppant Bulk Sand	20000 lb				
		Proppant Bulk Sand	13508 lb				
i		Proppant Bulk Sand	14452 lb				
APP F		Proppant Bulk Sand	46326 lb				